
# **ABSOLUTE MAXIMUM RATINGS**

#### (Note 1)

Supply Voltage .....±18V Input Voltages (Note 2) ...... 0.3V Beyond Either Rail Differential Input Current (Note 2) ..... ±25mA Output Short-Circuit Duration (Note 3) ...... Indefinite Storage Temperature Range ..... –65°C to 150°C

| Lead Temperature (Soldering, 10 sec.) |
|---------------------------------------|
| Operating Temperature Range           |
| (Note 4)40°C to 85°C                  |
| Specified Temperature Range           |
| (Note 5)40°C to 85°C                  |
|                                       |

## PACKAGE/ORDER INFORMATION



Consult LTC Marketing for parts specified with wider operating temperature ranges.

## **ELECTRICAL CHARACTERISTICS**

The • denotes the specifications which apply over the full operating temperature range, otherwise specifications are at  $T_A = 25^{\circ}$ C.  $V_S = 3V$ ,  $V_{CM} = V_0 = 1.7V$ ;  $V_S = 5V$ ,  $V_{CM} = V_0 = 2.5V$  unless otherwise noted.

| SYMBOL                              | PARAMETER                            | CONDITIONS (Note 6)                                                                                                                                                                                                            |   | MIN               | ТҮР                     | MAX                  | UNITS          |
|-------------------------------------|--------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---|-------------------|-------------------------|----------------------|----------------|
| V <sub>OS</sub>                     | Input Offset Voltage                 | $ \begin{array}{l} (\text{Note 11}) \\ 0^\circ\text{C} \leq \text{T}_\text{A} \leq 70^\circ\text{C} \\ -40^\circ\text{C} \leq \text{T}_\text{A} \leq 85^\circ\text{C} \end{array} $                                            | • |                   | 35<br>55<br>75          | 100<br>270<br>350    | μV<br>μV<br>μV |
|                                     |                                      | $ \begin{array}{ c c c c c } V_S = 5V, \ V_{CM} = V_S + 0.1V \\ V_S = 5V, \ V_{CM} = V_S - 0.3V, \ 0^\circ C \leq T_A \leq 70^\circ C \\ V_S = 5V, \ V_{CM} = V_S - 0.3V, \ -40^\circ C \leq T_A \leq 85^\circ C \end{array} $ | • |                   | 150<br>180<br>200       | 550<br>750<br>1000   | μV<br>μV<br>μV |
|                                     |                                      | $ \begin{array}{l} V_{S} = \!\!\!\!\!\!\!\!\!\!\!\!\!\!\!\!\!\!\!\!\!\!\!\!\!\!\!\!\!\!\!\!\!\!\!$                                                                                                                             | • |                   | 1.5<br>1.8<br>2.0       | 30<br>45<br>50       | mV<br>mV<br>mV |
| $\frac{\Delta V_{OS}}{\Delta Temp}$ | Average Input Offset Drift (Note 10) |                                                                                                                                                                                                                                | • |                   | 0.40                    | 3                    | μV/°C          |
| I <sub>B</sub>                      | Input Bias Current                   | (Note 11)<br>$0^{\circ}C \le T_A \le 70^{\circ}C$<br>$-40^{\circ}C \le T_A \le 85^{\circ}C$                                                                                                                                    | • |                   | ±2<br>±3<br>±7          | ±20<br>±35<br>±50    | nA<br>nA<br>nA |
|                                     |                                      | $ \begin{array}{l} V_S = 5V,  V_{CM} = V_S + 0.1V \\ V_S = 5V,  V_{CM} = V_S - 0.3V,  0^\circ C \leq T_A \leq 70^\circ C \\ V_S = 5V,  V_{CM} = V_S - 0.3V,  -40^\circ C \leq T_A \leq 85^\circ C \end{array} $                | • |                   | 0.19<br>0.19<br>0.25    | 0.40<br>0.60<br>0.75 | μΑ<br>μΑ<br>μΑ |
|                                     |                                      | $ \begin{array}{l} V_S = 5V,  V_{CM} = -0.1V \\ V_S = 5V,  V_{CM} = 0V,  0^\circ C \leq T_A \leq 70^\circ C \\ V_S = 5V,  V_{CM} = 0V,  -40^\circ C \leq T_A \leq 85^\circ C \end{array} $                                     | • | -5<br>-8.4<br>-10 | -0.41<br>-0.45<br>-0.47 |                      | μΑ<br>μΑ<br>μΑ |



**ELECTRICAL CHARACTERISTICS** The  $\bullet$  denotes the specifications which apply over the full operating temperature range, otherwise specifications are at  $T_A = 25^{\circ}$ C.  $V_S = 3V$ ,  $V_{CM} = V_0 = 1.7V$ ;  $V_S = 5V$ ,  $V_{CM} = V_0 = 2.5V$  unless otherwise noted.

| SYMBOL           | PARAMETER                            | CONDITIONS (Note 6)                                                                                                 | MIN       | ТҮР          | MAX                                            | UNITS                                  |
|------------------|--------------------------------------|---------------------------------------------------------------------------------------------------------------------|-----------|--------------|------------------------------------------------|----------------------------------------|
| I <sub>OS</sub>  | Input Offset Current                 | (Note 11)                                                                                                           |           | 4            | 25                                             | nA                                     |
|                  |                                      | $0^{\circ}C \le T_A \le 70^{\circ}C$<br>-40^{\circ}C \le T_A \le 85^{\circ}C                                        |           | 5<br>8       | 35<br>55                                       | nA<br>nA                               |
|                  |                                      | $V_{\rm S} = 5V, V_{\rm CM} = V_{\rm S} + 0.1V$                                                                     |           | 6            | 30                                             | nA                                     |
|                  |                                      | $V_{S} = 5V, V_{CM} = V_{S} - 0.3V, 0^{\circ}C \le T_{A} \le 70^{\circ}C$                                           |           | 10           | 40                                             | nA                                     |
|                  |                                      | $V_{\rm S} = 5V, V_{\rm CM} = V_{\rm S} - 0.3V, -40^{\circ}{\rm C} \le T_{\rm A} \le 85^{\circ}{\rm C}$             |           | 15           | 65                                             | nA                                     |
|                  |                                      | $V_{S} = 5V, V_{CM} = -0.1V$<br>$V_{S} = 5V, V_{CM} = 0V, 0^{\circ}C \le T_{A} \le 70^{\circ}C$                     |           | 0.1<br>0.1   | 1.6<br>2.0                                     | μA<br>μA                               |
|                  |                                      | $V_{\rm S} = 5V, V_{\rm CM} = 0V, -40^{\circ}{\rm C} \le {\rm T}_{\rm A} \le 85^{\circ}{\rm C}$                     |           | 0.15         | 2.4                                            | μA                                     |
| en               | Input Noise Voltage                  | 0.1Hz to 10Hz (Note 7)                                                                                              |           | 90           |                                                | nV <sub>P-P</sub>                      |
|                  |                                      | $V_{CM} = V_S$<br>$V_{CM} = 0V$                                                                                     |           | 180<br>1600  |                                                | nV <sub>P-P</sub><br>nV <sub>P-P</sub> |
|                  | Input Noise Voltage Density (Note 8) | $f_0 = 10$ Hz                                                                                                       |           | 4.4          |                                                | nV/√Hz                                 |
|                  |                                      | $V_{CM} = V_S$ , $f_0 = 10Hz$                                                                                       |           | 6.6          |                                                | nV/√Hz                                 |
|                  |                                      | $V_{CM} = 0V, f_0 = 10Hz$                                                                                           |           | 19           |                                                | nV/√Hz                                 |
|                  |                                      | $f_0 = 1$ kHz<br>V <sub>CM</sub> = V <sub>S</sub> , $f_0 = 1$ kHz                                                   |           | 3.9<br>5.3   | 5.5                                            | nV/√Hz<br>nV/√Hz                       |
|                  |                                      | $V_{CM} = 0$ , $f_0 = 1$ kHz                                                                                        |           | 9            |                                                | nV/√Hz                                 |
| i <sub>n</sub>   | Input Noise Current Density          | $f_0 = 10Hz$                                                                                                        |           | 1.2          |                                                | pA/√Hz                                 |
|                  |                                      | $f_0 = 1 \text{kHz}$                                                                                                |           | 0.3          |                                                | pA/√Hz                                 |
| V <sub>CM</sub>  | Input Voltage Range                  |                                                                                                                     | -0.1      |              | V <sub>S</sub> + 0.1V<br>V <sub>S</sub> - 0.3V | V<br>V                                 |
| R <sub>IN</sub>  | Input Resistance                     | Common Mode                                                                                                         |           | 2            |                                                | GΩ                                     |
| CIN              | Input Capacitance                    |                                                                                                                     |           | 4.2          |                                                | pF                                     |
| CMRR             | Common Mode Rejection Ratio          |                                                                                                                     | 98<br>92  | 120<br>120   |                                                | dB<br>dB                               |
| PSRR             | Power Supply Rejection Ratio         |                                                                                                                     | 100<br>98 | 125<br>120   |                                                | dB<br>dB                               |
| A <sub>VOL</sub> | Large-Signal Voltage Gain            | $V_{S} = 3V, R_{L} = 10k, V_{0} = 2.5V \text{ to } 0.7V$                                                            | 0.6       | 3<br>2       |                                                | V/μV<br>V/μV                           |
|                  |                                      | $V_{\rm S} = 3V, R_{\rm L} = 2k, V_{\rm O} = 2.2V \text{ to } 0.7V$                                                 | 0.5       | 3            |                                                |                                        |
|                  |                                      | $0^{\circ}C \le T_A \le 70^{\circ}C$                                                                                | 0.4       | 0.9          |                                                | V/µV                                   |
|                  |                                      | $-40^{\circ}\text{C} \le \text{T}_{\text{A}} \le 85^{\circ}\text{C}$                                                | 0.4       | 0.8          |                                                | V/μV                                   |
|                  |                                      | $V_{S} = 3V, R_{L} = 600\Omega, V_{0} = 2.2V \text{ to } 0.7V$<br>$0^{\circ}C \le T_{A} \le 70^{\circ}C$            | 0.20      | 0.43<br>0.40 |                                                | V/μV<br>V/μV                           |
|                  |                                      | $-40^{\circ}C \le T_{A} \le 85^{\circ}C$                                                                            | 0.10      | 0.35         |                                                | V/µV                                   |
|                  |                                      | $V_{\rm S}$ = 5V, R <sub>L</sub> = 10k, V <sub>0</sub> = 4.5V to 0.7V                                               | 1         | 3.8          |                                                | V/µV                                   |
|                  |                                      | $ \begin{array}{c} 0^{\circ}C < T_{A} < 70^{\circ}C \\ -40 < T_{A} < 85^{\circ}C \end{array} $                      |           | 2<br>2       |                                                | V/μV<br>V/μV                           |
|                  |                                      | $V_{\rm S} = 5V, R_{\rm L} = 2k, V_{\rm O} = 4.2V \text{ to } 0.7V$                                                 | 0.7       | 3.5          |                                                |                                        |
|                  |                                      | $0^{\circ}C \le T_A \le 70^{\circ}C$                                                                                | 0.6       | 3.2          |                                                | V/μV                                   |
|                  |                                      | $-40^{\circ}\text{C} \le \text{T}_{\text{A}} \le 85^{\circ}\text{C}$                                                |           | 3.0          |                                                | V/µV                                   |
|                  |                                      | $V_{S} = 5V, R_{L} = 600\Omega, V_{0} = 4.2V \text{ to } 0.7V$<br>$0^{\circ}C \le T_{A} \le 70^{\circ}C$            | 0.6       | 3.0<br>2.8   |                                                | V/μV<br>V/μV                           |
|                  |                                      | $ \begin{array}{c} 0^{\circ}C \leq T_{A} \leq 70^{\circ}C \\ -40^{\circ}C \leq T_{A} \leq 85^{\circ}C \end{array} $ |           | 2.0          |                                                | ν/μν<br>V/μV                           |
| V <sub>OL</sub>  | Output Voltage Swing Low (Note 11)   | Above GND                                                                                                           |           |              |                                                | <u> </u>                               |
|                  |                                      | $I_{SINK} = 0.1 \text{mA}$                                                                                          |           | 80<br>125    | 170                                            | mV                                     |
|                  |                                      | $0^{\circ}C \le T_A \le 70^{\circ}C$<br>-40^{\circ}C \le T_A \le 85^{\circ}C                                        |           | 125<br>130   | 200<br>250                                     | mV<br>mV                               |



**ELECTRICAL CHARACTERISTICS** The  $\bullet$  denotes the specifications which apply over the full operating temperature range, otherwise specifications are at  $T_A = 25^{\circ}$ C.  $V_S = 3V$ ,  $V_{CM} = V_0 = 1.7V$ ;  $V_S = 5V$ ,  $V_{CM} = V_0 = 2.5V$  unless otherwise noted.

| SYMBOL          | PARAMETER                                                    | CONDITIONS (Note 6)                                                                                                    |   | MIN           | ТҮР               | MAX               | UNITS                |
|-----------------|--------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------|---|---------------|-------------------|-------------------|----------------------|
| V <sub>OL</sub> | Output Voltage Swing Low (Note 11)                           | Above GND<br>$I_{SINK} = 2.5mA$<br>$0^{\circ}C \le T_A \le 70^{\circ}C$<br>$-40^{\circ}C \le T_A \le 85^{\circ}C$      | • |               | 170<br>195<br>205 | 250<br>320<br>350 | mV<br>mV<br>mV       |
|                 |                                                              | Above GND<br>$I_{SINK} = 10mA$<br>$0^{\circ}C \le T_A \le 70^{\circ}C$<br>$-40^{\circ}C \le T_A \le 85^{\circ}C$       | • |               | 370<br>440<br>465 | 600<br>720<br>770 | mV<br>mV<br>mV       |
| V <sub>OH</sub> | Output Voltage Swing High (Note 11)                          |                                                                                                                        | • |               | 75<br>85<br>93    | 150<br>200<br>250 | mV<br>mV<br>mV       |
|                 |                                                              | $      Below V_S \\ I_{SOURCE} = 2.5mA \\ 0^{\circ}C \le T_A \le 70^{\circ}C \\ -40^{\circ}C \le T_A \le 85^{\circ}C $ | • |               | 110<br>195<br>205 | 250<br>350<br>375 | mV<br>mV<br>mV       |
|                 |                                                              |                                                                                                                        | • |               | 170<br>200<br>230 | 400<br>500<br>550 | mV<br>mV<br>mV       |
| I <sub>SC</sub> | Output Short-Circuit Current (Note 3)                        | V <sub>S</sub> = 3V                                                                                                    | • | 15<br>13      | 22<br>19          |                   | mA<br>mA             |
|                 |                                                              | V <sub>S</sub> = 5V                                                                                                    | • | 18<br>14      | 29<br>25          |                   | mA<br>mA             |
| SR              | Slew Rate (Note 13)                                          |                                                                                                                        | • | 4<br>3.5<br>3 | 6<br>5.8<br>5.5   |                   | V/μs<br>V/μs<br>V/μs |
| GBW             | Gain Bandwidth Product (Note 11)                             | $f_0 = 100$ kHz<br>$f_0 = 100$ kHz                                                                                     | • | 13<br>12.5    | 20<br>19          |                   | MHz<br>MHz           |
| ts              | Settling Time                                                | 2V Step 0.1%, A <sub>V</sub> = +1<br>2V Step 0.01%, A <sub>V</sub> = +1                                                |   |               | 1.4<br>2.4        |                   | μS<br>μS             |
| R <sub>0</sub>  | Open-Loop Output Resistance<br>Closed-Loop Output Resistance | I <sub>OUT</sub> = 0<br>A <sub>V</sub> = 100, f = 10kHz                                                                |   |               | 100<br>1          |                   | Ω<br>Ω               |
| I <sub>S</sub>  | Supply Current per Amplifier (Note 12)                       |                                                                                                                        | • |               | 2<br>2.5          | 3.4<br>3.8        | mA<br>mA             |
| $\Delta V_{0S}$ | Offset Voltage Match<br>(Notes 11, 15)                       | $0^{\circ}C \le T_A \le 70^{\circ}C$<br>-40°C $\le T_A \le 85^{\circ}C$                                                | • |               | 35<br>55<br>75    | 150<br>400<br>525 | Ψμ<br>Ψμ<br>Ψμ       |
| ΔIB+            | Noninverting Bias Current Match<br>(Notes 11, 15)            | $0^{\circ}C \le T_A \le 70^{\circ}C$<br>-40°C $\le T_A \le 85^{\circ}C$                                                | • |               | ±2<br>±3<br>±7    | ±30<br>±55<br>±75 | nA<br>nA<br>nA       |
| ∆CMRR           | Common Mode Rejection Match<br>(Notes 11, 14, 15)            | V <sub>S</sub> = 5V, V <sub>CM</sub> = 1.9V to 3.9V                                                                    | • | 94<br>88      | 110<br>110        |                   | dB<br>dB             |
| ΔPSRR           | Power Supply Rejection Match<br>(Notes 11, 14, 15)           |                                                                                                                        | • | 96<br>94      | 120<br>120        |                   | dB<br>dB             |



**ELECTRICAL CHARACTERISTICS** The  $\bullet$  denotes the specifications which apply over the full operating temperature range, otherwise specifications are at T<sub>A</sub> = 25°C. V<sub>S</sub> = ±15V, V<sub>CM</sub> = V<sub>0</sub> = 0V unless otherwise noted.

| SYMBOL                              | PARAMETER                            | CONDITIONS (Note 6)                                                                                                                       |   | MIN               | ТҮР               | MAX               | UNITS                                                       |
|-------------------------------------|--------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------|---|-------------------|-------------------|-------------------|-------------------------------------------------------------|
| V <sub>OS</sub>                     | Input Offset Voltage                 | 0°C ≤ T <sub>A</sub> ≤ 70°C<br>−40°C ≤ T <sub>A</sub> ≤ 85°C                                                                              | • |                   | 20<br>30<br>45    | 150<br>350<br>420 | μγ<br>μγ<br>μγ                                              |
| $\frac{\Delta V_{OS}}{\Delta Temp}$ | Average Input Offset Drift (Note 10) |                                                                                                                                           | • |                   | 0.40              | 3                 | μV/°C                                                       |
| I <sub>B</sub>                      | Input Bias Current                   | 0°C ≤ T <sub>A</sub> ≤ 70°C<br>−40°C ≤ T <sub>A</sub> ≤ 85°C                                                                              | • |                   | ±2<br>±3<br>±7    | ±20<br>±35<br>±50 | nA<br>nA<br>nA                                              |
| I <sub>OS</sub>                     | Input Offset Current                 | $0^{\circ}C \le T_A \le 70^{\circ}C$<br>$-40^{\circ}C \le T_A \le 85^{\circ}C$                                                            | • |                   | 3<br>5<br>8       | 25<br>35<br>55    | nA<br>nA<br>nA                                              |
| en                                  | Input Noise Voltage                  | 0.1Hz to 10Hz (Note 7)<br>V <sub>CM</sub> = 15V<br>V <sub>CM</sub> = -15V                                                                 |   |                   | 90<br>180<br>1600 |                   | nV <sub>P-P</sub><br>nV <sub>P-P</sub><br>nV <sub>P-P</sub> |
|                                     | Input Noise Voltage Density          |                                                                                                                                           |   |                   | 4.4<br>6.6<br>19  |                   | nV/√Hz<br>nV/√Hz<br>nV/√Hz                                  |
|                                     |                                      | f <sub>0</sub> = 1kHz<br>V <sub>CM</sub> = 15V, f <sub>0</sub> = 1kHz<br>V <sub>CM</sub> = -15V, f <sub>0</sub> = 1kHz                    |   |                   | 3.9<br>5.3<br>9   | 5.5               | nV/√Hz<br>nV/√Hz<br>nV/√Hz                                  |
| i <sub>n</sub>                      | Input Noise Current Density          | $f_0 = 10$ Hz<br>$f_0 = 1$ kHz                                                                                                            |   |                   | 1.2<br>0.3        |                   | pA/√Hz<br>pA/√Hz                                            |
| V <sub>CM</sub>                     | Input Voltage Range (Note 16)        |                                                                                                                                           | • | -13.3             |                   | 14                | V                                                           |
| R <sub>IN</sub>                     | Input Resistance                     | Common Mode                                                                                                                               |   |                   | 2                 |                   | GΩ                                                          |
| C <sub>IN</sub>                     | Input Capacitance                    |                                                                                                                                           |   |                   | 4.2               |                   | pF                                                          |
| CMRR                                | Common Mode Rejection Ratio          | V <sub>CM</sub> = -13.3V to 14V                                                                                                           | • | 100<br>96         | 130<br>124        |                   | dB<br>dB                                                    |
| PSRR                                | Power Supply Rejection Ratio         | $V_{S} = \pm 1.7 V$ to $\pm 18 V$                                                                                                         | • | 106<br>100        | 130<br>125        |                   | dB<br>dB                                                    |
| A <sub>VOL</sub>                    | Large-Signal Voltage Gain            | $ \begin{array}{l} R_L = 10k, \ V_0 = \pm 14V \\ 0^\circ C \leq T_A \leq 70^\circ C \\ -40^\circ C \leq T_A \leq 85^\circ C \end{array} $ | • | 3<br>2<br>1       | 7<br>6<br>4       |                   | V/μV<br>V/μV<br>V/μV                                        |
|                                     |                                      | $\begin{array}{l} R_L = 2k,  V_0 = \pm 13.5V \\ 0^\circC \leq T_A \leq 70^\circC \\ -40^\circC \leq T_A \leq 85^\circC \end{array}$       | • | 0.8<br>0.5<br>0.4 | 1.7<br>1.4<br>1.1 |                   | V/μV<br>V/μV<br>V/μV                                        |



**ELECTRICAL CHARACTERISTICS** The  $\bullet$  denotes the specifications which apply over the full operating temperature range, otherwise specifications are at  $T_A = 25^{\circ}$ C.  $V_S = \pm 15$ V,  $V_{CM} = V_0 = 0$ V unless otherwise noted.

| SYMBOL           | PARAMETER                                                    | CONDITIONS (Note 6)                                                                                                                                                                                                                                     | N   | IIN           | ТҮР               | MAX                      | UNITS                |
|------------------|--------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|---------------|-------------------|--------------------------|----------------------|
| V <sub>OL</sub>  | Output Voltage Swing Low                                     | Above $-V_S$<br>$I_{SINK} = 0.1mA$<br>$0^{\circ}C \le T_A \le 70^{\circ}C$<br>$-40^{\circ}C \le T_A \le 85^{\circ}C$                                                                                                                                    | •   |               | 110<br>125<br>130 | 200<br>230<br>260        | mV<br>mV<br>mV       |
|                  |                                                              | $\begin{array}{l} \text{Above} - V_{\text{S}} \\ \text{I}_{\text{SINK}} = 2.5\text{mA} \\ 0^{\circ}\text{C} \leq T_{\text{A}} \leq 70^{\circ}\text{C} \\ -40^{\circ}\text{C} \leq T_{\text{A}} \leq 85^{\circ}\text{C} \end{array}$                     | •   |               | 170<br>195<br>205 | 280<br>280<br>350<br>380 | mV<br>mV<br>mV       |
|                  |                                                              | Above $-V_S$<br>$I_{SINK} = 10mA$<br>$0^{\circ}C \le T_A \le 70^{\circ}C$<br>$-40^{\circ}C \le T_A \le 85^{\circ}C$                                                                                                                                     | •   |               | 370<br>440<br>450 | 600<br>700<br>750        | mV<br>mV<br>mV       |
| V <sub>OH</sub>  | Output Voltage Swing High                                    | $\begin{array}{l} \text{Below +V}_S\\ I_{SOURCE} = 0.1\text{mA}\\ 0^\circ\text{C} \leq \text{T}_A \leq 70^\circ\text{C}\\ -40^\circ\text{C} \leq \text{T}_A \leq 85^\circ\text{C} \end{array}$                                                          | •   |               | 80<br>90<br>100   | 150<br>200<br>250        | mV<br>mV<br>mV       |
|                  |                                                              | $\begin{array}{l} \text{Below } +\text{V}_{\text{S}}\\ \text{I}_{\text{SOURCE}} = 2.5\text{mA}\\ 0^{\circ}\text{C} \leq \text{T}_{\text{A}} \leq 70^{\circ}\text{C}\\ -40^{\circ}\text{C} \leq \text{T}_{\text{A}} \leq 85^{\circ}\text{C} \end{array}$ | •   |               | 110<br>120<br>120 | 200<br>300<br>350        | mV<br>mV<br>mV       |
|                  |                                                              | $\begin{array}{l} \text{Below +V}_{\text{S}} \\ \text{I}_{\text{SOURCE}} = 10\text{mA} \\ 0^{\circ}\text{C} \leq \text{T}_{\text{A}} \leq 70^{\circ}\text{C} \\ -40^{\circ}\text{C} \leq \text{T}_{\text{A}} \leq 85^{\circ}\text{C} \end{array}$       | •   |               | 200<br>250<br>250 | 450<br>500<br>550        | mV<br>mV<br>mV       |
| I <sub>SC</sub>  | Output Short-Circuit Current (Note 3)                        |                                                                                                                                                                                                                                                         |     | 20<br>15      | 35<br>28          |                          | mA<br>mA             |
| SR               | Slew Rate                                                    | $ \begin{array}{l} R_L = 10k \; (Note \; 9) \\ R_L = 10k \; (Note \; 9) \; 0^{\circ}C \leq T_A \leq 70^{\circ}C \\ R_L = 10k \; (Note \; 9) \; -40^{\circ}C \leq T_A \leq 85^{\circ}C \end{array} $                                                     | • 3 | 4<br>3.5<br>3 | 6<br>5.8<br>5.5   |                          | V/μs<br>V/μs<br>V/μs |
| GBW              | Gain Bandwidth Product                                       | $f_0 = 100 \text{kHz}$<br>$f_0 = 100 \text{kHz}$                                                                                                                                                                                                        |     | 13<br>2.5     | 20<br>19          |                          | MHz<br>MHz           |
| THD              | Total Harmonic Distortion                                    | $R_{L} = 2k, A_{V} = 1, f_{0} = 1kHz, V_{0} = 20V_{P-P}$                                                                                                                                                                                                |     |               | 0.00025           |                          | %                    |
| t <sub>S</sub>   | Settling Time                                                | 10V Step 0.1%, A <sub>V</sub> = +1<br>10V Step 0.01%, A <sub>V</sub> = +1                                                                                                                                                                               |     |               | 2.7<br>3.9        |                          | μS<br>μS             |
| R <sub>0</sub>   | Open-Loop Output Resistance<br>Closed-Loop Output Resistance | $I_{OUT} = 0$<br>A <sub>V</sub> = 100, f = 10kHz                                                                                                                                                                                                        |     |               | 100<br>1          |                          | Ω<br>Ω               |
| I <sub>S</sub>   | Supply Current per Amplifier                                 |                                                                                                                                                                                                                                                         | •   |               | 2.5<br>3          | 3.5<br>4.5               | mA<br>mA             |
|                  | Channel Separation                                           | $f = 10Hz, V_0 = \pm 10V, R_L = 10k$                                                                                                                                                                                                                    |     |               | 132               |                          | dB                   |
| ΔV <sub>OS</sub> | Offset Voltage Match<br>(Note 15)                            | $0^{\circ}C \le T_A \le 70^{\circ}C$<br>-40°C $\le T_A \le 85^{\circ}C$                                                                                                                                                                                 | •   |               | 5<br>30<br>45     | 225<br>525<br>630        | Vպ<br>Vպ<br>Vպ       |
| ΔIB+             | Noninverting Bias Current Match<br>(Note 15)                 | $0^{\circ}C \le T_A \le 70^{\circ}C$<br>-40°C ≤ $T_A \le 85^{\circ}C$                                                                                                                                                                                   | •   |               | ±2<br>±3<br>±7    | ±30<br>±55<br>±75        | nA<br>nA<br>nA       |
| ΔCMRR            | Common Mode Rejection Match<br>(Notes 14, 15)                | V <sub>CM</sub> = -13.3V to 14V                                                                                                                                                                                                                         |     | 96<br>92      | 120<br>115        |                          | dB<br>dB             |
| ΔPSRR            | Power Supply Rejection Match<br>(Notes 14, 15)               | $V_{S} = \pm 1.7V \text{ to } \pm 18V$                                                                                                                                                                                                                  |     | 00<br>96      | 123<br>120        |                          | dB<br>dB             |





## **ELECTRICAL CHARACTERISTICS**

**Note 1:** Absolute Maximum Ratings are those values beyond which the life of the device may be impaired.

**Note 2:** The inputs are protected by back-to-back diodes. Current limiting resistors are not used in order to achieve low noise. If differential input voltage exceeds  $\pm 1.4V$ , the input current should be limited to 25mA. If the common mode range exceeds either rail, the input current should be limited to 10mA.

**Note 3:** A heat sink may be required to keep the junction temperature below absolute maximum.

**Note 4:** The LT1678C/LT1679C and LT1678I/LT1679I are guaranteed functional over the Operating Temperature Range of  $-40^{\circ}$ C to  $85^{\circ}$ C.

**Note 5:** The LT1678C/LT1679C are guaranteed to meet specified performance from 0°C to 70°C. The LT1678C/LT1679C are designed, characterized and expected to meet specified performance from -40°C to 85°C but is not tested or QA sampled at these temperatures. The LT1678I/LT1679I are guaranteed to meet specified performance from -40°C to 85°C.

**Note 6:** Typical parameters are defined as the 60% yield of parameter distributions of individual amplifier; i.e., out of 100 LT1678/LT1679s, typically 60 op amps will be better than the indicated specification.

**Note 7:** See the test circuit and frequency response curve for 0.1Hz to10Hz tester in the Applications Information section.

Note 8: Noise is 100% tested at ±15V supplies.

Note 9: Slew rate is measured in  $A_V = -1$ ; input signal is ±10V, output measured at ±5V.

Note 10: This parameter is not 100% tested.

Note 11:  $V_S$  = 5V limits are guaranteed by correlation to  $V_S$  = 3V and  $V_S$  =  $\pm 15V$  tests.

Note 12:  $V_S$  = 3V limits are guaranteed by correlation to  $V_S$  = 5V and  $V_S$  =  $\pm 15V$  tests.

Note 13: Guaranteed by correlation to slew rate at V\_S =  $\pm 15V$  and GBW at V\_S = 3V and V\_S =  $\pm 15V$  tests.


Note 14:  $\triangle CMRR$  and  $\triangle PSRR$  are defined as follows:

- 1. CMRR and PSRR are measured in  $\mu$ V/V on the individual amplifiers.
- 2. The difference is calculated between the matching sides in  $\mu$ V/V.
- 3. The result is converted to dB.


**Note 15:** Matching parameters are the difference between amplifiers A and B on the LT1678 and between amplifiers A and D and B and C in the LT1679.

Note 16: Input range guaranteed by the common mode rejection ratio test.


## TYPICAL PERFORMANCE CHARACTERISTICS




#### 0.1Hz to 10Hz Voltage Noise



#### 0.01Hz to 1Hz Voltage Noise



# **TYPICAL PERFORMANCE CHARACTERISTICS**



-500

-700

-900

-16 -12 -8 -4 0 4 8 12 16

0

-3.0 -2.0 -1.0 0 1.0 2.0 3.0

#### **Current Noise vs Frequency**

------

1


V<sub>CM</sub> = 14.5V

V<sub>CM</sub> = 14.1V


10

16789 G05

**Input Bias Current vs Temperature** 



**Offset Voltage Shift vs Common Mode** 



Warm-Up Drift vs Time 10  $V_{\rm S} = \pm 15V$  $T_A = 25^{\circ}C$ CHANGE IN OFFSET VOLTAGE (µV) 8 SO PACKAGE 6 4 2 0 2 0 1 3 4 TIME (min) 16789 G10


V<sub>CM</sub> = 14.7V

CURRENT INTO DUT

TEMPERATURE (°C)

75 100 125

16789 G07




INPUT OFFSET VOLTAGE DRIFT (µV/°C)

16789 G11

COMMON MODE INPUT VOLTAGE (V)

V<sub>CM</sub> = -15.2V

V<sub>OS</sub> vs Temperature of **Representive Units** 



sn16789 16789fs



400

200


0

-50

-25

0 25 50


### **TYPICAL PERFORMANCE CHARACTERISTICS**





Q

# TYPICAL PERFORMANCE CHARACTERISTICS



sn16789 16789fs



## **APPLICATIONS INFORMATION**

#### **Rail-to-Rail Operation**

To take full advantage of an input range that can exceed the supply, the LT1678/LT1679 are designed to eliminate phase reversal. Referring to the photographs shown in Figure 1, the LT1678/LT1679 are operating in the follower mode ( $A_V = +1$ ) at a single 3V supply. The output of the LT1678/LT1679 clips cleanly and recovers with no phase reversal. This has the benefit of preventing lock-up in servo systems and minimizing distortion components.




Figure 1. Voltage Follower with Input Exceeding the Supply Voltage ( $V_S = 3V$ )

#### **Unity-Gain Buffer Application**

When  $R_F \le 100\Omega$  and the input is driven with a fast, largesignal pulse (>1V), the output waveform will look as shown in the pulsed operation diagram (Figure 2).

During the fast feedthrough-like portion of the output, the input protection diodes effectively short the output to the



input and a current, limited only by the output short-circuit protection, will be drawn by the signal generator. With  $R_F \ge 500\Omega$ , the output is capable of handling the current requirements ( $I_L \le 20$ mA at 10V) and the amplifier stays in its active mode and a smooth transition will occur.

As with all operational amplifiers when  $R_F > 2k$ , a pole will be created with  $R_F$  and the amplifier's input capacitance, creating additional phase shift and reducing the phase margin. A small capacitor (20pFto 50pF) in parallel with  $R_F$ will eliminate this problem.




Figure 2. Pulsed Operation


#### Noise Testing

The 0.1Hz to 10Hz peak-to-peak noise of the LT1678/ LT1679 are measured in the test circuit shown (Figure 3). The frequency response of this noise tester (Figure 4) indicates that the 0.1Hz corner is defined by only one zero. The test time to measure 0.1Hz to 10Hz noise should not exceed ten seconds, as this time limit acts as an additional zero to eliminate noise contributions from the frequency band below 0.1Hz.

Measuring the typical 90nV peak-to-peak noise performance of the LT1678/LT1679 requires special test precautions:

- 1. The device should be warmed up for at least five minutes. As the op amp warms up, its offset voltage changes typically  $3\mu V$  due to its chip temperature increasing  $10^{\circ}$ C to  $20^{\circ}$ C from the moment the power supplies are turned on. In the ten-second measurement interval these temperature-induced effects can easily exceed tens of nanovolts.
- 2. For similar reasons, the device must be well shielded from air currents to eliminate the possibility of thermoelectric effects in excess of a few nanovolts, which would invalidate the measurements.

# **APPLICATIONS INFORMATION**






Figure 3. 0.1Hz to 10Hz Noise Test Circuit

3. Sudden motion in the vicinity of the device can also "feedthrough" to increase the observed noise.

Current noise is measured in the circuit shown in Figure 5 and calculated by the following formula:




Figure 5.

The LT1678/LT1679 achieve their low noise, in part, by operating the input stage at 100µA versus the typical 10µA of most other op amps. Voltage noise is inversely proportional while current noise is directly proportional to the square root of the input stage current. Therefore, the LT1678/LT1679's current noise will be relatively high. At low frequencies, the low 1/f current noise corner frequency ( $\approx$  200Hz) minimizes current noise to some extent.

In most practical applications, however, current noise will not limit system performance. This is illustrated in the Total Noise vs Source Resistance plot (Figure 6) where:

Figure 4. 0.1Hz to 10Hz Peak-to-Peak **Noise Tester Frequency Response** 

Total Noise =  $[(op amp voltage noise)^2 + (resistor noise)^2$ + (current noise  $R_s$ )<sup>2</sup>]<sup>1/2</sup>

100

90


80

70

Three regions can be identified as a function of source resistance:

- (i)  $R_S \le 400\Omega$ . Voltage noise dominates
- (ii)  $400\Omega \le R_S \le 50k$  at 1kHz Resistor Noise  $400\Omega \le R_S \le 8k$  at 10Hz Dominates
- (iii)  $R_S > 50k$  at 1kHz Current Noise  $R_S > 8k$  at 10Hz Dominates

Clearly the LT1678/LT1679 should not be used in region (iii), where total system noise is at least six times higher than the voltage noise of the op amp, i.e., the low voltage noise specification is completely wasted. In this region the LT1113 or LT1169 are better choices.





## **APPLICATIONS INFORMATION**

#### Rail-to-Rail Input

The input common mode range for the LT1678/LT1679 can exceed the supplies by at least 100mV. As the common mode voltage approaches the positive rail (+V<sub>S</sub> – 0.7V), the tail current for the input pair (Q1, Q2) is reduced, which prevents the input pair from saturating (refer to the Simplified Schematic). The voltage drop across the load resistors  $R_{C1}$ ,  $R_{C2}$  is reduced to less than 200mV, degrading the slew rate, bandwidth, voltage noise, offset voltage and input bias current (the cancellation is shut off).

When the input common mode range goes below 1.5V above the negative rail, the NPN input pair (Q1, Q2) shuts off and the PNP input pair (Q8, Q9) turns on. The offset voltage, input bias current, voltage noise and bandwidth are also degraded. The graph of Offset Voltage Shift vs Common Mode shows where the knees occur by displaying the change in offset voltage. The change-over points are temperature dependent; see the graph Common Mode Range vs Temperature.

#### Rail-to-Rail Output

The rail-to-rail output swing is achieved by using transistor collectors (Q28, Q29 referring to the Simplified Schematic) instead of customary class A-B emitter followers for the output stage. The output NPN transistor (Q29) sinks the current necessary to move the output in the negative direction. The change in Q29's base emitter voltage is reflected directly to the gain node (collectors of Q20 and Q16). For large sinking currents, the delta V<sub>BF</sub> of Q29 can dominate the gain. Figure 7 shows the change in input voltage for a change in output voltage for different load resistors connected between the supplies. The gain is much higher for output voltages above ground (Q28 sources current) since the change in base emitter voltage of Q28 is attenuated by the gain in the PNP portion of the output stage. Therefore, for positive output swings (output sourcing current) there is hardly any change in input voltage for any load resistance. Highest gain and best linearity are achieved when the output is sourcing current, which is the case in single supply operation when the load is ground referenced. Figure 8 shows gains for both sinking and sourcing load currents for a worst-case load of  $600\Omega$ .




Figure 7. Voltage Gain Split Supply





Figure 8. Voltage Gain Single Supply




## SIMPLIFIED SCHEMATIC






#### PACKAGE DESCRIPTION



S8 Package 8-Lead Plastic Small Outline (Narrow .150 Inch) (Reference LTC DWG # 05-08-1610)

S Package 14-Lead Plastic Small Outline (Narrow .150 Inch) (Reference LTC DWG # 05-08-1610)



MOLD FLASH OR PROTRUSIONS SHALL NOT EXCEED .006" (0.15mm)


sn16789 16789fs



Information furnished by Linear Technology Corporation is believed to be accurate and reliable. However, no responsibility is assumed for its use. Linear Technology Corporation makes no representation that the interconnection of its circuits as described herein will not infringe on existing patent rights.

## TYPICAL APPLICATION

Bridge Reversal Eliminates 1/f Noise and Offset Drift of a Low Noise, Non-autozeroed, Bipolar Amplifier. Circuit Gives 14nV Noise Level or 19 Effective Bits Over a 10mV Span



#### **RELATED PARTS**

| PART NUMBER   | DESCRIPTION                                                     | COMMENTS                                                       |
|---------------|-----------------------------------------------------------------|----------------------------------------------------------------|
| LT1028/LT1128 | Ultralow Noise Precision Op Amps                                | Lowest Noise 0.85nV/ <del>/Hz</del>                            |
| LT1115        | Ultralow Noise, Low distortion Audio Op Amp                     | 0.002% THD, Max Noise 1.2nV/ <del>√Hz</del>                    |
| LT1124/LT1125 | Dual/Quad Low Noise, High Speed Precision Op Amps               | Similar to LT1007                                              |
| LT1126/LT1127 | Dual/Quad Decompensated Low Noise, High Speed Precision Op Amps | Similar to LT1037                                              |
| LT1226        | Low Noise, Very High Speed Op Amp                               | 1GHz, 2.6nV/√Hz, Gain of 25 Stable                             |
| LT1498/LT1499 | 10MHz, 5V/µs, Dual/Quad Rail-to-Rail Input and Output Op Amps   | Precision C-Load <sup>™</sup> Stable                           |
| LT1677        | Single Version of LT1678/LT1679                                 | Rail-to-Rail 3.2nV/√Hz                                         |
| LT1792        | Low Noise, Precision JFET Input Op Amp                          | 4.2nV/√Hz, 10fA/√Hz                                            |
| LT1793        | Low Noise, Picoampere Bias Current Op Amp                       | $6nV/\sqrt{Hz}$ , 1fA/ $\sqrt{Hz}$ , I <sub>B</sub> = 10pA Max |
| LT1806        | Low Noise, 325MHz Rail-to-Rail Input and Output Op Amp          | 3.5nV/√Hz                                                      |
| LT1881/LT1882 | Dual/Quad Rail-to-Rail Output Picoamp Input Precision Op Amps   | $C_{LOAD}$ to 1000pF, $I_B = 200$ pA Max                       |
| LT1884/LT1885 | Dual/Quad Rail-to-Rail Output Picoamp Input Precision Op Amps   | 2.2MHz Bandwidth, 1.2V/µs SR                                   |

C-Load is a trademark of Linear Technology Corporation.



