TABLE 1: PIC32MX1XX 28/36/44-PIN GENERAL PURPOSE FAMILY FEATURES

				Rem	appab	le Pe	riphe	rals							(S				
Device	Pins	Program Memory (KB) <sup>(1)</sup>	Data Memory (KB)	Remappable Pins	Timers <sup>(2)</sup> /Capture/Compare	UART	SPI/I <sup>2</sup> S	External Interrupts <sup>(3)</sup>	Analog Comparators	USB On-The-Go (OTG)	1 <sup>2</sup> C	ЬМР	DMA Channels (Programmable/Dedicated)	СТМО	10-bit 1 Msps ADC (Channels)	RTCC	I/O Pins	JTAG	Packages
PIC32MX110F016B	28	16+3	4	20	5/5/5	2	2	5	3	N	2	Υ	4/0	Υ	10	Υ	21	Υ	SOIC, SSOP, SPDIP, QFN
PIC32MX110F016C	36	16+3	4	24	5/5/5	2	2	5	3	Ν	2	Υ	4/0	Υ	12	Υ	25	Υ	VTLA
PIC32MX110F016D	44	16+3	4	32	5/5/5	2	2	5	3	N	2	Υ	4/0	Υ	13	Υ	35	Υ	VTLA, TQFP, QFN
PIC32MX120F032B	28	32+3	8	20	5/5/5	2	2	5	3	N	2	Y	4/0	Υ	10	Υ	21	Υ	SOIC, SSOP, SPDIP, QFN
PIC32MX120F032C	36	32+3	8	24	5/5/5	2	2	5	3	N	2	Υ	4/0	Υ	12	Υ	25	Υ	VTLA
PIC32MX120F032D	44	32+3	8	32	5/5/5	2	2	5	3	N	2	Υ	4/0	Υ	13	Υ	35	Υ	VTLA, TQFP, QFN
PIC32MX130F064B	28	64+3	16	20	5/5/5	2	2	5	3	N	2	Υ	4/0	Υ	10	Υ	21	Υ	SOIC, SSOP, SPDIP, QFN
PIC32MX130F064C	36	64+3	16	24	5/5/5	2	2	5	3	N	2	Υ	4/0	Υ	12	Υ	25	Υ	VTLA
PIC32MX130F064D	44	64+3	16	32	5/5/5	2	2	5	3	N	2	Υ	4/0	Υ	13	Υ	35	Υ	VTLA, TQFP, QFN
PIC32MX150F128B	28	128+3	32	20	5/5/5	2	2	5	3	Ν	2	Y	4/0	Υ	10	Υ	21	Υ	SOIC, SSOP, SPDIP, QFN
PIC32MX150F128C	36	128+3	32	24	5/5/5	2	2	5	3	N	2	Υ	4/0	Υ	12	Υ	25	Υ	VTLA
PIC32MX150F128D	44	128+3	32	32	5/5/5	2	2	5	3	N	2	Υ	4/0	Υ	13	Υ	35	Υ	VTLA, TQFP, QFN
PIC32MX130F256B	28	256+3	16	20	5/5/5	2	2	5	3	N	2	Υ	4/0	Υ	10	Υ	21	Υ	SSOP, SPDIP, QFN
PIC32MX130F256D	44	256+3	16	32	5/5/5	2	2	5	3	Ν	2	Υ	4/0	Υ	13	Υ	35	Υ	VTLA, TQFP, QFN
PIC32MX170F256B	28	256+3	64	20	5/5/5	2	2	5	3	N	2	Υ	4/0	Υ	10	Υ	21	Υ	SOIC, SSOP, SPDIP, QFN
PIC32MX170F256D	44	256+3	64	32	5/5/5	2	2	5	3	N	2	Υ	4/0	Υ	13	Υ	35	Υ	VTLA, TQFP, QFN

Note 1: This device features 3 KB of boot Flash memory.

**<sup>2:</sup>** Four out of five timers are remappable.

**<sup>3:</sup>** Four out of five external interrupts are remappable.

TABLE 2: PIC32MX2XX 28/36/44-PIN USB FAMILY FEATURES

			13014		appab	le Pe	riphe	rals					_		ŝ				
Device	Pins	Program Memory (KB) <sup>(1)</sup>	Data Memory (KB)	Remappable Pins	Timers <sup>(2)</sup> /Capture/Compare	UART	SPI/I <sup>2</sup> S	External Interrupts <sup>(3)</sup>	Analog Comparators	USB On-The-Go (OTG)	1 <sup>2</sup> C	PMP	DMA Channels (Programmable/Dedicated)	СТМО	10-bit 1 Msps ADC (Channels)	RTCC	I/O Pins	JTAG	Packages
PIC32MX210F016B	28	16+3	4	19	5/5/5	2	2	5	3	Υ	2	Υ	4/2	Υ	9	Υ	19	Υ	SOIC, SSOP, SPDIP, QFN
PIC32MX210F016C	36	16+3	4	23	5/5/5	2	2	5	3	Υ	2	Υ	4/2	Υ	12	Υ	25	Υ	VTLA
PIC32MX210F016D	44	16+3	4	31	5/5/5	2	2	5	3	Υ	2	Υ	4/2	Υ	13	Υ	33	Υ	VTLA, TQFP, QFN
PIC32MX220F032B	28	32+3	8	19	5/5/5	2	2	5	3	Υ	2	Υ	4/2	Υ	9	Υ	19	Υ	SOIC, SSOP, SPDIP, QFN
PIC32MX220F032C	36	32+3	8	23	5/5/5	2	2	5	3	Υ	2	Υ	4/2	Υ	12	Υ	23	Υ	VTLA
PIC32MX220F032D	44	32+3	8	31	5/5/5	2	2	5	3	Υ	2	Υ	4/2	Υ	13	Υ	33	Υ	VTLA, TQFP, QFN
PIC32MX230F064B	28	64+3	16	19	5/5/5	2	2	5	3	Υ	2	Υ	4/2	Υ	9	Υ	19	Y	SOIC, SSOP, SPDIP, QFN
PIC32MX230F064C	36	64+3	16	23	5/5/5	2	2	5	3	Υ	2	Υ	4/2	Υ	12	Υ	23	Υ	VTLA
PIC32MX230F064D	44	64+3	16	31	5/5/5	2	2	5	3	Υ	2	Υ	4/2	Υ	13	Υ	33	Υ	VTLA, TQFP, QFN
PIC32MX250F128B	28	128+3	32	19	5/5/5	2	2	5	3	Υ	2	Y	4/2	Υ	9	Υ	19	Y	SOIC, SSOP, SPDIP, QFN
PIC32MX250F128C	36	128+3	32	23	5/5/5	2	2	5	3	Υ	2	Υ	4/2	Υ	12	Υ	23	Υ	VTLA
PIC32MX250F128D	44	128+3	32	31	5/5/5	2	2	5	3	Υ	2	Υ	4/2	Υ	13	Υ	33	Υ	VTLA, TQFP, QFN
PIC32MX230F256B	28	256+3	16	19	5/5/5	2	2	5	3	Υ	2	Υ	4/2	Υ	9	Υ	19	Υ	SSOP, SPDIP, QFN
PIC32MX230F256D	44	256+3	16	31	5/5/5	2	2	5	3	Υ	2	Υ	4/2	Υ	13	Υ	33	Υ	VTLA, TQFP, QFN
PIC32MX270F256B	28	256+3	64	19	5/5/5	2	2	5	3	Υ	2	Υ	4/2	Υ	9	Υ	19	Υ	SOIC, SSOP, SPDIP, QFN
PIC32MX270F256D  Note 1: This device	44	256+3	64	31	5/5/5	2	2	5	3	Υ	2	Υ	4/2	Υ	13	Υ	33	Υ	VTLA, TQFP, QFN


Note 1: This device features 3 KB of boot Flash memory.

**<sup>2:</sup>** Four out of five timers are remappable.

**<sup>3:</sup>** Four out of five external interrupts are remappable.

#### **Pin Diagrams**

#### TABLE 3: PIN NAMES FOR 28-PIN GENERAL PURPOSE DEVICES




Pin#	Full Pin Name
1	MCLR
2	VREF+/CVREF+/AN0/C3INC/RPA0/CTED1/RA0
3	VREF-/CVREF-/AN1/RPA1/CTED2/RA1
4	PGED1/AN2/C1IND/C2INB/C3IND/RPB0/RB0
5	PGEC1/AN3/C1INC/C2INA/RPB1/CTED12/RB1
6	AN4/C1INB/C2IND/RPB2/SDA2/CTED13/RB2
7	AN5/C1INA/C2INC/RTCC/RPB3/SCL2/RB3
8	Vss
9	OSC1/CLKI/RPA2/RA2
10	OSC2/CLKO/RPA3/PMA0/RA3
11	SOSCI/RPB4/RB4
12	SOSCO/RPA4/T1CK/CTED9/PMA1/RA4
13	VDD
14	PGED3/RPB5/PMD7/RB5

Pin#	Full Pin Name
15	PGEC3/RPB6/PMD6/RB6
16	TDI/RPB7/CTED3/PMD5/INT0/RB7
17	TCK/RPB8/SCL1/CTED10/PMD4/RB8
18	TDO/RPB9/SDA1/CTED4/PMD3/RB9
19	Vss
20	VCAP
21	PGED2/RPB10/CTED11/PMD2/RB10
22	PGEC2/TMS/RPB11/PMD1/RB11
23	AN12/PMD0/RB12
24	AN11/RPB13/CTPLS/PMRD/RB13
25	CVREFOUT/AN10/C3INB/RPB14/SCK1/CTED5/PMWR/RB14
26	AN9/C3INA/RPB15/SCK2/CTED6/PMCS1/RB15
27	AVss
28	AVDD

- 1: The RPn pins can be used by remappable peripherals. See Table 1 for the available peripherals and Section 11.3 "Peripheral Pin Select" for restrictions.
- 2: Every I/O port pin (RAx-RCx) can be used as a change notification pin (CNAx-CNCx). See Section 11.0 "I/O Ports" for more information.
- 3: Shaded pins are 5V tolerant.

#### TABLE 4: PIN NAMES FOR 28-PIN USB DEVICES



Pin#	Full Pin Name
1	MCLR
2	PGED3/VREF+/CVREF+/AN0/C3INC/RPA0/CTED1/PMD7/RA0
3	PGEC3/VREF-/CVREF-/AN1/RPA1/CTED2/PMD6/RA1
4	PGED1/AN2/C1IND/C2INB/C3IND/RPB0/PMD0/RB0
5	PGEC1/AN3/C1INC/C2INA/RPB1/CTED12/PMD1/RB1
6	AN4/C1INB/C2IND/RPB2/SDA2/CTED13/PMD2/RB2
7	AN5/C1INA/C2INC/RTCC/RPB3/SCL2/PMWR/RB3
8	Vss
9	OSC1/CLKI/RPA2/RA2
10	OSC2/CLKO/RPA3/PMA0/RA3
11	SOSCI/RPB4/RB4
12	SOSCO/RPA4/T1CK/CTED9/PMA1/RA4
13	VDD
14	TMS/RPB5/USBID/RB5


Pin#	Full Pin Name
15	VBUS
16	TDI/RPB7/CTED3/PMD5/INT0/RB7
17	TCK/RPB8/SCL1/CTED10/PMD4/RB8
18	TDO/RPB9/SDA1/CTED4/PMD3/RB9
19	Vss
20	VCAP
21	PGED2/RPB10/D+/CTED11/RB10
22	PGEC2/RPB11/D-/RB11
23	Vusb3v3
24	AN11/RPB13/CTPLS/PMRD/RB13
25	CVREFOUT/AN10/C3INB/RPB14/VBUSON/SCK1/CTED5/RB14
26	AN9/C3INA/RPB15/SCK2/CTED6/PMCS1/RB15
27	AVss
28	AVDD

- 1: The RPn pins can be used by remappable peripherals. See Table 1 for the available peripherals and Section 11.3 "Peripheral Pin Select" for restrictions.
- 2: Every I/O port pin (RAx-RCx) can be used as a change notification pin (CNAx-CNCx). See Section 11.0 "I/O Ports" for more information.
- 3: Shaded pins are 5V tolerant.

#### TABLE 5: PIN NAMES FOR 28-PIN GENERAL PURPOSE DEVICES

### 28-PIN QFN (TOP VIEW)(1,2,3.4)

PIC32MX110F016B PIC32MX120F032B PIC32MX130F064B PIC32MX130F256B PIC32MX150F128B PIC32MX170F256B



Pin#	Full Pin Name
1	PGED1/AN2/C1IND/C2INB/C3IND/RPB0/RB0
2	PGEC1/AN3/C1INC/C2INA/RPB1/CTED12/RB1
3	AN4/C1INB/C2IND/RPB2/SDA2/CTED13/RB2
4	AN5/C1INA/C2INC/RTCC/RPB3/SCL2/RB3
5	Vss
6	OSC1/CLKI/RPA2/RA2
7	OSC2/CLKO/RPA3/PMA0/RA3
8	SOSCI/RPB4/RB4
9	SOSCO/RPA4/T1CK/CTED9/PMA1/RA4
10	VDD
11	PGED3/RPB5/PMD7/RB5
12	PGEC3/RPB6/PMD6/RB6
13	TDI/RPB7/CTED3/PMD5/INT0/RB7
14	TCK/RPB8/SCL1/CTED10/PMD4/RB8

Pin#	Full Pin Name
15	TDO/RPB9/SDA1/CTED4/PMD3/RB9
16	Vss
17	VCAP
18	PGED2/RPB10/CTED11/PMD2/RB10
19	PGEC2/TMS/RPB11/PMD1/RB11
20	AN12/PMD0/RB12
21	AN11/RPB13/CTPLS/PMRD/RB13
22	CVREFOUT/AN10/C3INB/RPB14/SCK1/CTED5/PMWR/RB14
23	AN9/C3INA/RPB15/SCK2/CTED6/PMCS1/RB15
24	AVss
25	AVDD
26	MCLR
27	VREF+/CVREF+/AN0/C3INC/RPA0/CTED1/RA0
28	VREF-/CVREF-/AN1/RPA1/CTED2/RA1


Note 1: The RPn pins can be used by remappable peripherals. See Table 1 for the available peripherals and Section 11.3 "Peripheral Pin Select" for restrictions.

- 2: Every I/O port pin (RAx-RCx) can be used as a change notification pin (CNAx-CNCx). See Section 11.0 "I/O Ports" for more information.
- 3: The metal plane at the bottom of the device is not connected to any pins and is recommended to be connected to Vss externally.
- 4: Shaded pins are 5V tolerant.

#### TABLE 6: PIN NAMES FOR 28-PIN USB DEVICES

### 28-PIN QFN (TOP VIEW)(1,2,3,4)

PIC32MX210F016B PIC32MX220F032B PIC32MX230F064B PIC32MX230F256B PIC32MX250F128B PIC32MX270F256B



Pin#	Full Pin Name
1	PGED1/AN2/C1IND/C2INB/C3IND/RPB0/PMD0/RB0
2	PGEC1/AN3/C1INC/C2INA/RPB1/CTED12/PMD1/RB1
3	AN4/C1INB/C2IND/RPB2/SDA2/CTED13/PMD2/RB2
4	AN5/C1INA/C2INC/RTCC/RPB3/SCL2/PMWR/RB3
5	Vss
6	OSC1/CLKI/RPA2/RA2
7	OSC2/CLKO/RPA3/PMA0/RA3
8	SOSCI/RPB4/RB4
9	SOSCO/RPA4/T1CK/CTED9/PMA1/RA4
10	VDD
11	TMS/RPB5/USBID/RB5
12	VBUS
13	TDI/RPB7/CTED3/PMD5/INT0/RB7
14	TCK/RPB8/SCL1/CTED10/PMD4/RB8

Pin#	Full Pin Name
15	TDO/RPB9/SDA1/CTED4/PMD3/RB9
16	Vss
17	VCAP
18	PGED2/RPB10/D+/CTED11/RB10
19	PGEC2/RPB11/D-/RB11
20	Vusb3v3
21	AN11/RPB13/CTPLS/PMRD/RB13
22	CVREFOUT/AN10/C3INB/RPB14/VBUSON/SCK1/CTED5/RB14
23	AN9/C3INA/RPB15/SCK2/CTED6/PMCS1/RB15
24	AVss
25	AVDD
26	MCLR
27	PGED3/VREF+/CVREF+/AN0/C3INC/RPA0/CTED1/PMD7/RA0
28	PGEC3/VREF-/CVREF-/AN1/RPA1/CTED2/PMD6/RA1


Note 1:

- 1: The RPn pins can be used by remappable peripherals. See Table 1 for the available peripherals and Section 11.3 "Peripheral Pin Select" for restrictions.
- 2: Every I/O port pin (RAx-RCx) can be used as a change notification pin (CNAx-CNCx). See Section 11.0 "I/O Ports" for more information.
- 3: The metal plane at the bottom of the device is not connected to any pins and is recommended to be connected to Vss externally.
- 4: Shaded pins are 5V tolerant.

#### TABLE 7: PIN NAMES FOR 36-PIN GENERAL PURPOSE DEVICES

**36-PIN VTLA (BOTTOM VIEW)** (1,2,3,5)

PIC32MX110F016C PIC32MX120F032C PIC32MX130F064C PIC32MX150F128C



Pin#	Full Pin Name
1	AN4/C1INB/C2IND/RPB2/SDA2/CTED13/RB2
2	AN5/C1INA/C2INC/RTCC/RPB3/SCL2/RB3
3	PGED4 <sup>(4)</sup> /AN6/RPC0/RC0
4	PGEC4 <sup>(4)</sup> /AN7/RPC1/RC1
5	VDD
6	Vss
7	OSC1/CLKI/RPA2/RA2
8	OSC2/CLKO/RPA3/PMA0/RA3
9	SOSCI/RPB4/RB4
10	SOSCO/RPA4/T1CK/CTED9/PMA1/RA4
11	RPC3/RC3
12	Vss
13	VDD
14	VDD
15	PGED3/RPB5/PMD7/RB5
16	PGEC3/RPB6/PMD6/RB6
17	TDI/RPB7/CTED3/PMD5/INT0/RB7
18	TCK/RPB8/SCL1/CTED10/PMD4/RB8

Pin#	Full Pin Name
19	TDO/RPB9/SDA1/CTED4/PMD3/RB9
20	RPC9/CTED7/RC9
21	Vss
22	VCAP
23	VDD
24	PGED2/RPB10/CTED11/PMD2/RB10
25	PGEC2/TMS/RPB11/PMD1/RB11
26	AN12/PMD0/RB12
27	AN11/RPB13/CTPLS/PMRD/RB13
28	CVREFOUT/AN10/C3INB/RPB14/SCK1/CTED5/PMWR/RB14
29	AN9/C3INA/RPB15/SCK2/CTED6/PMCS1/RB15
30	AVss
31	AVDD
32	MCLR
33	VREF+/CVREF+/AN0/C3INC/RPA0/CTED1/RA0
34	VREF-/CVREF-/AN1/RPA1/CTED2/RA1
35	PGED1/AN2/C1IND/C2INB/C3IND/RPB0/RB0
36	PGEC1/AN3/C1INC/C2INA/RPB1/CTED12/RB1


Note 1: The RPn pins can be used by remappable peripherals. See Table 1 for the available peripherals and Section 11.3 "Peripheral Pin Select" for restrictions.

- 2: Every I/O port pin (RAx-RCx) can be used as a change notification pin (CNAx-CNCx). See Section 11.0 "I/O Ports" for more information.
- 3: The metal plane at the bottom of the device is not connected to any pins and is recommended to be connected to Vss externally.
- 4: This pin function is not available on PIC32MX110F016C and PIC32MX120F032C devices.
- 5: Shaded pins are 5V tolerant.

#### TABLE 8: PIN NAMES FOR 36-PIN USB DEVICES

36-PIN VTLA (BOTTOM VIEW)(1,2,3,5)

PIC32MX210F016C PIC32MX220F032C PIC32MX230F064C PIC32MX250F128C



Pin#	Full Pin Name
1	AN4/C1INB/C2IND/RPB2/SDA2/CTED13/PMD2/RB2
2	AN5/C1INA/C2INC/RTCC/RPB3/SCL2/PMWR/RB3
3	PGED4 <sup>(4)</sup> /AN6/RPC0/RC0
4	PGEC4 <sup>(4)</sup> /AN7/RPC1/RC1
5	VDD
6	Vss
7	OSC1/CLKI/RPA2/RA2
8	OSC2/CLKO/RPA3/PMA0/RA3
9	SOSCI/RPB4/RB4
10	SOSCO/RPA4/T1CK/CTED9/PMA1/RA4
11	AN12/RPC3/RC3
12	Vss
13	VDD
14	VDD
15	TMS/RPB5/USBID/RB5
16	VBUS
17	TDI/RPB7/CTED3/PMD5/INT0/RB7
18	TCK/RPB8/SCL1/CTED10/PMD4/RB8


Pin#	Full Pin Name
19	TDO/RPB9/SDA1/CTED4/PMD3/RB9
20	RPC9/CTED7/RC9
21	Vss
22	VCAP
23	VDD
24	PGED2/RPB10/D+/CTED11/RB10
25	PGEC2/RPB11/D-/RB11
26	Vusb3v3
27	AN11/RPB13/CTPLS/PMRD/RB13
28	CVREFOUT/AN10/C3INB/RPB14/VBUSON/SCK1/CTED5/RB14
29	AN9/C3INA/RPB15/SCK2/CTED6/PMCS1/RB15
30	AVss
31	AVDD
32	MCLR
33	PGED3/VREF+/CVREF+/AN0/C3INC/RPA0/CTED1/PMD7/RA0
34	PGEC3/VREF-/CVREF-/AN1/RPA1/CTED2/PMD6/RA1
35	PGED1/AN2/C1IND/C2INB/C3IND/RPB0/PMD0/RB0
36	PGEC1/AN3/C1INC/C2INA/RPB1/CTED12/PMD1/RB1

- Note 1: The RPn pins can be used by remappable peripherals. See Table 1 for the available peripherals and Section 11.3 "Peripheral Pin Select" for restrictions
  - 2: Every I/O port pin (RAx-RCx) can be used as a change notification pin (CNAx-CNCx). See Section 11.0 "I/O Ports" for more information.
  - 3: The metal plane at the bottom of the device is not connected to any pins and is recommended to be connected to Vss externally.
  - 4: This pin function is not available on PIC32MX210F016C and PIC32MX120F032C devices.
  - 5: Shaded pins are 5V tolerant.

#### TABLE 9: PIN NAMES FOR 44-PIN GENERAL PURPOSE DEVICES

44-PIN QFN (TOP VIEW)(1,2,3,5)

PIC32MX110F016D PIC32MX120F032D PIC32MX130F064D PIC32MX130F256D PIC32MX150F128D PIC32MX170F256D



Pin#	Full Pin Name
1	RPB9/SDA1/CTED4/PMD3/RB9
2	RPC6/PMA1/RC6
3	RPC7/PMA0/RC7
4	RPC8/PMA5/RC8
5	RPC9/CTED7/PMA6/RC9
6	Vss
7	VCAP
8	PGED2/RPB10/CTED11/PMD2/RB10
9	PGEC2/RPB11/PMD1/RB11
10	AN12/PMD0/RB12
11	AN11/RPB13/CTPLS/PMRD/RB13
12	PGED4 <sup>(4)</sup> /TMS/PMA10/RA10
13	PGEC4 <sup>(4)</sup> /TCK/CTED8/PMA7/RA7
14	CVREFOUT/AN10/C3INB/RPB14/SCK1/CTED5/PMWR/RB14
15	AN9/C3INA/RPB15/SCK2/CTED6/PMCS1/RB15
16	AVss
17	AVDD
18	MCLR
19	VREF+/CVREF+/AN0/C3INC/RPA0/CTED1/RA0
20	VREF-/CVREF-/AN1/RPA1/CTED2/RA1
21	PGED1/AN2/C1IND/C2INB/C3IND/RPB0/RB0
22	PGEC1/AN3/C1INC/C2INA/RPB1/CTED12/RB1


Pin#	Full Pin Name
23	AN4/C1INB/C2IND/RPB2/SDA2/CTED13/RB2
24	AN5/C1INA/C2INC/RTCC/RPB3/SCL2/RB3
25	AN6/RPC0/RC0
26	AN7/RPC1/RC1
27	AN8/RPC2/PMA2/RC2
28	VDD
29	Vss
30	OSC1/CLKI/RPA2/RA2
31	OSC2/CLKO/RPA3/RA3
32	TDO/RPA8/PMA8/RA8
33	SOSCI/RPB4/RB4
34	SOSCO/RPA4/T1CK/CTED9/RA4
35	TDI/RPA9/PMA9/RA9
36	RPC3/RC3
37	RPC4/PMA4/RC4
38	RPC5/PMA3/RC5
39	Vss
40	VDD
41	PGED3/RPB5/PMD7/RB5
42	PGEC3/RPB6/PMD6/RB6
43	RPB7/CTED3/PMD5/INT0/RB7
44	RPB8/SCL1/CTED10/PMD4/RB8

- The RPn pins can be used by remappable peripherals. See Table 1 for the available peripherals and Section 11.3 "Peripheral Pin
- Every I/O port pin (RAx-RCx) can be used as a change notification pin (CNAx-CNCx). See Section 11.0 "I/O Ports" for more information.
- The metal plane at the bottom of the device is not connected to any pins and is recommended to be connected to Vss externally. This pin function is not available on PIC32MX110F016D and PIC32MX120F032D devices. 3:
- 4:
- Shaded pins are 5V tolerant.

#### **TABLE 10: PIN NAMES FOR 44-PIN USB DEVICES**

44-PIN QFN (TOP VIEW)(1,2,3,5)

PIC32MX210F016D PIC32MX220F032D PIC32MX230F064D PIC32MX230F256D PIC32MX250F128D PIC32MX270F256D



Pin#	Full Pin Name
1	RPB9/SDA1/CTED4/PMD3/RB9
2	RPC6/PMA1/RC6
3	RPC7/PMA0/RC7
4	RPC8/PMA5/RC8
5	RPC9/CTED7/PMA6/RC9
6	Vss
7	VCAP
8	PGED2/RPB10/D+/CTED11/RB10
9	PGEC2/RPB11/D-/RB11
10	Vusb3v3
11	AN11/RPB13/CTPLS/PMRD/RB13
12	PGED4/TMS/PMA10/RA10
13	PGEC4/TCK/CTED8/PMA7/RA7
14	CVREFOUT/AN10/C3INB/RPB14/VBUSON/SCK1/CTED5/RB14
15	AN9/C3INA/RPB15/SCK2/CTED6/PMCS1/RB15
16	AVss
17	AVDD
18	MCLR
19	PGED3/VREF+/CVREF+/AN0/C3INC/RPA0/CTED1/PMD7/RA0
20	PGEC3/VREF-/CVREF-/AN1/RPA1/CTED2/PMD6/RA1
21	PGED1/AN2/C1IND/C2INB/C3IND/RPB0/PMD0/RB0
22	PGEC1/AN3/C1INC/C2INA/RPB1/CTED12/PMD1/RB1


Pin#	Full Pin Name
23	AN4/C1INB/C2IND/RPB2/SDA2/CTED13/PMD2/RB2
24	AN5/C1INA/C2INC/RTCC/RPB3/SCL2/PMWR/RB3
25	AN6/RPC0/RC0
26	AN7/RPC1/RC1
27	AN8/RPC2/PMA2/RC2
28	VDD
29	Vss
30	OSC1/CLKI/RPA2/RA2
31	OSC2/CLKO/RPA3/RA3
32	TDO/RPA8/PMA8/RA8
33	SOSCI/RPB4/RB4
34	SOSCO/RPA4/T1CK/CTED9/RA4
35	TDI/RPA9/PMA9/RA9
36	AN12/RPC3/RC3
37	RPC4/PMA4/RC4
38	RPC5/PMA3/RC5
39	Vss
40	VDD
41	RPB5/USBID/RB5
42	VBUS
43	RPB7/CTED3/PMD5/INT0/RB7
44	RPB8/SCL1/CTED10/PMD4/RB8

- The RPn pins can be used by remappable peripherals. See Table 1 for the available peripherals and Section 11.3 "Peripheral Pin
- Every I/O port pin (RAx-RCx) can be used as a change notification pin (CNAx-CNCx). See Section 11.0 "I/O Ports" for more information. The metal plane at the bottom of the device is not connected to any pins and is recommended to be connected to Vss externally.
- 3:
- This pin function is not available on PIC32MX110F016D and PIC32MX120F032D devices.
- Shaded pins are 5V tolerant.

#### TABLE 11: PIN NAMES FOR 44-PIN GENERAL PURPOSE DEVICES

### 44-PIN TQFP (TOP VIEW)(1,2,3,5)

PIC32MX110F016D PIC32MX120F032D PIC32MX130F064D PIC32MX130F256D PIC32MX150F128D PIC32MX170F256D



Pin#	Full Pin Name
1	RPB9/SDA1/CTED4/PMD3/RB9
2	RPC6/PMA1/RC6
3	RPC7/PMA0/RC7
4	RPC8/PMA5/RC8
5	RPC9/CTED7/PMA6/RC9
6	Vss
7	VCAP
8	PGED2/RPB10/CTED11/PMD2/RB10
9	PGEC2/RPB11/PMD1/RB11
10	AN12/PMD0/RB12
11	AN11/RPB13/CTPLS/PMRD/RB13
12	PGED4 <sup>(4)</sup> /TMS/PMA10/RA10
13	PGEC4 <sup>(4)</sup> /TCK/CTED8/PMA7/RA7
14	CVREFOUT/AN10/C3INB/RPB14/SCK1/CTED5/PMWR/RB14
15	AN9/C3INA/RPB15/SCK2/CTED6/PMCS1/RB15
16	AVss
17	AVDD
18	MCLR
19	VREF+/CVREF+/AN0/C3INC/RPA0/CTED1/RA0
20	VREF-/CVREF-/AN1/RPA1/CTED2/RA1
21	PGED1/AN2/C1IND/C2INB/C3IND/RPB0/RB0
22	PGEC1/AN3/C1INC/C2INA/RPB1/CTED12/RB1


Pin#	Full Pin Name
23	AN4/C1INB/C2IND/RPB2/SDA2/CTED13/RB2
24	AN5/C1INA/C2INC/RTCC/RPB3/SCL2/RB3
25	AN6/RPC0/RC0
26	AN7/RPC1/RC1
27	AN8/RPC2/PMA2/RC2
28	VDD
29	Vss
30	OSC1/CLKI/RPA2/RA2
31	OSC2/CLKO/RPA3/RA3
32	TDO/RPA8/PMA8/RA8
33	SOSCI/RPB4/RB4
34	SOSCO/RPA4/T1CK/CTED9/RA4
35	TDI/RPA9/PMA9/RA9
36	RPC3/RC3
37	RPC4/PMA4/RC4
38	RPC5/PMA3/RC5
39	Vss
40	VDD
41	PGED3/RPB5/PMD7/RB5
42	PGEC3/RPB6/PMD6/RB6
43	RPB7/CTED3/PMD5/INT0/RB7
44	RPB8/SCL1/CTED10/PMD4/RB8

- 1: The RPn pins can be used by remappable peripherals. See Table 1 for the available peripherals and Section 11.3 "Peripheral Pin
- 2: Every I/O port pin (RAx-RCx) can be used as a change notification pin (CNAx-CNCx). See Section 11.0 "I/O Ports" for more information.
- 3: The metal plane at the bottom of the device is not connected to any pins and is recommended to be connected to Vss externally.
- 4: This pin function is not available on PIC32MX110F016D and PIC32MX120F032D devices.
- 5: Shaded pins are 5V tolerant.

#### **TABLE 12: PIN NAMES FOR 44-PIN USB DEVICES**

44-PIN TQFP (TOP VIEW)(1,2,3,5)

PIC32MX210F016D PIC32MX220F032D PIC32MX230F064D PIC32MX230F256D PIC32MX250F128D PIC32MX270F256D



Pin#	Full Pin Name
1	RPB9/SDA1/CTED4/PMD3/RB9
2	RPC6/PMA1/RC6
3	RPC7/PMA0/RC7
4	RPC8/PMA5/RC8
5	RPC9/CTED7/PMA6/RC9
6	Vss
7	VCAP
8	PGED2/RPB10/D+/CTED11/RB10
9	PGEC2/RPB11/D-/RB11
10	VUSB3V3
11	AN11/RPB13/CTPLS/PMRD/RB13
12	PGED4 <sup>(4)</sup> /TMS/PMA10/RA10
13	PGEC4 <sup>(4)</sup> /TCK/CTED8/PMA7/RA7
14	CVREFOUT/AN10/C3INB/RPB14/VBUSON/SCK1/CTED5/RB14
15	AN9/C3INA/RPB15/SCK2/CTED6/PMCS1/RB15
16	AVss
17	AVDD
18	MCLR
19	PGED3/VREF+/CVREF+/AN0/C3INC/RPA0/CTED1/PMD7/RA0
20	PGEC3/VREF-/CVREF-/AN1/RPA1/CTED2/PMD6/RA1
21	PGED1/AN2/C1IND/C2INB/C3IND/RPB0/PMD0/RB0
22	PGEC1/AN3/C1INC/C2INA/RPB1/CTED12/PMD1/RB1


Pin#	Full Pin Name
23	AN4/C1INB/C2IND/RPB2/SDA2/CTED13/PMD2/RB2
24	AN5/C1INA/C2INC/RTCC/RPB3/SCL2/PMWR/RB3
25	AN6/RPC0/RC0
26	AN7/RPC1/RC1
27	AN8/RPC2/PMA2/RC2
28	VDD
29	Vss
30	OSC1/CLKI/RPA2/RA2
31	OSC2/CLKO/RPA3/RA3
32	TDO/RPA8/PMA8/RA8
33	SOSCI/RPB4/RB4
34	SOSCO/RPA4/T1CK/CTED9/RA4
35	TDI/RPA9/PMA9/RA9
36	AN12/RPC3/RC3
37	RPC4/PMA4/RC4
38	RPC5/PMA3/RC5
39	Vss
40	VDD
41	RPB5/USBID/RB5
42	VBUS
43	RPB7/CTED3/PMD5/INT0/RB7
44	RPB8/SCL1/CTED10/PMD4/RB8

- The RPn pins can be used by remappable peripherals. See Table 1 for the available peripherals and Section 11.3 "Peripheral Pin
- Every I/O port pin (RAx-RCx) can be used as a change notification pin (CNAx-CNCx). See Section 11.0 "I/O Ports" for more information.
- The metal plane at the bottom of the device is not connected to any pins and is recommended to be connected to Vss externally. This pin function is not available on PIC32MX210F016D and PIC32MX220F032D devices. 3:
- Shaded pins are 5V tolerant.

#### TABLE 13: PIN NAMES FOR 44-PIN GENERAL PURPOSE DEVICES

#### 44-PIN VTLA (BOTTOM VIEW)(1,2,3,5)

PIC32MX110F016D PIC32MX120F032D PC32MX130F064D PIC32MX130F256D PIC32MX150F128D PIC32MX170F256D



Pin#	Full Pin Name
1	RPB9/SDA1/CTED4/PMD3/RB9
2	RPC6/PMA1/RC6
3	RPC7/PMA0/RC7
4	RPC8/PMA5/RC8
5	RPC9/CTED7/PMA6/RC9
6	Vss
7	VCAP
8	PGED2/RPB10/CTED11/PMD2/RB10
9	PGEC2/RPB11/PMD1/RB11
10	AN12/PMD0/RB12
11	AN11/RPB13/CTPLS/PMRD/RB13
12	PGED4 <sup>(4)</sup> /TMS/PMA10/RA10
13	PGEC4 <sup>(4)</sup> /TCK/CTED8/PMA7/RA7
14	CVREFOUT/AN10/C3INB/RPB14/SCK1/CTED5/PMWR/RB14
15	AN9/C3INA/RPB15/SCK2/CTED6/PMCS1/RB15
16	AVss
17	AVDD
18	MCLR
19	VREF+/CVREF+/AN0/C3INC/RPA0/CTED1/RA0
20	VREF-/CVREF-/AN1/RPA1/CTED2/RA1
21	PGED1/AN2/C1IND/C2INB/C3IND/RPB0/RB0
22	PGEC1/AN3/C1INC/C2INA/RPB1/CTED12/RB1

Pin#	Full Pin Name
23	AN4/C1INB/C2IND/RPB2/SDA2/CTED13/RB2
24	AN5/C1INA/C2INC/RTCC/RPB3/SCL2/RB3
25	AN6/RPC0/RC0
26	AN7/RPC1/RC1
27	AN8/RPC2/PMA2/RC2
28	VDD
29	Vss
30	OSC1/CLKI/RPA2/RA2
31	OSC2/CLKO/RPA3/RA3
32	TDO/RPA8/PMA8/RA8
33	SOSCI/RPB4/RB4
34	SOSCO/RPA4/T1CK/CTED9/RA4
35	TDI/RPA9/PMA9/RA9
36	RPC3/RC3
37	RPC4/PMA4/RC4
38	RPC5/PMA3/RC5
39	Vss
40	VDD
41	PGED3/RPB5/PMD7/RB5
42	PGEC3/RPB6/PMD6/RB6
43	RPB7/CTED3/PMD5/INT0/RB7
44	RPB8/SCI 1/CTFD10/PMD4/RB8


Note 1: The RPn pins can be used by remappable peripherals. See Table 1 for the available peripherals and Section 11.3 "Peripheral Pin Select" for restrictions.

- 2: Every I/O port pin (RAx-RCx) can be used as a change notification pin (CNAx-CNCx). See Section 11.0 "I/O Ports" for more information.
- 3: The metal plane at the bottom of the device is not connected to any pins and is recommended to be connected to Vss externally.
- 4: This pin function is not available on PIC32MX110F016D and PIC32MX120F032D devices.
- 5: Shaded pins are 5V tolerant.

#### **TABLE 14: PIN NAMES FOR 44-PIN USB DEVICES**

#### 44-PIN VTLA (BOTTOM VIEW)(1,2,3,5)

PIC32MX210F016D PIC32MX220F032D PIC32MX230F064D PIC32MX230F256D PIC32MX250F128D PIC32MX270F256D



Pin#	Full Pin Name
1	RPB9/SDA1/CTED4/PMD3/RB9
2	RPC6/PMA1/RC6
3	RPC7/PMA0/RC7
4	RPC8/PMA5/RC8
5	RPC9/CTED7/PMA6/RC9
6	Vss
7	VCAP
8	PGED2/RPB10/D+/CTED11/RB10
9	PGEC2/RPB11/D-/RB11
10	Vusbava
11	AN11/RPB13/CTPLS/PMRD/RB13
12	PGED4 <sup>(4)</sup> /TMS/PMA10/RA10
13	PGEC4 <sup>(4)</sup> /TCK/CTED8/PMA7/RA7
14	CVREFOUT/AN10/C3INB/RPB14/VBUSON/SCK1/CTED5/RB14
15	AN9/C3INA/RPB15/SCK2/CTED6/PMCS1/RB15
16	AVss
17	AVDD
18	MCLR
19	PGED3/VREF+/CVREF+/AN0/C3INC/RPA0/CTED1/PMD7/RA0
20	PGEC3/VREF-/CVREF-/AN1/RPA1/CTED2/PMD6/RA1
21	PGED1/AN2/C1IND/C2INB/C3IND/RPB0/PMD0/RB0
22	PGEC1/AN3/C1INC/C2INA/RPB1/CTED12/PMD1/RB1

Pin#	Full Pin Name
23	AN4/C1INB/C2IND/RPB2/SDA2/CTED13/PMD2/RB2
24	AN5/C1INA/C2INC/RTCC/RPB3/SCL2/PMWR/RB3
25	AN6/RPC0/RC0
26	AN7/RPC1/RC1
27	AN8/RPC2/PMA2/RC2
28	VDD
29	Vss
30	OSC1/CLKI/RPA2/RA2
31	OSC2/CLKO/RPA3/RA3
32	TDO/RPA8/PMA8/RA8
33	SOSCI/RPB4/RB4
34	SOSCO/RPA4/T1CK/CTED9/RA4
35	TDI/RPA9/PMA9/RA9
36	AN12/RPC3/RC3
37	RPC4/PMA4/RC4
38	RPC5/PMA3/RC5
39	Vss
40	VDD
41	RPB5/USBID/RB5
42	VBUS
43	RPB7/CTED3/PMD5/INT0/RB7
44	RPB8/SCL1/CTED10/PMD4/RB8

- The RPn pins can be used by remappable peripherals. See Table 1 for the available peripherals and Section 11.3 "Peripheral Pin
- Every I/O port pin (RAx-RCx) can be used as a change notification pin (CNAx-CNCx). See Section 11.0 "I/O Ports" for more information.
- The metal plane at the bottom of the device is not connected to any pins and is recommended to be connected to Vss externally. This pin function is not available on PIC32MX210F016D and PIC32MX220F032D devices. 3:
- Shaded pins are 5V tolerant.

#### **Table of Contents**

1.0	Device Overview	19
2.0	Guidelines for Getting Started with 32-bit MCUs	27
3.0	CPU	37
4.0	Memory Organization	41
5.0	Flash Program Memory	57
6.0	Resets	63
7.0	Interrupt Controller	67
8.0	Oscillator Configuration	77
9.0	Direct Memory Access (DMA) Controller	87
10.0	USB On-The-Go (OTG)	107
11.0	I/O Ports	131
12.0	Timer1	147
13.0	Timer2/3, Timer4/5	151
14.0	Watchdog Timer (WDT)	157
15.0	Input Capture	161
16.0	Output Compare	165
	Serial Peripheral Interface (SPI)	
18.0	Inter-Integrated Circuit (I <sup>2</sup> C)	177
19.0	Universal Asynchronous Receiver Transmitter (UART)	185
20.0	Parallel Master Port (PMP)	193
21.0	Real-Time Clock and Calendar (RTCC)	203
22.0	10-bit Analog-to-Digital Converter (ADC)	213
23.0	Comparator	223
24.0	Comparator Voltage Reference (CVREF)	227
25.0	Charge Time Measurement Unit (CTMU)	231
26.0	Power-Saving Features	237
27.0	Special Features	243
28.0	Instruction Set	255
29.0	Development Support	257
30.0	Electrical Characteristics	261
31.0	50 MHz Electrical Characteristics	305
32.0	DC and AC Device Characteristics Graphs	311
33.0	Packaging Information	315
The I	Microchip Web Site	
Custo	tomer Change Notification Service	
Custo	tomer Support	347
Prod	duct Identification System	348

#### TO OUR VALUED CUSTOMERS

It is our intention to provide our valued customers with the best documentation possible to ensure successful use of your Microchip products. To this end, we will continue to improve our publications to better suit your needs. Our publications will be refined and enhanced as new volumes and updates are introduced.

If you have any questions or comments regarding this publication, please contact the Marketing Communications Department via E-mail at docerrors@microchip.com. We welcome your feedback.

#### **Most Current Data Sheet**

To obtain the most up-to-date version of this data sheet, please register at our Worldwide Web site at:

http://www.microchip.com

You can determine the version of a data sheet by examining its literature number found on the bottom outside corner of any page. The last character of the literature number is the version number, (e.g., DS30000000A is version A of document DS30000000).

#### **Errata**

An errata sheet, describing minor operational differences from the data sheet and recommended workarounds, may exist for current devices. As device/documentation issues become known to us, we will publish an errata sheet. The errata will specify the revision of silicon and revision of document to which it applies.

To determine if an errata sheet exists for a particular device, please check with one of the following:

- · Microchip's Worldwide Web site; http://www.microchip.com
- · Your local Microchip sales office (see last page)

When contacting a sales office, please specify which device, revision of silicon and data sheet (include literature number) you are using.

#### **Customer Notification System**

Register on our web site at www.microchip.com to receive the most current information on all of our products.

#### Referenced Sources

This device data sheet is based on the following individual chapters of the "PIC32 Family Reference Manual". These documents should be considered as the general reference for the operation of a particular module or device feature.

Note:

To access the following documents, refer to the *Documentation* > *Reference Manuals* section of the Microchip PIC32 website: http://www.microchip.com/pic32

- Section 1. "Introduction" (DS60001127)
- Section 2. "CPU" (DS60001113)
- Section 3. "Memory Organization" (DS60001115)
- · Section 5. "Flash Program Memory" (DS60001121)
- Section 6. "Oscillator Configuration" (DS60001112)
- Section 7. "Resets" (DS60001118)
- Section 8. "Interrupt Controller" (DS60001108)
- Section 9. "Watchdog Timer and Power-up Timer" (DS60001114)
- Section 10. "Power-Saving Features" (DS60001130)
- Section 12. "I/O Ports" (DS60001120)
- Section 13. "Parallel Master Port (PMP)" (DS60001128)
- Section 14. "Timers" (DS60001105)
- Section 15. "Input Capture" (DS60001122)
- Section 16. "Output Compare" (DS60001111)
- Section 17. "10-bit Analog-to-Digital Converter (ADC)" (DS60001104)
- **Section 19. "Comparator"** (DS60001110)
- Section 20. "Comparator Voltage Reference (CVREF)" (DS60001109)
- Section 21. "Universal Asynchronous Receiver Transmitter (UART)" (DS60001107)
- Section 23. "Serial Peripheral Interface (SPI)" (DS60001106)
- Section 24. "Inter-Integrated Circuit (I<sup>2</sup>C)" (DS60001116)
- Section 27. "USB On-The-Go (OTG)" (DS60001126)
- Section 29. "Real-Time Clock and Calendar (RTCC)" (DS60001125)
- Section 31. "Direct Memory Access (DMA) Controller" (DS60001117)
- Section 32. "Configuration" (DS60001124)
- Section 33. "Programming and Diagnostics" (DS60001129)
- Section 37. "Charge Time Measurement Unit (CTMU)" (DS60001167)

#### 1.0 DEVICE OVERVIEW

Note:

This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To complement the information in this data sheet, refer to documents listed in the *Documentation* > *Reference Manual* section of the Microchip PIC32 web site (www.microchip.com/pic32).

This document contains device-specific information for PIC32MX1XX/2XX 28/36/44-pin Family of devices.

Figure 1-1 illustrates a general block diagram of the core and peripheral modules in the PIC32MX1XX/2XX 28/36/44-pin Family of devices.

Table 1-1 lists the functions of the various pins shown in the pinout diagrams.

#### FIGURE 1-1: BLOCK DIAGRAM




TABLE 1-1: PINOUT I/O DESCRIPTIONS

		Pin Nu	mber <sup>(1)</sup>					
Pin Name	28-pin QFN	28-pin SSOP/ SPDIP/ SOIC	36-pin VTLA	44-pin QFN/ TQFP/ VTLA	QFN/ Type Type		Description	
AN0	27	2	33	19	I	Analog	Analog input channels.	
AN1	28	3	34	20	I	Analog		
AN2	1	4	35	21	I	Analog		
AN3	2	5	36	22	I	Analog		
AN4	3	6	1	23	ı	Analog		
AN5	4	7	2	24	ı	Analog		
AN6	_	_	3	25	I	Analog		
AN7	_	_	4	26	ı	Analog		
AN8	_	_	_	27	ı	Analog		
AN9	23	26	29	15	I	Analog		
AN10	22	25	28	14	ı	Analog		
AN11	21	24	27	11	ı	Analog		
AN12	20 <sup>(2)</sup>	23 <sup>(2)</sup>	26 <sup>(2)</sup>	10 <sup>(2)</sup>		Analog		
		-	11 <sup>(3)</sup>	36 <sup>(3)</sup>		_		
CLKI	6	9	7	30	I	ST/CMOS	External clock source input. Always associated with OSC1 pin function.	
CLKO	7	10	8	31	0	_	Oscillator crystal output. Connects to crystal or resonator in Crystal Oscillator mode. Optionally functions as CLKO in RC and EC modes. Always associated with OSC2 pin function.	
OSC1	6	9	7	30	I	ST/CMOS	Oscillator crystal input. ST buffer when configured in RC mode; CMOS otherwise.	
OSC2	7	10	8	31	0	_	Oscillator crystal output. Connects to crystal or resonator in Crystal Oscillator mode. Optionally functions as CLKO in RC and EC modes.	
SOSCI	8	11	9	33	-	ST/CMOS	32.768 kHz low-power oscillator crystal input; CMOS otherwise.	
SOSCO	9	12	10	34	0	_	32.768 kHz low-power oscillator crystal output.	
REFCLKI	PPS	PPS	PPS	PPS	I	ST	Reference Input Clock	
REFCLKO	PPS	PPS	PPS	PPS	0	_	Reference Output Clock	
IC1	PPS	PPS	PPS	PPS	I	ST	Capture Inputs 1-5	
IC2	PPS	PPS	PPS	PPS	I	ST		
IC3	PPS	PPS	PPS	PPS	I	ST		
IC4	PPS	PPS	PPS	PPS	I	ST		
IC5	PPS	PPS	PPS	PPS	I	ST		

Legend: CMOS = CMOS compatible input or output ST = Schmitt Trigger input with CMOS levels TTL = TTL input buffer Analog = Analog input P = Power O = Output I = Input PPS = Peripheral Pin Select <math>--= N/A

Note 1: Pin numbers are provided for reference only. See the "Pin Diagrams" section for device pin availability.

2: Pin number for PIC32MX1XX devices only.

TABLE 1-1: PINOUT I/O DESCRIPTIONS (CONTINUED)

Pin Name         28-pin QFN         36-pin SSOP/ SPDIP/ SPDIP/ SOIC         36-pin VTLA         Pin QFN/ TQFP/ VTLA         Buffer Type         Description           OC1         PPS         PPS         PPS         PPS         O         —         Output Compare Output 1         Output Compare Output 2         Output Compare Output 2         Output Compare Output 3         Output Compare Output 3         Output Compare Output 4         Output Compare Output 4         Output Compare Output 4         Output Compare Output 5         Output Compare Output 5         Output Compare Fault A II         Output Compare Fault A II         Output Compare Fault A II         Output Compare Fault B II         Output Compare Fault B II         INTO         13         16         17         43         I         ST         External Interrupt 0         INT1         PPS         PPS         PPS         IPS	
OC2PPSPPSPPSPPSO—Output Compare Output 2OC3PPSPPSPPSPPSO—Output Compare Output 3OC4PPSPPSPPSPPSO—Output Compare Output 4OC5PPSPPSPPSPPSO—Output Compare Output 5OCFAPPSPPSPPSPPSISTOutput Compare Fault A IIOCFBPPSPPSPPSISTOutput Compare Fault B IINT013161743ISTExternal Interrupt 0INT1PPSPPSPPSISTExternal Interrupt 1INT2PPSPPSPPSISTExternal Interrupt 2INT3PPSPPSPPSISTExternal Interrupt 3INT4PPSPPSPPSPPSISTExternal Interrupt 4RA02723319I/OSTPORTA is a bidirectional I/O	
OC3PPSPPSPPSPPSO—Output Compare Output 3OC4PPSPPSPPSPPSO—Output Compare Output 4OC5PPSPPSPPSPPSO—Output Compare Output 5OCFAPPSPPSPPSPPSISTOutput Compare Fault A IIOCFBPPSPPSPPSPPSISTOutput Compare Fault B IINT013161743ISTExternal Interrupt 0INT1PPSPPSPPSPPSISTExternal Interrupt 1INT2PPSPPSPPSISTExternal Interrupt 2INT3PPSPPSPPSISTExternal Interrupt 3INT4PPSPPSPPSISTExternal Interrupt 4RA02723319I/OSTPORTA is a bidirectional I/O	
OC4         PPS         PPS         PPS         O         —         Output Compare Output 4           OC5         PPS         PPS         PPS         O         —         Output Compare Output 5           OCFA         PPS         PPS         PPS         I         ST         Output Compare Fault A Ir           OCFB         PPS         PPS         PPS         I         ST         Output Compare Fault B Ir           INT0         13         16         17         43         I         ST         External Interrupt 0           INT1         PPS         PPS         PPS         PPS         I         ST         External Interrupt 1           INT2         PPS         PPS         PPS         I         ST         External Interrupt 2           INT3         PPS         PPS         PPS         I         ST         External Interrupt 3           INT4         PPS         PPS         PPS         I         ST         External Interrupt 4           RA0         27         2         33         19         I/O         ST         PORTA is a bidirectional I/O	•
OC5 PPS PPS PPS PPS I ST Output Compare Output 5 OCFA PPS PPS PPS PPS I ST Output Compare Fault A II OCFB PPS PPS PPS PPS I ST Output Compare Fault B I INTO 13 16 17 43 I ST External Interrupt 0 INT1 PPS PPS PPS PPS I ST External Interrupt 1 INT2 PPS PPS PPS PPS I ST External Interrupt 2 INT3 PPS PPS PPS PPS I ST External Interrupt 3 INT4 PPS PPS PPS PPS I ST External Interrupt 4 RAO 27 2 33 19 I/O ST PORTA is a bidirectional II	
OCFA         PPS         PPS         PPS         I         ST         Output Compare Fault A Incompare Fault A Incompare Fault A Incompare Fault B Inco	1
OCFB         PPS         PPS         PPS         I         ST         Output Compare Fault B I           INT0         13         16         17         43         I         ST         External Interrupt 0           INT1         PPS         PPS         PPS         I         ST         External Interrupt 1           INT2         PPS         PPS         PPS         I         ST         External Interrupt 2           INT3         PPS         PPS         PPS         I         ST         External Interrupt 3           INT4         PPS         PPS         PPS         I         ST         External Interrupt 4           RA0         27         2         33         19         I/O         ST         PORTA is a bidirectional I/O	
INTO         13         16         17         43         I         ST         External Interrupt 0           INT1         PPS         PPS         PPS         I         ST         External Interrupt 1           INT2         PPS         PPS         PPS         I         ST         External Interrupt 2           INT3         PPS         PPS         PPS         I         ST         External Interrupt 3           INT4         PPS         PPS         PPS         I         ST         External Interrupt 4           RA0         27         2         33         19         I/O         ST         PORTA is a bidirectional I/O	nput
INT1         PPS         PPS         PPS         I         ST         External Interrupt 1           INT2         PPS         PPS         PPS         I         ST         External Interrupt 2           INT3         PPS         PPS         PPS         I         ST         External Interrupt 3           INT4         PPS         PPS         PPS         I         ST         External Interrupt 4           RA0         27         2         33         19         I/O         ST         PORTA is a bidirectional I/O	nput
INT2         PPS         PPS         PPS         I         ST         External Interrupt 2           INT3         PPS         PPS         PPS         I         ST         External Interrupt 3           INT4         PPS         PPS         PPS         I         ST         External Interrupt 4           RA0         27         2         33         19         I/O         ST         PORTA is a bidirectional I/O	
INT3 PPS PPS PPS I ST External Interrupt 3 INT4 PPS PPS PPS PPS I ST External Interrupt 4 RA0 27 2 33 19 I/O ST PORTA is a bidirectional I/O	
INT4 PPS PPS PPS I ST External Interrupt 4 RA0 27 2 33 19 I/O ST PORTA is a bidirectional I/O	
RA0 27 2 33 19 I/O ST PORTA is a bidirectional I/O	
RA1 28 3 34 20 1/O ST	O port
	•
RA2 6 9 7 30 I/O ST	
RA3 7 10 8 31 I/O ST	
RA4 9 12 10 34 I/O ST	
RA7 — — 13 I/O ST	
RA8 — — 32 I/O ST	
RA9 — — 35 I/O ST	
RA10 — — 12 I/O ST	
RB0 1 4 35 21 I/O ST PORTB is a bidirectional I	/O port
RB1 2 5 36 22 I/O ST	
RB2 3 6 1 23 I/O ST	
RB3 4 7 2 24 I/O ST	
RB4 8 11 9 33 I/O ST	
RB5 11 14 15 41 I/O ST	
RB6 12 <sup>(2)</sup> 15 <sup>(2)</sup> 16 <sup>(2)</sup> 42 <sup>(2)</sup> I/O ST	
RB7 13 16 17 43 I/O ST	
RB8 14 17 18 44 I/O ST	
RB9 15 18 19 1 I/O ST	
RB10 18 21 24 8 I/O ST	
RB11 19 22 25 9 I/O ST	
RB12 20 <sup>(2)</sup> 23 <sup>(2)</sup> 26 <sup>(2)</sup> 10 <sup>(2)</sup> I/O ST	
RB13 21 24 27 11 I/O ST	
RB14 22 25 28 14 I/O ST	
RB15 23 26 29 15 I/O ST	

**Legend:** CMOS = CMOS compatible input or output ST = Schmitt Trigger input with CMOS levels

Analog = Analog input O = Output P = Power I = Input

TTL = TTL input buffer

PPS = Peripheral Pin Select

— = N/A

Note 1: Pin numbers are provided for reference only. See the "Pin Diagrams" section for device pin availability.

- 2: Pin number for PIC32MX1XX devices only.
- 3: Pin number for PIC32MX2XX devices only.

TABLE 1-1: PINOUT I/O DESCRIPTIONS (CONTINUED)

		Pin Nu	mber <sup>(1)</sup>				
Pin Name	28-pin QFN	28-pin SSOP/ SPDIP/ SOIC	36-pin VTLA	44-pin QFN/ TQFP/ VTLA	Pin Type	Buffer Type	Description
RC0	_	_	3	25	I/O	ST	PORTC is a bidirectional I/O port
RC1	_	_	4	26	I/O	ST	
RC2	_	_		27	I/O	ST	
RC3	_	_	11	36	I/O	ST	
RC4	_	_	_	37	I/O	ST	
RC5	_	_		38	I/O	ST	
RC6		_	_	2	I/O	ST	
RC7		_	_	3	I/O	ST	
RC8	_	_	_	4	I/O	ST	
RC9	_	_	20	5	I/O	ST	
T1CK	9	12	10	34	I	ST	Timer1 external clock input
T2CK	PPS	PPS	PPS	PPS	I	ST	Timer2 external clock input
T3CK	PPS	PPS	PPS	PPS	I	ST	Timer3 external clock input
T4CK	PPS	PPS	PPS	PPS	I	ST	Timer4 external clock input
T5CK	PPS	PPS	PPS	PPS	I	ST	Timer5 external clock input
U1CTS	PPS	PPS	PPS	PPS	I	ST	UART1 clear to send
U1RTS	PPS	PPS	PPS	PPS	0	_	UART1 ready to send
U1RX	PPS	PPS	PPS	PPS	I	ST	UART1 receive
U1TX	PPS	PPS	PPS	PPS	0	_	UART1 transmit
U2CTS	PPS	PPS	PPS	PPS	ı	ST	UART2 clear to send
U2RTS	PPS	PPS	PPS	PPS	0	_	UART2 ready to send
U2RX	PPS	PPS	PPS	PPS	I	ST	UART2 receive
U2TX	PPS	PPS	PPS	PPS	0	_	UART2 transmit
SCK1	22	25	28	14	I/O	ST	Synchronous serial clock input/output for SPI1
SDI1	PPS	PPS	PPS	PPS	I	ST	SPI1 data in
SDO1	PPS	PPS	PPS	PPS	0	_	SPI1 data out
SS1	PPS	PPS	PPS	PPS	I/O	ST	SPI1 slave synchronization or frame pulse I/O
SCK2	23	26	29	15	I/O	ST	Synchronous serial clock input/output for SPI2
SDI2	PPS	PPS	PPS	PPS	I	ST	SPI2 data in
SDO2	PPS	PPS	PPS	PPS	0	_	SPI2 data out
SS2	PPS	PPS	PPS	PPS	I/O	ST	SPI2 slave synchronization or frame pulse I/O
SCL1	14	17	18	44	I/O	ST	Synchronous serial clock input/output for I2C1

**Legend:** CMOS = CMOS compatible input or output

ST = Schmitt Trigger input with CMOS levels

TTL = TTL input buffer

Analog = Analog input

P = Power I = Input

O = Output PPS = Peripheral Pin Select

n Select — = N/A

Note 1: Pin numbers are provided for reference only. See the "Pin Diagrams" section for device pin availability.

- 2: Pin number for PIC32MX1XX devices only.
- 3: Pin number for PIC32MX2XX devices only.

**TABLE 1-1:** PINOUT I/O DESCRIPTIONS (CONTINUED)

		Pin Nu	mber <sup>(1)</sup>	-			
Pin Name	28-pin QFN	28-pin SSOP/ SPDIP/ SOIC	36-pin VTLA	44-pin QFN/ TQFP/ VTLA	Pin Type	Buffer Type	Description
SDA1	15	18	19	1	I/O	ST	Synchronous serial data input/output for I2C1
SCL2	4	7	2	24	I/O	ST	Synchronous serial clock input/output for I2C2
SDA2	3	6	1	23	I/O	ST	Synchronous serial data input/output for I2C2
TMS	19 <sup>(2)</sup> 11 <sup>(3)</sup>	22 <sup>(2)</sup> 14 <sup>(3)</sup>	25 <sup>(2)</sup> 15 <sup>(3)</sup>	12	I	ST	JTAG Test mode select pin
TCK	14	17	18	13	I	ST	JTAG test clock input pin
TDI	13	16	17	35	0		JTAG test data input pin
TDO	15	18	19	32	0		JTAG test data output pin
RTCC	4	7	2	24	0	ST	Real-Time Clock alarm output
CVREF-	28	3	34	20	I	Analog	Comparator Voltage Reference (low)
CVREF+	27	2	33	19	I	Analog	Comparator Voltage Reference (high)
CVREFOUT	22	25	28	14	0	Analog	Comparator Voltage Reference output
C1INA	4	7	2	24	I	Analog	Comparator Inputs
C1INB	3	6	1	23	I	Analog	
C1INC	2	5	36	22	I	Analog	
C1IND	1	4	35	21	I	Analog	
C2INA	2	5	36	22	I	Analog	
C2INB	1	4	35	21	Ι	Analog	
C2INC	4	7	2	24	Ι	Analog	
C2IND	3	6	1	23	I	Analog	
C3INA	23	26	29	15	I	Analog	
C3INB	22	25	28	14	- 1	Analog	
C3INC	27	2	33	19	I	Analog	
C3IND	1	4	35	21	I	Analog	
C10UT	PPS	PPS	PPS	PPS	0	_	Comparator Outputs
C2OUT	PPS	PPS	PPS	PPS	0	_	
C3OUT	PPS	PPS	PPS	PPS	0	_	Analogians

Legend: CMOS = CMOS compatible input or output

ST = Schmitt Trigger input with CMOS levels

TTL = TTL input buffer

Analog = Analog input

P = Power

O = Output

I = Input --- = N/A

PPS = Peripheral Pin Select Note 1: Pin numbers are provided for reference only. See the "Pin Diagrams" section for device pin availability.

2: Pin number for PIC32MX1XX devices only.

**TABLE 1-1:** PINOUT I/O DESCRIPTIONS (CONTINUED)

		Pin Nu	mber <sup>(1)</sup>					
Pin Name	Pin Name 28-pin SSOP QFN SPDIF		28-pin		Pin Type	Buffer Type	Description	
PMA0	7	10	8	3	I/O	TTL/ST	Parallel Master Port Address bit 0 input (Buffered Slave modes) and output (Master modes)	
PMA1	9	12	10	2	I/O	TTL/ST	Parallel Master Port Address bit 1 input (Buffered Slave modes) and output (Master modes)	
PMA2		_		27	0	_	Parallel Master Port address	
PMA3		_	_	38	0	_	(Demultiplexed Master modes)	
PMA4		_		37	0	_		
PMA5		_	_	4	0	_		
PMA6		_	_	5	0	_		
PMA7		_	_	13	0	_		
PMA8		_	_	32	0	_		
PMA9		_	_	35	0	_		
PMA10		_	_	12	0	_		
PMCS1	23	26	29	15	0	_	Parallel Master Port Chip Select 1 strobe	
PMD0	20 <sup>(2)</sup>	23 <sup>(2)</sup> 4 <sup>(3)</sup>	26 <sup>(2)</sup> 35 <sup>(3)</sup>	10 <sup>(2)</sup> 21 <sup>(3)</sup>	I/O	TTL/ST	Parallel Master Port data (Demultiplexed Master mode) or address/data	
PMD1	19 <sup>(2)</sup> 2 <sup>(3)</sup>	22 <sup>(2)</sup> 5 <sup>(3)</sup>	25 <sup>(2)</sup> 36 <sup>(3)</sup>	9 <sup>(2)</sup>	I/O	TTL/ST	(Multiplexed Master modes)	
PMD2	18 <sup>(2)</sup>	21 <sup>(2)</sup> 6 <sup>(3)</sup>	24 <sup>(2)</sup>	8 <sup>(2)</sup>	I/O	TTL/ST	-	
PMD3	15	18	19	1	I/O	TTL/ST	-	
PMD4	14	17	18	44	I/O	TTL/ST	-	
PMD5	13	16	17	43	I/O	TTL/ST	+	
PMD6	12 <sup>(2)</sup> 28 <sup>(3)</sup>	15 <sup>(2)</sup> 3 <sup>(3)</sup>	16 <sup>(2)</sup> 34 <sup>(3)</sup>	42 <sup>(2)</sup> 20 <sup>(3)</sup>	I/O	TTL/ST	_	
PMD7	11 <sup>(2)</sup> 27 <sup>(3)</sup>	14 <sup>(2)</sup> 2 <sup>(3)</sup>	15 <sup>(2)</sup> 33 <sup>(3)</sup>	41 <sup>(2)</sup> 19 <sup>(3)</sup>	I/O	TTL/ST	_	
PMRD	21	24	27	11	0	_	Parallel Master Port read strobe	
	22 <sup>(2)</sup>	25 <sup>(2)</sup>	28 <sup>(2)</sup>	14 <sup>(2)</sup>	<del>                                     </del>			
PMWR	4(3)	7 <sup>(3)</sup>	2 <sup>(3)</sup>	24 <sup>(3)</sup>	0	_	Parallel Master Port write strobe	
VBUS	12 <sup>(3)</sup>	15 <sup>(3)</sup>	16 <sup>(3)</sup>	42(3)	ı	Analog	USB bus power monitor	
VUSB3V3	20 <sup>(3)</sup>	23 <sup>(3)</sup>	26 <sup>(3)</sup>	10 <sup>(3)</sup>	Р	_	USB internal transceiver supply. This pin must be connected to VDD.	
VBUSON	22 <sup>(3)</sup>	25 <sup>(3)</sup>	28 <sup>(3)</sup>	14 <sup>(3)</sup>	0	_	USB Host and OTG bus power control output	
D+	18 <sup>(3)</sup>	21 <sup>(3)</sup>	24 <sup>(3)</sup>	8(3)	I/O	Analog	USB D+	
D-	19 <sup>(3)</sup>	22 <sup>(3)</sup>	25 <sup>(3)</sup>	9(3)	I/O	Analog	USB D-	

Legend: CMOS = CMOS compatible input or output ST = Schmitt Trigger input with CMOS levels

Analog = Analog input O = Output

P = Power

TTL = TTL input buffer

PPS = Peripheral Pin Select

I = Input

Note 1: Pin numbers are provided for reference only. See the "Pin Diagrams" section for device pin availability.

--=N/A

2: Pin number for PIC32MX1XX devices only.

**TABLE 1-1:** PINOUT I/O DESCRIPTIONS (CONTINUED)

		Pin Nu	mber <sup>(1)</sup>	•		-	
Pin Name	28-pin QFN	28-pin SSOP/ SPDIP/ SOIC	36-pin VTLA	44-pin QFN/ TQFP/ VTLA	Pin Type	Buffer Type	Description
USBID	11 <sup>(3)</sup>	14 <sup>(3)</sup>	15 <sup>(3)</sup>	41 <sup>(3)</sup>	ı	ST	USB OTG ID detect
CTED1	27	2	33	19	I	ST	CTMU External Edge Input
CTED2	28	3	34	20	I	ST	
CTED3	13	16	17	43	I	ST	
CTED4	15	18	19	1	I	ST	1
CTED5	22	25	28	14	I	ST	
CTED6	23	26	29	15	I	ST	1
CTED7	_	_	20	5	I	ST	1
CTED8	_	_	_	13	I	ST	1
CTED9	9	12	10	34	I	ST	1
CTED10	14	17	18	44	I	ST	1
CTED11	18	21	24	8	I	ST	1
CTED12	2	5	36	22	I	ST	1
CTED13	3	6	1	23	I	ST	1
CTPLS	21	24	27	11	0	_	CTMU Pulse Output
PGED1	1	4	35	21	I/O	ST	Data I/O pin for Programming/Debugging Communication Channel 1
PGEC1	2	5	36	22	I	ST	Clock input pin for Programming/Debugging Communication Channel 1
PGED2	18	21	24	8	I/O	ST	Data I/O pin for Programming/Debugging Communication Channel 2
PGEC2	19	22	25	9	I	ST	Clock input pin for Programming/Debugging Communication Channel 2
PGED3	11 <sup>(2)</sup> 27 <sup>(3)</sup>	14 <sup>(2)</sup> 2 <sup>(3)</sup>	15 <sup>(2)</sup> 33 <sup>(3)</sup>	41 <sup>(2)</sup> 19 <sup>(3)</sup>	I/O	ST	Data I/O pin for Programming/Debugging Communication Channel 3
PGEC3	12 <sup>(2)</sup> 28 <sup>(3)</sup>	15 <sup>(2)</sup> 3 <sup>(3)</sup>	16 <sup>(2)</sup> 34 <sup>(3)</sup>	42 <sup>(2)</sup> 20 <sup>(3)</sup>	I	ST	Clock input pin for Programming/ Debugging Communication Channel 3
PGED4	_	_	3	12	I/O	ST	Data I/O pin for Programming/Debugging Communication Channel 4
PGEC4	_	_	4	13	I	ST	Clock input pin for Programming/ Debugging Communication Channel 4

**Legend:** CMOS = CMOS compatible input or output

ST = Schmitt Trigger input with CMOS levels

O = Output PPS = Peripheral Pin Select

Analog = Analog input

P = Power I = Input

TTL = TTL input buffer

Note 1: Pin numbers are provided for reference only. See the "Pin Diagrams" section for device pin availability.

\_\_ = N/A

2: Pin number for PIC32MX1XX devices only.

TABLE 1-1: PINOUT I/O DESCRIPTIONS (CONTINUED)

		Pin Nu	mber <sup>(1)</sup>					
Pin Name	28-pin QFN	28-pin SSOP/ SPDIP/ SOIC	36-pin VTLA	44-pin QFN/ TQFP/ VTLA	Pin Type	Buffer Type	Description	
MCLR	26	1	32	18	I/P	ST	Master Clear (Reset) input. This pin is a active-low Reset to the device.	
AVDD	25	28	31	17	Р	_	Positive supply for analog modules. This pin must be connected at all times.	
AVss	24	27	30	16	Р	_	Ground reference for analog modules	
VDD	10	13	5, 13, 14, 23	28, 40	Р	_	Positive supply for peripheral logic and I/O pins	
VCAP	17	20	22	7	Р		CPU logic filter capacitor connection	
Vss	5, 16	8, 19	6, 12, 21	6, 29, 39	Р	_	Ground reference for logic and I/O pins. This pin must be connected at all times.	
VREF+	27	2	33	19	I	Analog	Analog voltage reference (high) input	
VREF-	28	3	34	20	I	Analog	Analog voltage reference (low) input	

Legend: CMOS = CMOS compatible input or output ST = Schmitt Trigger input with CMOS levels TTL = TTL input buffer Analog = Analog input P = Power O = Output I = InputPPS = Peripheral Pin Select --= N/A

Note 1: Pin numbers are provided for reference only. See the "Pin Diagrams" section for device pin availability.

2: Pin number for PIC32MX1XX devices only.

# 2.0 GUIDELINES FOR GETTING STARTED WITH 32-BIT MCUs

Note:

This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To complement the information in this data sheet, refer to the documents listed in the *Documentation* > *Reference Manual* section of the Microchip PIC32 web site (www.microchip.com/pic32).

#### 2.1 Basic Connection Requirements

Getting started with the PIC32MX1XX/2XX 28/36/44-pin Family of 32-bit Microcontrollers (MCUs) requires attention to a minimal set of device pin connections before proceeding with development. The following is a list of pin names, which must always be connected:

- All VDD and Vss pins (see 2.2 "Decoupling Capacitors")
- All AVDD and AVSS pins, even if the ADC module is not used (see 2.2 "Decoupling Capacitors")
- VCAP pin (see 2.3 "Capacitor on Internal Voltage Regulator (VCAP)")
- MCLR pin (see 2.4 "Master Clear (MCLR) Pin")
- PGECx/PGEDx pins, used for In-Circuit Serial Programming™ (ICSP™) and debugging purposes (see 2.5 "ICSP Pins")
- OSC1 and OSC2 pins, when external oscillator source is used (see 2.7 "External Oscillator Pins")

The following pins may be required:

 VREF+/VREF- pins – used when external voltage reference for the ADC module is implemented

Note: The A

The AVDD and AVSS pins must be connected, regardless of ADC use and the ADC voltage reference source.


#### 2.2 Decoupling Capacitors

The use of decoupling capacitors on power supply pins, such as VDD, VSS, AVDD and AVSS is required. See Figure 2-1.

Consider the following criteria when using decoupling capacitors:

- Value and type of capacitor: A value of 0.1 µF (100 nF), 10-20V is recommended. The capacitor should be a low Equivalent Series Resistance (low-ESR) capacitor and have resonance frequency in the range of 20 MHz and higher. It is further recommended that ceramic capacitors be used.
- Placement on the printed circuit board: The
  decoupling capacitors should be placed as close
  to the pins as possible. It is recommended that
  the capacitors be placed on the same side of the
  board as the device. If space is constricted, the
  capacitor can be placed on another layer on the
  PCB using a via; however, ensure that the trace
  length from the pin to the capacitor is within onequarter inch (6 mm) in length.
- Handling high frequency noise: If the board is experiencing high frequency noise, upward of tens of MHz, add a second ceramic-type capacitor in parallel to the above described decoupling capacitor. The value of the second capacitor can be in the range of 0.01 μF to 0.001 μF. Place this second capacitor next to the primary decoupling capacitor. In high-speed circuit designs, consider implementing a decade pair of capacitances as close to the power and ground pins as possible. For example, 0.1 μF in parallel with 0.001 μF.
- Maximizing performance: On the board layout from the power supply circuit, run the power and return traces to the decoupling capacitors first, and then to the device pins. This ensures that the decoupling capacitors are first in the power chain. Equally important is to keep the trace length between the capacitor and the power pins to a minimum thereby reducing PCB track inductance.

# FIGURE 2-1: RECOMMENDED MINIMUM CONNECTION



Note 1: If the USB module is not used, this pin must be connected to VDD.

2: As an option, instead of a hard-wired connection, an inductor (L1) can be substituted between VDD and AVDD to improve ADC noise rejection. The inductor impedance should be less than  $3\Omega$  and the inductor capacity greater than 10 mA.

Where:

$$f = \frac{FCNV}{2} \qquad \text{(i.e., ADC conversion rate/2)}$$
 
$$f = \frac{1}{(2\pi\sqrt{LC})}$$
 
$$L = \left(\frac{1}{(2\pi f\sqrt{C})}\right)^2$$

1: Aluminum or electrolytic capacitors should not be used. ESR  $\leq 3\Omega$  from -40°C to 125°C @ SYSCLK frequency (i.e., MIPS).

#### 2.2.1 BULK CAPACITORS

The use of a bulk capacitor is recommended to improve power supply stability. Typical values range from 4.7  $\mu F$  to 47  $\mu F$ . This capacitor should be located as close to the device as possible.

# 2.3 Capacitor on Internal Voltage Regulator (VCAP)

#### 2.3.1 INTERNAL REGULATOR MODE

A low-ESR (3 ohm) capacitor is required on the VCAP pin, which is used to stabilize the internal voltage regulator output. The VCAP pin must not be connected to VDD, and must have a CEFC capacitor, with at least a 6V rating, connected to ground. The type can be ceramic or tantalum. Refer to 30.0 "Electrical Characteristics" for additional information on CEFC specifications.

#### 2.4 Master Clear (MCLR) Pin

The  $\overline{\text{MCLR}}$  pin provides two specific device functions:


- Device Reset
- · Device programming and debugging

Pulling The MCLR pin low generates a device Reset. Figure 2-2 illustrates a typical MCLR circuit. During device programming and debugging, the resistance and capacitance that can be added to the pin must be considered. Device programmers and debuggers drive the MCLR pin. Consequently, specific voltage levels (VIH and VIL) and fast signal transitions must not be adversely affected. Therefore, specific values of R and C will need to be adjusted based on the application and PCB requirements.

For example, as illustrated in Figure 2-2, it is recommended that the capacitor C, be isolated from the  $\overline{\text{MCLR}}$  pin during programming and debugging operations.

Place the components illustrated in Figure 2-2 within one-quarter inch (6 mm) from the MCLR pin.

# FIGURE 2-2: EXAMPLE OF MCLR PIN CONNECTIONS



Note 1:  $\frac{470\Omega \leq R1 \leq 1\Omega}{MCLR} \text{ from the external capacitor C, in the event of } \frac{MCLR}{MCLR} \text{ pin breakdown, due to Electrostatic Discharge } (ESD) \text{ or Electrical Overstress (EOS). Ensure that the } \frac{MCLR}{MCLR} \text{ pin V}_{IH} \text{ and V}_{IL} \text{ specifications are met without interfering with the Debug/Programmer tools.}$ 

- 2: The capacitor can be sized to prevent unintentional Resets from brief glitches or to extend the device Reset period during POR.
- **3:** No pull-ups or bypass capacitors are allowed on active debug/program PGECx/PGEDx pins.

#### 2.5 ICSP Pins

The PGECx and PGEDx pins are used for ICSP and debugging purposes. It is recommended to keep the trace length between the ICSP connector and the ICSP pins on the device as short as possible. If the ICSP connector is expected to experience an ESD event, a series resistor is recommended, with the value in the range of a few tens of Ohms, not to exceed 100 Ohms.

Pull-up resistors, series diodes and capacitors on the PGECx and PGEDx pins are not recommended as they will interfere with the programmer/debugger communications to the device. If such discrete components are an application requirement, they should be removed from the circuit during programming and debugging. Alternatively, refer to the AC/DC characteristics and timing requirements information in the respective device Flash programming specification for information on capacitive loading limits and pin input voltage high (VIH) and input low (VIL) requirements.

Ensure that the "Communication Channel Select" (i.e., PGECx/PGEDx pins) programmed into the device matches the physical connections for the ICSP to MPLAB® ICD 3 or MPLAB REAL ICE $^{\text{TM}}$ .

For more information on ICD 3 and REAL ICE connection requirements, refer to the following documents that are available on the Microchip web site:

- "Using MPLAB® ICD 3" (poster) (DS50001765)
- "MPLAB® ICD 3 Design Advisory" (DS50001764)
- "MPLAB<sup>®</sup> REAL ICE™ In-Circuit Debugger User's Guide" (DS50001616)
- "Using MPLAB® REAL ICE™ Emulator" (poster) (DS50001749)

#### **2.6 JTAG**

The TMS, TDO, TDI and TCK pins are used for testing and debugging according to the Joint Test Action Group (JTAG) standard. It is recommended to keep the trace length between the JTAG connector and the JTAG pins on the device as short as possible. If the JTAG connector is expected to experience an ESD event, a series resistor is recommended with the value in the range of a few tens of Ohms, not to exceed 100 Ohms.


Pull-up resistors, series diodes and capacitors on the TMS, TDO, TDI and TCK pins are not recommended as they will interfere with the programmer/debugger communications to the device. If such discrete components are an application requirement, they should be removed from the circuit during programming and debugging. Alternatively, refer to the AC/DC characteristics and timing requirements information in the respective device Flash programming specification for information on capacitive loading limits and pin input voltage high (VIH) and input low (VIL) requirements.

#### 2.7 External Oscillator Pins

Many MCUs have options for at least two oscillators: a high-frequency primary oscillator and a low-frequency secondary oscillator (refer to **Section 8.0 "Oscillator Configuration"** for details).

The oscillator circuit should be placed on the same side of the board as the device. Also, place the oscillator circuit close to the respective oscillator pins, not exceeding one-half inch (12 mm) distance between them. The load capacitors should be placed next to the oscillator itself, on the same side of the board. Use a grounded copper pour around the oscillator circuit to isolate them from surrounding circuits. The grounded copper pour should be routed directly to the MCU ground. Do not run any signal traces or power traces inside the ground pour. Also, if using a two-sided board, avoid any traces on the other side of the board where the crystal is placed. A suggested layout is illustrated in Figure 2-3.

FIGURE 2-3: SUGGESTED OSCILLATOR CIRCUIT PLACEMENT



#### 2.8 Unused I/Os

Unused I/O pins should not be allowed to float as inputs. They can be configured as outputs and driven to a logic-low state.

Alternatively, inputs can be reserved by connecting the pin to Vss through a 1k to 10k resistor and configuring the pin as an input.

# 2.8.1 CRYSTAL OSCILLATOR DESIGN CONSIDERATION

The following example assumptions are used to calculate the Primary Oscillator loading capacitor values:

- CIN = PIC32\_OSC2\_Pin Capacitance = ~4-5 pF
- COUT = PIC32 OSC1 Pin Capacitance = ~4-5 pF
- C1 and C2 = XTAL manufacturing recommended loading capacitance
- Estimated PCB stray capacitance, (i.e.,12 mm length) = 2.5 pF

# EXAMPLE 2-1: CRYSTAL LOAD CAPACITOR CALCULATION

```
Crystal manufacturer recommended: CI = C2 = 15 pF
Therefore:
CLOAD = \{([CIN + CI] * [COUT + C2]) / [CIN + CI + C2 + COUT]\} + estimated oscillator PCB stray capacitance
= \{([5 + 15][5 + 15]) / [5 + 15 + 15 + 5]\} + 2.5 pF
= \{([20][20]) / [40]\} + 2.5
= 10 + 2.5 = 12.5 pF
Rounded to the nearest standard value or 12 pF in this example for Primary Oscillator crystals "C1" and "C2".
```

The following tips are used to increase oscillator gain, (i.e., to increase peak-to-peak oscillator signal):


- Select a crystal with a lower "minimum" power drive rating
- Select an crystal oscillator with a lower XTAL manufacturing "ESR" rating.
- Add a parallel resistor across the crystal. The smaller the resistor value the greater the gain. It is recommended to stay in the range of 600k to 1M
- C1 and C2 values also affect the gain of the oscillator. The lower the values, the higher the gain.
- C2/C1 ratio also affects gain. To increase the gain, make C1 slightly smaller than C2, which will also help start-up performance.

Note: Do not add excessive gain such that the oscillator signal is clipped, flat on top of the sine wave. If so, you need to reduce the gain or add a series resistor, RS, as shown in circuit "C" in Figure 2-4. Failure to do so will stress and age the crystal, which can result in an early failure. Adjust the gain to trim the max peak-to-peak to ~VDD-0.6V. When measuring the oscillator signal you must use a FET scope probe or a probe with ≤ 1.5 pF or the scope probe itself will unduly change the gain and peak-to-peak levels.

#### 2.8.1.1 Additional Microchip References

- AN588 "PICmicro® Microcontroller Oscillator Design Guide"
- AN826 "Crystal Oscillator Basics and Crystal Selection for rfPIC™ and PICmicro® Devices"
- AN849 "Basic PICmicro® Oscillator Design"

# FIGURE 2-4: PRIMARY CRYSTAL OSCILLATOR CIRCUIT RECOMMENDATIONS



# 2.9 Typical Application Connection Examples

Examples of typical application connections are shown in Figure 2-5 and Figure 2-6.

FIGURE 2-5: CAPACITIVE TOUCH SENSING WITH GRAPHICS APPLICATION





FIGURE 2-6: AUDIO PLAYBACK APPLICATION




# 2.10 Considerations When Interfacing To Remotely Powered Circuits

#### 2.10.1 NON-5V TOLERANT INPUT PINS

A quick review of the maximum rating section in the **Section 30.0 "Electrical Characteristics"** will indicate that the voltage on any non-5V tolerant pin should not exceed AVDD/VDD+0.3V. Figure 2-7 illustrates a remote circuit using an independent power source that is powered while connected to a PIC32 non-5V tolerant circuit which is not powered.

FIGURE 2-7: REMOTE CIRCUIT WITH AN INDEPENDENT POWER SOURCE



Without proper signal isolation on non-5V tolerant pins, the remote signal can power the PIC32 through the high side ESD protection diodes. This violates the maximum rating specification and can cause improper initialization of internal PIC32 logic circuits. In this

case, it is recommended that users can implement a digital or analog signal isolation, as shown in Figure 2-8

PIC32 VDD PIC32 VDD Conn **Digital Isolator** Digital Isolator External VDD External VDD IN1 REMOTE IN REMOTE\_IN PIC32 PIC32 OUT1 VSS **REMOTE\_OUT** √vss PIC32 VDD PIC32 VDD Analog / Digital Isolator Opto Digital Conn ISOLATOR Analog\_Out2 IN1 External VDD External\_VDD PIC32 PIC32 Analog\_IN1 Analog REMOTE\_IN Switch(s) vss

FIGURE 2-8: DIGITAL AND ANALOG SIGNAL ISOLATION

Digital signal isolators along with optional level translation examples are provided in Table 2-1.

TABLE 2-1: EXAMPLES OF DIGITAL ISOLATORS WITH OPTIONAL LEVEL TRANSLATION

	Inductive Coupling	Capacitive Coupling	Optional Coupling	Analog/Digital Switch
ADuM7241 / 40 ARZ (1Mbps)	Х	-	-	-
ADuM7241 / 40 CRZ (25 Mbps)	Х	-	-	-
ISO721	-	X	-	-
LTV-829S (2 Chan)	-	-	X	-
LTV-849S (4 Chan)	-	-	-	-
FSA266 / NC7WB66	-	-	-	Х


#### 2.10.2 5V-TOLERANT INPUT PINS

The internal high-side diode on 5V-tolerant pins, rather than being connected to VDD, are bussed to an internal floating node, as shown in Figure 2-9. Voltages on these pins, if VDD < 2.3V, should not exceed roughly 3.2V relative to PIC32 Vss. At 3.6V or above, it will violate the absolute maximum specification and impact the device reliability.

If a remotely powered digital only signal can be guaranteed to always be  $\leq$  3.2V relative to PIC32 Vss, then a 5V-tolerant pin can be used without a digital isolator. This can be assumed when the following is applicable:

- · No ground loop issue
- The logic ground of the two circuits is not at the same absolute level
- No remote logic low inputs are less than Vss -0.3V


FIGURE 2-9: 5V-TOLERANT INPUT PINS BUSSED TO AN INTERNAL FLOATING NODE



# 2.11 EMI/EMC/EFT (IEC 61000-4-4 and IEC 61000-4-2) Suppression Considerations

The use of LDO regulators is preferred to reduce overall system noise and provide a cleaner power source. However, when utilizing switching Buck/Boost regulators as the local power source for PIC32 devices, as well as in electrically noisy environments or test conditions required for IEC 61000-4-4 and IEC 61000-4-2, users should evaluate the use of T-Filters (i.e., L-C-L) on the power pins, as shown in Figure 2-10. In addition to a more stable power source, using this type of T-Filter can greatly reduce susceptibility to EMI sources and events.

FIGURE 2-10: EMI/EMC/EFT SUPPRESSION CIRCUIT



NOTES:		

#### 3.0 CPU

Note:

This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To complement the information in this data sheet, refer to **Section 2.** "CPU" (DS60001113), which is available from the *Documentation > Reference Manual* section of the Microchip PIC32 web site (www.microchip.com/pic32). Resources for the MIPS32® M4K® Processor Core are available at: www.imgtec.com.


The MIPS32<sup>®</sup> M4K<sup>®</sup> Processor Core is the heart of the PIC32MX1XX/2XX family processor. The CPU fetches instructions, decodes each instruction, fetches source operands, executes each instruction and writes the results of instruction execution to the destinations.

#### 3.1 Features

- · 5-stage pipeline
- · 32-bit address and data paths
- MIPS32 Enhanced Architecture (Release 2)
  - Multiply-accumulate and multiply-subtract instructions
  - Targeted multiply instruction
  - Zero/One detect instructions
  - WAIT instruction
  - Conditional move instructions (MOVN, MOVZ)
  - Vectored interrupts
  - Programmable exception vector base
  - Atomic interrupt enable/disable
  - Bit field manipulation instructions

- MIPS16e<sup>®</sup> code compression
  - 16-bit encoding of 32-bit instructions to improve code density
  - Special PC-relative instructions for efficient loading of addresses and constants
  - SAVE and RESTORE macro instructions for setting up and tearing down stack frames within subroutines
  - Improved support for handling 8 and 16-bit data types
- Simple Fixed Mapping Translation (FMT) mechanism
- · Simple dual bus interface
  - Independent 32-bit address and data buses
  - Transactions can be aborted to improve interrupt latency
- · Autonomous multiply/divide unit
  - Maximum issue rate of one 32x16 multiply per clock
  - Maximum issue rate of one 32x32 multiply every other clock
  - Early-in iterative divide. Minimum 11 and maximum 33 clock latency (dividend (rs) sign extension-dependent)
- · Power control
  - Minimum frequency: 0 MHz
  - Low-Power mode (triggered by WAIT instruction)
  - Extensive use of local gated clocks
- · EJTAG debug and instruction trace
  - Support for single stepping
  - Virtual instruction and data address/value
  - Breakpoints

#### FIGURE 3-1: MIPS32® M4K® PROCESSOR CORE BLOCK DIAGRAM



#### 3.2 Architecture Overview

The MIPS32 M4K processor core contains several logic blocks working together in parallel, providing an efficient high-performance computing engine. The following blocks are included with the core:

- Execution Unit
- Multiply/Divide Unit (MDU)
- System Control Coprocessor (CP0)
- Fixed Mapping Translation (FMT)
- · Dual Internal Bus interfaces
- · Power Management
- MIPS16e<sup>®</sup> Support
- · Enhanced JTAG (EJTAG) Controller

#### 3.2.1 EXECUTION UNIT

The MIPS32 M4K processor core execution unit implements a load/store architecture with single-cycle ALU operations (logical, shift, add, subtract) and an autonomous multiply/divide unit. The core contains thirty-two 32-bit General Purpose Registers (GPRs) used for integer operations and address calculation. The register file consists of two read ports and one write port and is fully bypassed to minimize operation latency in the pipeline.

The execution unit includes:

- · 32-bit adder used for calculating the data address
- Address unit for calculating the next instruction address
- Logic for branch determination and branch target address calculation
- · Load aligner
- Bypass multiplexers used to avoid stalls when executing instruction streams where data producing instructions are followed closely by consumers of their results
- Leading Zero/One detect unit for implementing the CLZ and CLO instructions
- Arithmetic Logic Unit (ALU) for performing bitwise logical operations
- Shifter and store aligner

#### 3.2.2 MULTIPLY/DIVIDE UNIT (MDU)

The MIPS32 M4K processor core includes a Multiply/Divide Unit (MDU) that contains a separate pipeline for multiply and divide operations. This pipeline operates in parallel with the Integer Unit (IU) pipeline and does not stall when the IU pipeline stalls. This allows MDU operations to be partially masked by system stalls and/or other integer unit instructions.

The high-performance MDU consists of a 32x16 booth recoded multiplier, result/accumulation registers (HI and LO), a divide state machine, and the necessary multiplexers and control logic. The first number shown ('32' of 32x16) represents the *rs* operand. The second number ('16' of 32x16) represents the *rt* operand. The PIC32 core only checks the value of the latter (*rt*) operand to determine how many times the operation must pass through the multiplier. The 16x16 and 32x16 operations pass through the multiplier once. A 32x32 operation passes through the multiplier twice.

The MDU supports execution of one 16x16 or 32x16 multiply operation every clock cycle; 32x32 multiply operations can be issued every other clock cycle. Appropriate interlocks are implemented to stall the issuance of back-to-back 32x32 multiply operations. The multiply operand size is automatically determined by logic built into the MDU.

Divide operations are implemented with a simple 1 bit per clock iterative algorithm. An early-in detection checks the sign extension of the dividend (rs) operand. If rs is 8 bits wide, 23 iterations are skipped. For a 16-bit wide rs, 15 iterations are skipped and for a 24-bit wide rs, 7 iterations are skipped. Any attempt to issue a subsequent MDU instruction while a divide is still active causes an IU pipeline stall until the divide operation is completed.

Table 3-1 lists the repeat rate (peak issue rate of cycles until the operation can be reissued) and latency (number of cycles until a result is available) for the PIC32 core multiply and divide instructions. The approximate latency and repeat rates are listed in terms of pipeline clocks.

TABLE 3-1: MIPS32® M4K® PROCESSOR CORE HIGH-PERFORMANCE INTEGER MULTIPLY/DIVIDE UNIT LATENCIES AND REPEAT RATES

Opcode	Operand Size (mul rt) (div rs)	Latency	Repeat Rate
MULT/MULTU, MADD/MADDU,	16 bits	1	1
MSUB/MSUBU	32 bits	2	2
MUL	16 bits	2	1
	32 bits	3	2
DIV/DIVU	8 bits	12	11
	16 bits	19	18
	24 bits	26	25
	32 bits	33	32

The MIPS architecture defines that the result of a multiply or divide operation be placed in the HI and LO registers. Using the Move-From-HI (MFHI) and Move-From-LO (MFLO) instructions, these values can be transferred to the General Purpose Register file.

In addition to the HI/LO targeted operations, the MIPS32 $^{\circledR}$  architecture also defines a multiply instruction, MUL, which places the least significant results in the primary register file instead of the HI/LO register pair. By avoiding the explicit MFLO instruction required when using the LO register, and by supporting multiple destination registers, the throughput of multiply-intensive operations is increased.

Two other instructions, Multiply-Add (MADD) and Multiply-Subtract (MSUB), are used to perform the multiply-accumulate and multiply-subtract operations. The MADD instruction multiplies two numbers and then

adds the product to the current contents of the HI and LO registers. Similarly, the MSUB instruction multiplies two operands and then subtracts the product from the HI and LO registers. The MADD and MSUB operations are commonly used in DSP algorithms.

# 3.2.3 SYSTEM CONTROL COPROCESSOR (CP0)

In the MIPS architecture, CP0 is responsible for the virtual-to-physical address translation, the exception control system, the processor's diagnostics capability, the operating modes (Kernel, User and Debug) and whether interrupts are enabled or disabled. Configuration information, such as presence of options like MIPS16e, is also available by accessing the CP0 registers, listed in Table 3-2.

TABLE 3-2: COPROCESSOR 0 REGISTERS

Register Number	Register Name	Function
0-6	Reserved	Reserved in the PIC32MX1XX/2XX family core.
7	HWREna	Enables access via the RDHWR instruction to selected hardware registers.
8	BadVAddr <sup>(1)</sup>	Reports the address for the most recent address-related exception.
9	Count <sup>(1)</sup>	Processor cycle count.
10	Reserved	Reserved in the PIC32MX1XX/2XX family core.
11	Compare <sup>(1)</sup>	Timer interrupt control.
12	Status <sup>(1)</sup>	Processor status and control.
12	IntCtl <sup>(1)</sup>	Interrupt system status and control.
12	SRSCtl <sup>(1)</sup>	Shadow register set status and control.
12	SRSMap <sup>(1)</sup>	Provides mapping from vectored interrupt to a shadow set.
13	Cause <sup>(1)</sup>	Cause of last general exception.
14	EPC <sup>(1)</sup>	Program counter at last exception.
15	PRId	Processor identification and revision.
15	EBASE	Exception vector base register.
16	Config	Configuration register.
16	Config1	Configuration Register 1.
16	Config2	Configuration Register 2.
16	Config3	Configuration Register 3.
17-22	Reserved	Reserved in the PIC32MX1XX/2XX family core.
23	Debug <sup>(2)</sup>	Debug control and exception status.
24	DEPC <sup>(2)</sup>	Program counter at last debug exception.
25-29	Reserved	Reserved in the PIC32MX1XX/2XX family core.
30	ErrorEPC <sup>(1)</sup>	Program counter at last error.
31	DESAVE <sup>(2)</sup>	Debug handler scratchpad register.

Note 1: Registers used in exception processing.

2: Registers used during debug.

Coprocessor 0 also contains the logic for identifying and managing exceptions. Exceptions can be caused by a variety of sources, including alignment errors in data, external events or program errors. Table 3-3 lists the exception types in order of priority.

TABLE 3-3: MIPS32® M4K® PROCESSOR CORE EXCEPTION TYPES

Exception	Description
Reset	Assertion MCLR or a Power-on Reset (POR).
DSS	EJTAG debug single step.
DINT	EJTAG debug interrupt. Caused by the assertion of the external <i>EJ_DINT</i> input or by setting the EjtagBrk bit in the ECR register.
NMI	Assertion of NMI signal.
Interrupt	Assertion of unmasked hardware or software interrupt signal.
DIB	EJTAG debug hardware instruction break matched.
AdEL	Fetch address alignment error. Fetch reference to protected address.
IBE	Instruction fetch bus error.
DBp	EJTAG breakpoint (execution of SDBBP instruction).
Sys	Execution of SYSCALL instruction.
Вр	Execution of BREAK instruction.
RI	Execution of a reserved instruction.
CpU	Execution of a coprocessor instruction for a coprocessor that is not enabled.
CEU	Execution of a CorExtend instruction when CorExtend is not enabled.
Ov	Execution of an arithmetic instruction that overflowed.
Tr	Execution of a trap (when trap condition is true).
DDBL/DDBS	EJTAG Data Address Break (address only) or EJTAG data value break on store (address + value).
AdEL	Load address alignment error. Load reference to protected address.
AdES	Store address alignment error. Store to protected address.
DBE	Load or store bus error.
DDBL	EJTAG data hardware breakpoint matched in load data compare.

#### 3.3 Power Management

The MIPS M4K processor core offers many power management features, including low-power design, active power management and power-down modes of operation. The core is a static design that supports slowing or Halting the clocks, which reduces system power consumption during Idle periods.

# 3.3.1 INSTRUCTION-CONTROLLED POWER MANAGEMENT

The mechanism for invoking Power-Down mode is through execution of the WAIT instruction. For more information on power management, see Section 26.0 "Power-Saving Features".

#### 3.4 EJTAG Debug Support

The MIPS M4K processor core provides an Enhanced JTAG (EJTAG) interface for use in the software debug of application and kernel code. In addition to standard User mode and Kernel modes of operation, the M4K core provides a Debug mode that is entered after a debug exception (derived from a hardware breakpoint, single-step exception, etc.) is taken and continues until a Debug Exception Return (DERET) instruction is executed. During this time, the processor executes the debug exception handler routine.

The EJTAG interface operates through the Test Access Port (TAP), a serial communication port used for transferring test data in and out of the core. In addition to the standard JTAG instructions, special instructions defined in the EJTAG specification define which registers are selected and how they are used.

#### 4.0 MEMORY ORGANIZATION

Note:

This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source.For detailed information, refer to **Section 3.** "**Memory Organization**" (DS60001115), which is available from the *Documentation* > *Reference Manual* section of the Microchip PIC32 web site (www.microchip.com/pic32).

PIC32MX1XX/2XX 28/36/44-pin Family microcontrollers provide 4 GB unified virtual memory address space. All memory regions, including program, data memory, Special Function Registers (SFRs), and Configuration registers, reside in this address space at their respective unique addresses. The program and data memories can be optionally partitioned into user and kernel memories. In addition, the data memory can be made executable, allowing PIC32MX1XX/2XX 28/36/44-pin Family devices to execute from data memory.

Key features include:

- · 32-bit native data width
- Separate User (KUSEG) and Kernel (KSEG0/KSEG1) mode address space
- · Flexible program Flash memory partitioning
- Flexible data RAM partitioning for data and program space
- · Separate boot Flash memory for protected code
- Robust bus exception handling to intercept runaway code
- Simple memory mapping with Fixed Mapping Translation (FMT) unit
- Cacheable (KSEG0) and non-cacheable (KSEG1) address regions

# 4.1 PIC32MX1XX/2XX 28/36/44-pin Family Memory Layout

PIC32MX1XX/2XX 28/36/44-pin Family microcontrollers implement two address schemes: virtual and physical. All hardware resources, such as program memory, data memory and peripherals, are located at their respective physical addresses. Virtual addresses are exclusively used by the CPU to fetch and execute instructions as well as access peripherals. Physical addresses are used by bus master peripherals, such as DMA and the Flash controller, that access memory independently of the CPU.

The memory maps for the PIC32MX1XX/2XX 28/36/44-pin Family devices are illustrated in Figure 4-1 through Figure 4-6.

Table 4-1 provides SFR memory map details.





FIGURE 4-1: MEMORY MAP ON RESET FOR PIC32MX110/210 DEVICES (4 KB RAM, 16 KB FLASH)








FIGURE 4-3: MEMORY MAP ON RESET FOR PIC32MX130/230 DEVICES (16 KB RAM, 64 KB FLASH)








TABLE 4-1: SFR MEMORY MAP

TABLE 4-1. SPR MEI	Virtual A	ddress
Peripheral	Base	Offset Start
Watchdog Timer		0x0000
RTCC		0x0200
Timer1-5		0x0600
Input Capture 1-5		0x2000
Output Compare 1-5		0x3000
IC1 and IC2		0x5000
SPI1 and SPI2		0x5800
UART1 and UART2		0x6000
PMP		0x7000
ADC	0xBF80	0x9000
CVREF		0x9800
Comparator		0xA000
СТМИ		0xA200
Oscillator		0xF000
Device and Revision ID		0xF220
Peripheral Module Disable		0xF240
Flash Controller		0xF400
Reset		0xF600
PPS		0xFA04
Interrupts		0x1000
Bus Matrix		0x2000
DMA	0xBF88	0x3000
USB		0x5050
PORTA-PORTC		0x6000
Configuration	0xBFC0	0x0BF0

2 Bus Matrix Control Registers

		IIA stesets	RIS 001F	0041	0000	0000	0000	0000	0000	0000	XXXX	XXXX	0000	0000	XXXX	XXXX	0000	0000		
		16/0	S BMXER	٨	1		1		1											
		1//1	BMXERRD	BMXARB<2:0>	Ι		Ι		Ι				\<19:16>							
		18/2	BMXERRIXI BMXERRICD BMXERRDMA BMXERRDS BMXERRIS 001F	8	Ι		Ι		Ι				BMXPUPBA<19:16>							
		19/3	BMXERRICD	I	Ι		Ι		Ι											
		20/4	BMXERRIX	_	_		_		_				_							
		21/5	1	1	1	Δ	1	Δ	1	<(	ر	<u>\</u>	-	<(	1		/	١		
	Bits	22/6	I	BMXWSDRM	Ι	BMXDKPBA<15:0>	Ι	BMXDUDBA<15:0>	Ι	BMXDUPBA<15:0>	-0.15/23/19GAMa	7.1.6~26ININDV	-	BMXPUPBA<15:0>	BMYDEMS7/34:0>	7.10-20IV	PMYBOOTS7/31:0>	ADOO 1 02/01.		
		23/7	1	I	I	BN	I	BM	I	BM	BM	1	BN	BM	BM					
		24/8	1	I	1				1		1				-					
		25/9	1	I	1		1		1				1							
		26/10	1	ı	1		1		1				_							
IAP		27/11	1	I	1		1		1				1							
BUS MATRIX REGISTER MAP		3 28/12	1	1	1		1		1				-							
REGIS		4 29/13	1	I	1		1		1				-							
TRIX		5 30/14	1	-	1		-		1				-							
US MA		31/15	9	0	9	0	9	0	9	0	9	0	<b>—</b> 9	0	9	0	9	0		
ā		Bit Rang	31:16	15:0	31:16	15:0	31:1	15:0	31:1	15:0	31:16	15:0	31:1	15:0	31:16	15:0	31:16	15:0		
TABLE 4-2:		Register Name		BINACON	2010 PANY DIVIDEA (1)	DIVIDUREDA	31:16	BINIADUDBA	31:16	DIVIDURDA	7 ON OUNCY		31:16	DIVIATURDA	RMYDEMSZ		ZSTOCAVNA			
TAB	SSƏ.	ibbA IsuhiV #_8878)	0	7000	2,00	20102	0000	2020	0000	2030	0,000	2040	2050	7020	2060	7007	0206	2010		

H 1 0 0 0 0 0 0 X X 0 0 X X 0 0

**Legend:** x = unknown value on Reset; — = unimplemented, read as '0'. Reset values are shown in hexadecimal.

This register has corresponding CLR, SET and INV registers at its virtual address, plus an offset of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for more information.

#### REGISTER 4-1: BMXCON: BUS MATRIX CONFIGURATION REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.04	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31:24	_	_	_	_	_	_	_	_
	U-0	U-0	U-0	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
23:16	_	_	_	BMX ERRIXI	BMX ERRICD	BMX ERRDMA	BMX ERRDS	BMX ERRIS
45.0	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
15:8	_	_	_	_	_	_	_	_
	U-0	R/W-1	U-0	U-0	U-0	R/W-0	R/W-0	R/W-1
7:0	_	BMX WSDRM		_		E	3MXARB<2:0	>

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared

bit 31-21 Unimplemented: Read as '0'

bit 20 BMXERRIXI: Enable Bus Error from IXI bit

1 = Enable bus error exceptions for unmapped address accesses initiated from IXI shared bus

0 = Disable bus error exceptions for unmapped address accesses initiated from IXI shared bus

bit 19 BMXERRICD: Enable Bus Error from ICD Debug Unit bit

1 = Enable bus error exceptions for unmapped address accesses initiated from ICD

0 = Disable bus error exceptions for unmapped address accesses initiated from ICD

bit 18 BMXERRDMA: Bus Error from DMA bit

1 = Enable bus error exceptions for unmapped address accesses initiated from DMA

0 = Disable bus error exceptions for unmapped address accesses initiated from DMA

bit 17 BMXERRDS: Bus Error from CPU Data Access bit (disabled in Debug mode)

1 = Enable bus error exceptions for unmapped address accesses initiated from CPU data access

0 = Disable bus error exceptions for unmapped address accesses initiated from CPU data access

bit 16 BMXERRIS: Bus Error from CPU Instruction Access bit (disabled in Debug mode)

1 = Enable bus error exceptions for unmapped address accesses initiated from CPU instruction access

0 = Disable bus error exceptions for unmapped address accesses initiated from CPU instruction access

bit 15-7 Unimplemented: Read as '0'

bit 6 BMXWSDRM: CPU Instruction or Data Access from Data RAM Wait State bit

1 = Data RAM accesses from CPU have one wait state for address setup

0 = Data RAM accesses from CPU have zero wait states for address setup

bit 5-3 Unimplemented: Read as '0'

bit 2-0 BMXARB<2:0>: Bus Matrix Arbitration Mode bits

111 = Reserved (using these Configuration modes will produce undefined behavior)

•

•

011 = Reserved (using these Configuration modes will produce undefined behavior)010 = Arbitration Mode 2

001 = Arbitration Mode 1 (default)

000 = Arbitration Mode 0

#### REGISTER 4-2: BMXDKPBA: DATA RAM KERNEL PROGRAM BASE ADDRESS REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31.24	_	_	_	_	_		_	_
00:40	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23:16	_	_	_	_	_	_	_	_
45.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R-0	R-0
15:8				BMXDKI	PBA<15:8>			
7.0	R-0	R-0	R-0	R-0	R-0	R-0	R-0	R-0
7:0				BMXDK	PBA<7:0>			

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

bit 15-10 BMXDKPBA<15:10>: DRM Kernel Program Base Address bits

When non-zero, this value selects the relative base address for kernel program space in RAM

bit 9-0 **BMXDKPBA<9:0>:** Read-Only bits

This value is always '0', which forces 1 KB increments

**Note 1:** At Reset, the value in this register is forced to zero, which causes all of the RAM to be allocated to Kernal mode data usage.

2: The value in this register must be less than or equal to BMXDRMSZ.

#### REGISTER 4-3: BMXDUDBA: DATA RAM USER DATA BASE ADDRESS REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0	
24.04	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0	
31:24	_	_	_	_	_	_	_	_	
00.40	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0	
23:16	_	_	-	-	1	-		_	
45.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R-0	R-0	
15:8	BMXDUDBA<15:8>								
7.0	R-0	R-0	R-0	R-0	R-0	R-0	R-0	R-0	
7:0				BMXDU	DBA<7:0>				

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

bit 15-10 BMXDUDBA<15:10>: DRM User Data Base Address bits

When non-zero, the value selects the relative base address for User mode data space in RAM, the value must be greater than BMXDKPBA.

bit 9-0 BMXDUDBA<9:0>: Read-Only bits

This value is always '0', which forces 1 KB increments

**Note 1:** At Reset, the value in this register is forced to zero, which causes all of the RAM to be allocated to Kernal mode data usage.

2: The value in this register must be less than or equal to BMXDRMSZ.

#### REGISTER 4-4: BMXDUPBA: DATA RAM USER PROGRAM BASE ADDRESS REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31.24	_	_		_			_	_
22.46	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23:16	_	_		_	-		_	_
15.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R-0	R-0
15:8				BMXDU	PBA<15:8>			
7.0	R-0	R-0	R-0	R-0	R-0	R-0	R-0	R-0
7:0		·		BMXDU	PBA<7:0>	_		

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

bit 15-10 BMXDUPBA<15:10>: DRM User Program Base Address bits

When non-zero, the value selects the relative base address for User mode program space in RAM, BMXDUPBA must be greater than BMXDUDBA.

bit 9-0 BMXDUPBA<9:0>: Read-Only bits

This value is always '0', which forces 1 KB increments

**Note 1:** At Reset, the value in this register is forced to zero, which causes all of the RAM to be allocated to Kernal mode data usage.

2: The value in this register must be less than or equal to BMXDRMSZ.

#### REGISTER 4-5: BMXDRMSZ: DATA RAM SIZE REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0			
24.24	R	R	R	R	R	R	R	R			
31:24		BMXDRMSZ<31:24>									
00.40	R	R	R	R	R	R	R	R			
23:16	BMXDRMSZ<23:16>										
15.0	R	R	R	R	R	R	R	R			
15:8				BMXDRI	MSZ<15:8>						
7.0	R	R	R	R	R	R	R	R			
7:0				BMXDR	MSZ<7:0>						

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### bit 31-0 BMXDRMSZ<31:0>: Data RAM Memory (DRM) Size bits

Static value that indicates the size of the Data RAM in bytes:

0x00001000 = Device has 4 KB RAM 0x00002000 = Device has 8 KB RAM 0x00004000 = Device has 16 KB RAM 0x00008000 = Device has 32 KB RAM

0x00010000 = Device has 64 KB RAM

# REGISTER 4-6: BMXPUPBA: PROGRAM FLASH (PFM) USER PROGRAM BASE ADDRESS REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0			
31:24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0			
31.24	_	_	_	_	_	_	_	_			
00.40	U-0	U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0			
23:16	_	_	-	-	BMXPUPBA<19:16>						
45.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R-0	R-0	R-0			
15:8		BMXPUPBA<15:8>									
7.0	R-0	R-0	R-0	R-0	R-0	R-0	R-0	R-0			
7:0				BMXPU	PBA<7:0>						

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-20 Unimplemented: Read as '0'

bit 19-11 BMXPUPBA<19:11>: Program Flash (PFM) User Program Base Address bits

bit 10-0 **BMXPUPBA<10:0>:** Read-Only bits

This value is always '0', which forces 2 KB increments

**Note 1:** At Reset, the value in this register is forced to zero, which causes all of the RAM to be allocated to Kernal mode data usage.

2: The value in this register must be less than or equal to BMXPFMSZ.

#### REGISTER 4-7: BMXPFMSZ: PROGRAM FLASH (PFM) SIZE REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0			
31:24	R	R	R	R	R	R	R	R			
31.24		BMXPFMSZ<31:24>									
00:40	R	R	R	R	R	R	R	R			
23:16	BMXPFMSZ<23:16>										
45.0	R	R	R	R	R	R	R	R			
15:8				BMXPFN	//SZ<15:8>						
7.0	R	R	R	R	R	R	R	R			
7:0				BMXPF	MSZ<7:0>		_				

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### bit 31-0 BMXPFMSZ<31:0>: Program Flash Memory (PFM) Size bits

Static value that indicates the size of the PFM in bytes:

0x00004000 = Device has 16 KB Flash

0x00008000 = Device has 32 KB Flash

0x00010000 = Device has 64 KB Flash

0x00020000 = Device has 128 KB Flash

0x00040000 = Device has 256 KB Flash

#### REGISTER 4-8: BMXBOOTSZ: BOOT FLASH (IFM) SIZE REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0			
24.04	R	R	R	R	R	R	R	R			
31:24		BMXBOOTSZ<31:24>									
22.46	R	R	R	R	R	R	R	R			
23:16		BMXBOOTSZ<23:16>									
45.0	R	R	R	R	R	R	R	R			
15:8	BMXBOOTSZ<15:8>										
7.0	R	R	R	R	R	R	R	R			
7:0		·		BMXBO	OTSZ<7:0>	_					

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### bit 31-0 BMXBOOTSZ<31:0>: Boot Flash Memory (BFM) Size bits

Static value that indicates the size of the Boot PFM in bytes:

0x00000C00 = Device has 3 KB boot Flash

NOTES:			

#### 5.0 FLASH PROGRAM MEMORY

Note:

This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To complement the information in this data sheet, refer to **Section 5.** "Flash **Program Memory**" (DS60001121), which is available from the *Documentation* > *Reference Manual* section of the Microchip PIC32 web site (www.microchip.com/pic32).

PIC32MX1XX/2XX 28/36/44-pin Family devices contain an internal Flash program memory for executing user code. There are three methods by which the user can program this memory:

- Run-Time Self-Programming (RTSP)
- EJTAG Programming
- In-Circuit Serial Programming™ (ICSP™)

RTSP is performed by software executing from either Flash or RAM memory. Information about RTSP techniques is available in **Section 5.** "Flash Program Memory" (DS60001121) in the "PIC32 Family Reference Manual".

EJTAG is performed using the EJTAG port of the device and an EJTAG capable programmer.

ICSP is performed using a serial data connection to the device and allows much faster programming times than RTSP.

The EJTAG and ICSP methods are described in the "PIC32 Flash Programming Specification" (DS60001145), which can be downloaded from the Microchip web site.

Note

The Flash page size on PIC32MX-1XX/2XX 28/36/44-pin Family devices is 1 KB and the row size is 128 bytes (256 IW and 32 IW, respectively).

5.1 Flash Controller Control Registers
TABLE 5-1: FLASH CONTROLLER REGISTER MAP

s	steseR IIA	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000
	16/0	I									
	17/1	I	NVMOP<3:0>								
	18/2	_	NVMO								
	19/3	I									
	20/4	I	I								
	21/5	I	1								
	22/6		1 1								
S)	23/7		-	/0.45/	0	70.107	0.10	70.40	2.57	70.767	70.16/400
Bits	24/8	I	Ι	NIVMKEV/34:0>		NVMADDR<31:0>		-0.56 ATA CIM. (IA		NVMSRCADDR<31:0>	
	25/9	Ι	Ι							2	Z
	26/10	I	-								
	27/11	I	LVDSTAT								
	28/12	I	LVDERR								
	អ្នក 31/15 30/14 29/13		WRERR								
			WREN								
			WR								
€			15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0
	Register Name			NIVAREN		(1) GGGGALAN (14		ATACA MA	C C C C C C C C C C C C C C C C C C C	E440 NIVMSBCADDE	ADDROVENIA N
	Virtual Addr (#_0878)	00.0	5	7	<u>†</u>	00.6	1420	007	1	07.7	1

This register has corresponding CLR, SET and INV registers at its virtual address, plus offsets of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for more information. x= unknown value on Reset; — = unimplemented, read as '0'. Reset values are shown in hexadecimal.

#### REGISTER 5-1: NVMCON: PROGRAMMING CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31.24	_		_	_	_	_	_	_
23:16	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23.10	_			_	_	_	_	_
15:8	R/W-0	R/W-0	R-0	R-0	R-0	U-0	U-0	U-0
15.6	WR	WREN	WRERR <sup>(1)</sup>	LVDERR <sup>(1)</sup>	LVDSTAT <sup>(1)</sup>	_	_	_
7:0	U-0	U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0
1.0	_	_	_	_		NVMOF	P<3:0>	

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

bit 15 WR: Write Control bit

This bit is writable when WREN = 1 and the unlock sequence is followed.

1 = Initiate a Flash operation. Hardware clears this bit when the operation completes

0 = Flash operation is complete or inactive

bit 14 WREN: Write Enable bit

This is the only bit in this register reset by a device Reset.

1 = Enable writes to WR bit and enables LVD circuit

0 = Disable writes to WR bit and disables LVD circuit

bit 13 WRERR: Write Error bit<sup>(1)</sup>

This bit is read-only and is automatically set by hardware.

1 = Program or erase sequence did not complete successfully

0 = Program or erase sequence completed normally

bit 12 LVDERR: Low-Voltage Detect Error bit (LVD circuit must be enabled)<sup>(1)</sup>

This bit is read-only and is automatically set by hardware.

1 = Low-voltage detected (possible data corruption, if WRERR is set)

0 = Voltage level is acceptable for programming

bit 11 **LVDSTAT:** Low-Voltage Detect Status bit (LVD circuit must be enabled)<sup>(1)</sup>

This bit is read-only and is automatically set and cleared by the hardware.

1 = Low-voltage event is active

0 = Low-voltage event is not active

bit 10-4 **Unimplemented:** Read as '0'

bit 3-0 **NVMOP<3:0>:** NVM Operation bits

These bits are writable when WREN = 0.

1111 = Reserved

•

0111 = Reserved

0110 = No operation

0101 = Program Flash Memory (PFM) erase operation: erases PFM, if all pages are not write-protected

0100 = Page erase operation: erases page selected by NVMADDR, if it is not write-protected

0011 = Row program operation: programs row selected by NVMADDR, if it is not write-protected

0010 = No operation

0001 = Word program operation: programs word selected by NVMADDR, if it is not write-protected

0000 = No operation

**Note 1:** This bit is cleared by setting NVMOP == `b0000, and initiating a Flash operation (i.e., WR).

#### REGISTER 5-2: NVMKEY: PROGRAMMING UNLOCK REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0			
24.24	W-0	W-0	W-0	W-0	W-0	W-0	W-0	W-0			
31:24	NVMKEY<31:24>										
22.46	W-0	W-0	W-0	W-0	W-0	W-0	W-0	W-0			
23:16	NVMKEY<23:16>										
45.0	W-0	W-0	W-0	W-0	W-0	W-0	W-0	W-0			
15:8		NVMKEY<15:8>									
7.0	W-0	W-0	W-0	W-0	W-0	W-0	W-0	W-0			
7:0				NVMK	EY<7:0>						

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-0 NVMKEY<31:0>: Unlock Register bits

These bits are write-only, and read as '0' on any read

Note: This register is used as part of the unlock sequence to prevent inadvertent writes to the PFM.

#### REGISTER 5-3: NVMADDR: FLASH ADDRESS REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0	
24.24	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	
31:24	NVMADDR<31:24>								
00.40	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	
23:16	NVMADDR<23:16>								
15.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	
15:8	NVMADDR<15:8>								
7.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	
7:0				NVMAD	DR<7:0>				

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-0 NVMADDR<31:0>: Flash Address bits

Bulk/Chip/PFM Erase: Address is ignored. Page Erase: Address identifies the page to erase. Row Program: Address identifies the row to program.

Word Program: Address identifies the word to program.

#### REGISTER 5-4: NVMDATA: FLASH PROGRAM DATA REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0		
24.24	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0		
31:24				NVMDA <sup>*</sup>	TA<31:24>					
00.40	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0		
23:16	NVMDATA<23:16>									
45.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0		
15:8				NVMDA	TA<15:8>					
7.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0		
7:0				NVMD	ATA<7:0>					

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### bit 31-0 NVMDATA<31:0>: Flash Programming Data bits

**Note:** The bits in this register are only reset by a Power-on Reset (POR).

#### REGISTER 5-5: NVMSRCADDR: SOURCE DATA ADDRESS REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0			
24.04	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0			
31:24				NVMSRCA	DDR<31:24>	•					
00.40	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0			
23:16	NVMSRCADDR<23:16>										
45.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0			
15:8		NVMSRCADDR<15:8>									
7.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0			
7:0				NVMSRC	ADDR<7:0>						

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### bit 31-0 NVMSRCADDR<31:0>: Source Data Address bits

The system physical address of the data to be programmed into the Flash when the NVMOP<3:0> bits (NVMCON<3:0>) are set to perform row programming.

NOTES:		

#### 6.0 RESETS

Note:


This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To complement the information in this data sheet, refer to **Section 7.** "**Resets**" (DS60001118), which is available from the *Documentation* > *Reference Manual* section of the Microchip PIC32 web site (www.microchip.com/pic32).

The Reset module combines all Reset sources and controls the device Master Reset signal, SYSRST. The following is a list of device Reset sources:

- · Power-on Reset (POR)
- Master Clear Reset pin (MCLR)
- · Software Reset (SWR)
- Watchdog Timer Reset (WDTR)
- · Brown-out Reset (BOR)
- Configuration Mismatch Reset (CMR)

A simplified block diagram of the Reset module is illustrated in Figure 6-1.

#### FIGURE 6-1: SYSTEM RESET BLOCK DIAGRAM



6.1 Reset Control Registers

**RESET CONTROL REGISTER MAP** 

**TABLE 6-1:** 

s	tjəsəЯ IIA	0000	xxxx(2)	0000	0000	
	16/0	Ι	POR	Ι	SWRST	
	17/1	1	BOR	1	I	
	18/2	I	IDLE	_	_	
	19/3	I	SLEEP	_	_	
	20/4	I	WDTO	Ι	Ι	
	21/5	I	I	I	I	
	22/6	I	SWR	Ι	Ι	
Bits	23/7	I	EXTR	1	1	cimal.
	24/8	I	VREGS	-	-	as '0'. Reset values are shown in hexadecimal
	25/9	I	CMR	Ι	Ι	s are show
	26/10	I	I	I	I	eset value
	27/11	I	1	1	1	
	28/12	I	Ι	Ι	Ι	mented, re
	29/13	Ι	Ι	Ι	Ι	- = unimple
	30/14	I	I	I	I	n Reset; –
	31/15		Ι		Ι	vn value o
€	Bit Range	31:16	15:0	31:16	15:0	vouyur
	netsigeЯ <sup>(†)</sup> emsИ	14000		TSGWSG 0187	פאאפא	egend: x = unknown value on Reset; — = unimplemented, read
	Virtual Addr (#_0878)		0001	0.79	2	Legen

All registers in this table have corresponding CLR, SET and INV registers at their virtual addresses, plus offsets of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for

Reset values are dependent on the DEVCFGx Configuration bits and the type of reset.

#### REGISTER 6-1: RCON: RESET CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0	U-0						
31.24	_	_	1	_		_	1	_
23:16	U-0	U-0						
23.10	_	_	-	_		_	_	_
45.0	U-0	U-0	U-0	U-0	U-0	U-0	R/W-0, HS	R/W-0
15:8	_	_	-	_	-	_	CMR	VREGS
7.0	R/W-0, HS	R/W-0, HS	U-0	R/W-0, HS	R/W-0, HS	R/W-0, HS	R/W-1, HS	R/W-1, HS
7:0	EXTR	SWR	_	WDTO	SLEEP	IDLE	BOR <sup>(1)</sup>	POR <sup>(1)</sup>

 Legend:
 HS = Set by hardware

 R = Readable bit
 W = Writable bit
 U = Unimplemented bit, read as '0'

 -n = Value at POR
 '1' = Bit is set
 '0' = Bit is cleared
 x = Bit is unknown

bit 31-10 Unimplemented: Read as '0'

bit 9 CMR: Configuration Mismatch Reset Flag bit

1 = Configuration mismatch Reset has occurred

0 = Configuration mismatch Reset has not occurred

bit 8 VREGS: Voltage Regulator Standby Enable bit

1 = Regulator is enabled and is on during Sleep mode

0 = Regulator is set to standby tracking mode

bit 7 **EXTR:** External Reset (MCLR) Pin Flag bit

1 = Master Clear (pin) Reset has occurred

0 = Master Clear (pin) Reset has not occurred

bit 6 **SWR:** Software Reset Flag bit

1 = Software Reset was executed

0 = Software Reset as not executed

bit 5 Unimplemented: Read as '0'

bit 4 WDTO: Watchdog Timer Time-out Flag bit

1 = WDT Time-out has occurred

0 = WDT Time-out has not occurred

bit 3 SLEEP: Wake From Sleep Flag bit

1 = Device was in Sleep mode

0 = Device was not in Sleep mode

bit 2 IDLE: Wake From Idle Flag bit

1 = Device was in Idle mode

0 = Device was not in Idle mode

bit 1 **BOR:** Brown-out Reset Flag bit<sup>(1)</sup>

1 = Brown-out Reset has occurred

0 = Brown-out Reset has not occurred

bit 0 **POR:** Power-on Reset Flag bit<sup>(1)</sup>

1 = Power-on Reset has occurred

0 = Power-on Reset has not occurred

**Note 1:** User software must clear this bit to view next detection.

#### REGISTER 6-2: RSWRST: SOFTWARE RESET REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31:24	ı	_	ı	1	-		1	_
23:16	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23.10	1		1	1	1		1	_
15:8	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
15.6	_	_	_	_	_	_	_	_
7.0	U-0	U-0	U-0	U-0	U-0	U-0	U-0	W-0, HC
7:0	_	_	_	_	_	_	_	SWRST <sup>(1)</sup>

**Legend:** HC = Cleared by hardware

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-1 Unimplemented: Read as '0'

bit 0 **SWRST:** Software Reset Trigger bit<sup>(1)</sup>

1 = Enable Software Reset event

0 = No effect

Note 1: The system unlock sequence must be performed before the SWRST bit is written. Refer to **Section 6.** "Oscillator" (DS60001112) in the "PIC32 Family Reference Manual" for details.

#### 7.0 INTERRUPT CONTROLLER

Note:

This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To complement the information in this data sheet, refer to **Section 8. "Interrupt Controller"** (DS60001108), which is available from the *Documentation* > *Reference Manual* section of the Microchip PIC32 web site (www.microchip.com/pic32).

PIC32MX1XX/2XX 28/36/44-pin Family devices generate interrupt requests in response to interrupt events from peripheral modules. The interrupt control module exists externally to the CPU logic and prioritizes the interrupt events before presenting them to the CPU.

The PIC32MX1XX/2XX 28/36/44-pin Family interrupt module includes the following features:

- · Up to 64 interrupt sources
- · Up to 44 interrupt vectors
- · Single and multi-vector mode operations
- · Five external interrupts with edge polarity control
- · Interrupt proximity timer
- Seven user-selectable priority levels for each vector
- Four user-selectable subpriority levels within each priority
- Software can generate any interrupt
- User-configurable Interrupt Vector Table (IVT) location
- · User-configurable interrupt vector spacing

**Note:** The dedicated shadow register set is not present on PIC32MX1XX/2XX 28/36/44-pin Family devices.

A simplified block diagram of the Interrupt Controller module is illustrated in Figure 7-1.

FIGURE 7-1: INTERRUPT CONTROLLER MODULE BLOCK DIAGRAM




TABLE 7-1: INTERRUPT IRQ, VECTOR AND BIT LOCATION

Interrupt Source(1)	# Highes	Flag	Enable	Priority	1	
CS0 – Core Software Interrupt 0         1           CS1 – Core Software Interrupt 1         2           INT0 – External Interrupt         3           T1 – Timer1         4           IC1E – Input Capture 1 Error         5           IC1 – Input Capture 1         6           OC1 – Output Compare 1         7           INT1 – External Interrupt 1         8           T2 – Timer2         9           IC2E – Input Capture 2         10           IC2 – Input Capture 2         11           OC2 – Output Compare 2         12           INT2 – External Interrupt 2         13           T3 – Timer3         14           IC3E – Input Capture 3         15           IC3 – Input Capture 3         16           OC3 – Output Compare 3         17           INT3 – External Interrupt 3         18				FITOTILY	Sub-priority	Interrupt
CS0 – Core Software Interrupt 0         1           CS1 – Core Software Interrupt 1         2           INT0 – External Interrupt         3           T1 – Timer1         4           IC1E – Input Capture 1 Error         5           IC1 – Input Capture 1         6           OC1 – Output Compare 1         7           INT1 – External Interrupt 1         8           T2 – Timer2         9           IC2E – Input Capture 2         10           IC2 – Input Capture 2         11           OC2 – Output Compare 2         12           INT2 – External Interrupt 2         13           T3 – Timer3         14           IC3E – Input Capture 3         15           IC3 – Input Capture 3         16           OC3 – Output Compare 3         17           INT3 – External Interrupt 3         18	0	it Natural O	rder Priority	,		
CS1 – Core Software Interrupt 1       2         INT0 – External Interrupt       3         T1 – Timer1       4         IC1E – Input Capture 1 Error       5         IC1 – Input Capture 1       6         OC1 – Output Compare 1       7         INT1 – External Interrupt 1       8         T2 – Timer2       9         IC2E – Input Capture 2       10         IC2 – Input Capture 2       11         OC2 – Output Compare 2       12         INT2 – External Interrupt 2       13         T3 – Timer3       14         IC3E – Input Capture 3       15         IC3 – Input Capture 3       16         OC3 – Output Compare 3       17         INT3 – External Interrupt 3       18	U	IFS0<0>	IEC0<0>	IPC0<4:2>	IPC0<1:0>	No
INT0 - External Interrupt   3   T1 - Timer1   4   IC1E - Input Capture 1 Error   5   IC1 - Input Capture 1   6   OC1 - Output Compare 1   7   INT1 - External Interrupt 1   8   T2 - Timer2   9   IC2E - Input Capture 2   10   IC2 - Input Capture 2   11   OC2 - Output Compare 2   12   INT2 - External Interrupt 2   13   T3 - Timer3   14   IC3E - Input Capture 3   15   IC3 - Input Capture 3   16   OC3 - Output Compare 3   17   INT3 - External Interrupt 3   18	1	IFS0<1>	IEC0<1>	IPC0<12:10>	IPC0<9:8>	No
T1 - Timer1       4         IC1E - Input Capture 1 Error       5         IC1 - Input Capture 1       6         OC1 - Output Compare 1       7         INT1 - External Interrupt 1       8         T2 - Timer2       9         IC2E - Input Capture 2       10         IC2 - Input Capture 2       11         OC2 - Output Compare 2       12         INT2 - External Interrupt 2       13         T3 - Timer3       14         IC3E - Input Capture 3       15         IC3 - Input Capture 3       16         OC3 - Output Compare 3       17         INT3 - External Interrupt 3       18	2	IFS0<2>	IEC0<2>	IPC0<20:18>	IPC0<17:16>	No
IC1E - Input Capture 1 Error       5         IC1 - Input Capture 1       6         OC1 - Output Compare 1       7         INT1 - External Interrupt 1       8         T2 - Timer2       9         IC2E - Input Capture 2       10         IC2 - Input Capture 2       11         OC2 - Output Compare 2       12         INT2 - External Interrupt 2       13         T3 - Timer3       14         IC3E - Input Capture 3       15         IC3 - Input Capture 3       16         OC3 - Output Compare 3       17         INT3 - External Interrupt 3       18	3	IFS0<3>	IEC0<3>	IPC0<28:26>	IPC0<25:24>	No
IC1 - Input Capture 1       6         OC1 - Output Compare 1       7         INT1 - External Interrupt 1       8         T2 - Timer2       9         IC2E - Input Capture 2       10         IC2 - Input Capture 2       11         OC2 - Output Compare 2       12         INT2 - External Interrupt 2       13         T3 - Timer3       14         IC3E - Input Capture 3       15         IC3 - Input Capture 3       16         OC3 - Output Compare 3       17         INT3 - External Interrupt 3       18	4	IFS0<4>	IEC0<4>	IPC1<4:2>	IPC1<1:0>	No
OC1 – Output Compare 1       7         INT1 – External Interrupt 1       8         T2 – Timer2       9         IC2E – Input Capture 2       10         IC2 – Input Capture 2       11         OC2 – Output Compare 2       12         INT2 – External Interrupt 2       13         T3 – Timer3       14         IC3E – Input Capture 3       15         IC3 – Input Capture 3       16         OC3 – Output Compare 3       17         INT3 – External Interrupt 3       18	5	IFS0<5>	IEC0<5>	IPC1<12:10>	IPC1<9:8>	Yes
INT1 - External Interrupt 1   8   T2 - Timer2   9   IC2E - Input Capture 2   10   IC2 - Input Capture 2   11   OC2 - Output Compare 2   12   INT2 - External Interrupt 2   13   T3 - Timer3   14   IC3E - Input Capture 3   15   IC3 - Input Capture 3   16   OC3 - Output Compare 3   17   INT3 - External Interrupt 3   18	5	IFS0<6>	IEC0<6>	IPC1<12:10>	IPC1<9:8>	Yes
INT1 - External Interrupt 1   8   T2 - Timer2   9   IC2E - Input Capture 2   10   IC2 - Input Capture 2   11   OC2 - Output Compare 2   12   INT2 - External Interrupt 2   13   T3 - Timer3   14   IC3E - Input Capture 3   15   IC3 - Input Capture 3   16   OC3 - Output Compare 3   17   INT3 - External Interrupt 3   18	6	IFS0<7>	IEC0<7>	IPC1<20:18>	IPC1<17:16>	No
IC2E - Input Capture 2       10         IC2 - Input Capture 2       11         OC2 - Output Compare 2       12         INT2 - External Interrupt 2       13         T3 - Timer3       14         IC3E - Input Capture 3       15         IC3 - Input Capture 3       16         OC3 - Output Compare 3       17         INT3 - External Interrupt 3       18	7	IFS0<8>	IEC0<8>	IPC1<28:26>	IPC1<25:24>	No
IC2 - Input Capture 2       11         OC2 - Output Compare 2       12         INT2 - External Interrupt 2       13         T3 - Timer3       14         IC3E - Input Capture 3       15         IC3 - Input Capture 3       16         OC3 - Output Compare 3       17         INT3 - External Interrupt 3       18	8	IFS0<9>	IEC0<9>	IPC2<4:2>	IPC2<1:0>	No
OC2 – Output Compare 2       12         INT2 – External Interrupt 2       13         T3 – Timer3       14         IC3E – Input Capture 3       15         IC3 – Input Capture 3       16         OC3 – Output Compare 3       17         INT3 – External Interrupt 3       18	9	IFS0<10>	IEC0<10>	IPC2<12:10>	IPC2<9:8>	Yes
INT2 – External Interrupt 2       13         T3 – Timer3       14         IC3E – Input Capture 3       15         IC3 – Input Capture 3       16         OC3 – Output Compare 3       17         INT3 – External Interrupt 3       18	9	IFS0<11>	IEC0<11>	IPC2<12:10>	IPC2<9:8>	Yes
T3 - Timer3       14         IC3E - Input Capture 3       15         IC3 - Input Capture 3       16         OC3 - Output Compare 3       17         INT3 - External Interrupt 3       18	10	IFS0<12>	IEC0<12>	IPC2<20:18>	IPC2<17:16>	No
IC3E – Input Capture 3       15         IC3 – Input Capture 3       16         OC3 – Output Compare 3       17         INT3 – External Interrupt 3       18	11	IFS0<13>	IEC0<13>	IPC2<28:26>	IPC2<25:24>	No
IC3 – Input Capture 3       16         OC3 – Output Compare 3       17         INT3 – External Interrupt 3       18	12	IFS0<14>	IEC0<14>	IPC3<4:2>	IPC3<1:0>	No
OC3 – Output Compare 3 17 INT3 – External Interrupt 3 18	13	IFS0<15>	IEC0<15>	IPC3<12:10>	IPC3<9:8>	Yes
INT3 – External Interrupt 3 18	13	IFS0<16>	IEC0<16>	IPC3<12:10>	IPC3<9:8>	Yes
·	14	IFS0<17>	IEC0<17>	IPC3<20:18>	IPC3<17:16>	No
T4 – Timer4 19	15	IFS0<18>	IEC0<18>	IPC3<28:26>	IPC3<25:24>	No
	16	IFS0<19>	IEC0<19>	IPC4<4:2>	IPC4<1:0>	No
IC4E – Input Capture 4 Error 20	17	IFS0<20>	IEC0<20>	IPC4<12:10>	IPC4<9:8>	Yes
IC4 – Input Capture 4 21	17	IFS0<21>	IEC0<21>	IPC4<12:10>	IPC4<9:8>	Yes
OC4 – Output Compare 4 22	18	IFS0<22>	IEC0<22>	IPC4<20:18>	IPC4<17:16>	No
INT4 – External Interrupt 4 23	19	IFS0<23>	IEC0<23>	IPC4<28:26>	IPC4<25:24>	No
T5 – Timer5 24	20	IFS0<24>	IEC0<24>	IPC5<4:2>	IPC5<1:0>	No
IC5E – Input Capture 5 Error 25	21	IFS0<25>	IEC0<25>	IPC5<12:10>	IPC5<9:8>	Yes
IC5 – Input Capture 5 26	21	IFS0<26>	IEC0<26>	IPC5<12:10>	IPC5<9:8>	Yes
OC5 – Output Compare 5 27	22	IFS0<27>	IEC0<27>	IPC5<20:18>	IPC5<17:16>	No
AD1 – ADC1 Convert done 28	23	IFS0<28>	IEC0<28>	IPC5<28:26>	IPC5<25:24>	Yes
FSCM – Fail-Safe Clock Monitor 29	24	IFS0<29>	IEC0<29>	IPC6<4:2>	IPC6<1:0>	No
RTCC – Real-Time Clock and Calendar	25	IFS0<30>	IEC0<30>	IPC6<12:10>	IPC6<9:8>	No
FCE – Flash Control Event 31	26	IFS0<31>	IEC0<31>	IPC6<20:18>	IPC6<17:16>	No
CMP1 – Comparator Interrupt 32	27	IFS1<0>	IEC1<0>	IPC6<28:26>	IPC6<25:24>	No
CMP2 – Comparator Interrupt 33	28	IFS1<1>	IEC1<1>	IPC7<4:2>	IPC7<1:0>	No
CMP3 – Comparator Interrupt 34	29	IFS1<2>	IEC1<2>	IPC7<12:10>	IPC7<9:8>	No
USB – USB Interrupts 35	30	IFS1<3>	IEC1<3>	IPC7<20:18>	IPC7<17:16>	Yes
SPI1E – SPI1 Fault 36	31	IFS1<4>	IEC1<4>	IPC7<28:26>	IPC7<25:24>	Yes
SPI1RX – SPI1 Receive Done 37	31	IFS1<5>	IEC1<5>	IPC7<28:26>	IPC7<25:24>	Yes
SPI1TX – SPI1 Transfer Done 38	31	IFS1<6>	IEC1<6>	IPC7<28:26>	IPC7<25:24>	Yes

Note 1: Not all interrupt sources are available on all devices. See TABLE 1: "PIC32MX1XX 28/36/44-Pin General Purpose Family Features" and TABLE 2: "PIC32MX2XX 28/36/44-pin USB Family Features" for the lists of available peripherals.

TABLE 7-1: INTERRUPT IRQ, VECTOR AND BIT LOCATION (CONTINUED)

Interrupt Source <sup>(1)</sup>		Vector		Interru	pt Bit Location		Persistent
Interrupt Source(1)	#	#	Flag	Enable	Priority	Sub-priority	Interrupt
U1E – UART1 Fault	39	32	IFS1<7>	IEC1<7>	IPC8<4:2>	IPC8<1:0>	Yes
U1RX – UART1 Receive Done	40	32	IFS1<8>	IEC1<8>	IPC8<4:2>	IPC8<1:0>	Yes
U1TX – UART1 Transfer Done	41	32	IFS1<9>	IEC1<9>	IPC8<4:2>	IPC8<1:0>	Yes
I2C1B – I2C1 Bus Collision Event	42	33	IFS1<10>	IEC1<10>	IPC8<12:10>	IPC8<9:8>	Yes
I2C1S – I2C1 Slave Event	43	33	IFS1<11>	IEC1<11>	IPC8<12:10>	IPC8<9:8>	Yes
I2C1M – I2C1 Master Event	44	33	IFS1<12>	IEC1<12>	IPC8<12:10>	IPC8<9:8>	Yes
CNA – PORTA Input Change Interrupt		34	IFS1<13>	IEC1<13>	IPC8<20:18>	IPC8<17:16>	Yes
CNB – PORTB Input Change Interrupt	46	34	IFS1<14>	IEC1<14>	IPC8<20:18>	IPC8<17:16>	Yes
CNC – PORTC Input Change Interrupt	47	34	IFS1<15>	IEC1<15>	IPC8<20:18>	IPC8<17:16>	Yes
PMP – Parallel Master Port	48	35	IFS1<16>	IEC1<16>	IPC8<28:26>	IPC8<25:24>	Yes
PMPE – Parallel Master Port Error	49	35	IFS1<17>	IEC1<17>	IPC8<28:26>	IPC8<25:24>	Yes
SPI2E – SPI2 Fault	50	36	IFS1<18>	IEC1<18>	IPC9<4:2>	IPC9<1:0>	Yes
SPI2RX – SPI2 Receive Done	51	36	IFS1<19>	IEC1<19>	IPC9<4:2>	IPC9<1:0>	Yes
SPI2TX – SPI2 Transfer Done	52	36	IFS1<20>	IEC1<20>	IPC9<4:2>	IPC9<1:0>	Yes
U2E – UART2 Error	53	37	IFS1<21>	IEC1<21>	IPC9<12:10>	IPC9<9:8>	Yes
U2RX – UART2 Receiver	54	37	IFS1<22>	IEC1<22>	IPC9<12:10>	IPC9<9:8>	Yes
U2TX – UART2 Transmitter	55	37	IFS1<23>	IEC1<23>	IPC9<12:10>	IPC9<9:8>	Yes
I2C2B – I2C2 Bus Collision Event	56	38	IFS1<24>	IEC1<24>	IPC9<20:18>	IPC9<17:16>	Yes
I2C2S - I2C2 Slave Event	57	38	IFS1<25>	IEC1<25>	IPC9<20:18>	IPC9<17:16>	Yes
I2C2M – I2C2 Master Event	58	38	IFS1<26>	IEC1<26>	IPC9<20:18>	IPC9<17:16>	Yes
CTMU – CTMU Event	59	39	IFS1<27>	IEC1<27>	IPC9<28:26>	IPC9<25:24>	Yes
DMA0 - DMA Channel 0	60	40	IFS1<28>	IEC1<28>	IPC10<4:2>	IPC10<1:0>	No
DMA1 – DMA Channel 1	61	41	IFS1<29>	IEC1<29>	IPC10<12:10>	IPC10<9:8>	No
DMA2 – DMA Channel 2	62	42	IFS1<30>	IEC1<30>	IPC10<20:18>	IPC10<17:16>	No
DMA3 – DMA Channel 3	63	43	IFS1<31>	IEC1<31>	IPC10<28:26>	IPC10<25:24>	No
		Lowes	t Natural O	rder Priority			

Note 1: Not all interrupt sources are available on all devices. See TABLE 1: "PIC32MX1XX 28/36/44-Pin General Purpose Family Features" and TABLE 2: "PIC32MX2XX 28/36/44-pin USB Family Features" for the lists of available peripherals.

Interrupt Control Registers

INTERRUPT REGISTER MAP

**TABLE 7-2:** 

		•								Bits									
Virtual Addre (#_8878)	Register Name <sup>(1)</sup>	Bit Range	31/15	30/14	29/13	28/12	27/11	26/10	25/9	24/8	23/7	22/6	21/5	20/4	19/3	18/2	17/1	16/0	All Resets
000	ACCE.	31:16	1	1	1	I	1	1	1	1	1	1	1	1	1	1	1	Ι	0000
0001		15:0	Ι	Ι	1	MVEC	I		TPC<2:0>		I	1	I	INT4EP	INT3EP	INT2EP	INT1EP I	INTOEP	0000
7	11157747(3)	31:16	1	I	I	I	I	1	I	Ι	I	1	1	Ι	Ι	1	1	1	0000
0.01	ENION	15:0	1	I	1	I	1		SRIPL<2:0>		I	1			VEC<5:0>	,			0000
1020	IPTMR	31:16								IPTMR<31:0>	<0:1							1	0000
000	6	31:16	FCEIF	RTCCIF	FSCMIF	AD1IF	OCSIF	ICSIF	ICSEIF	TSIF	INT4IF	OC4IF	IC4IF	IC4EIF	T4IF	INT3IF	OC3IF	IC3IF	0000
1030	IFS0	15:0	IC3EIF	T3IF	INT2IF	OC2IF	IC2IF	IC2EIF	T2IF	INT1IF	OC1IF	IC1IF	IC1EIF	T1IF	INTOIF	CS1IF	CSOIF	CTIF	0000
7070	2	31:16	<b>DMA3IF</b>	DMA2IF	DMA11F	DMA0IF	CTMUIF	I2C2MIF	I2C2SIF	12C2BIF	U2TXIF	U2RXIF	U2EIF	SPI2TXIF	<b>SPI2RXIF</b>	SPI2EIF PMPEIF		PMPIF	0000
0401	2	15:0	CNCIF	CNBIF	CNAIF	I2C1MIF	I2C1SIF	I2C1BIF	U1TXIF	U1RXIF	U1EIF	SPI1TXIF	SPI1RXIF	SPI1EIF	USBIF <sup>(2)</sup>	<b>CMP3IF</b>	USBIF <sup>(2)</sup> CMP3IF CMP2IF CMP1IF	:MP1IF	0000
000	- C	31:16	FCEIE	RTCCIE	FSCMIE	AD11E	OCSE	ICSIE	IC5EIE	TSIE	INT4IE	OC4IE	IC4IE	IC4EIE	T4IE	INT3IE	OC3IE	IC3IE	0000
0001		15:0	IC3EIE	T3IE	INT2IE	OC2IE	IC2IE	IC2EIE	T2IE	INT1IE	OC1IE	IC1IE	IC1EIE	T11E	INTOIE	CS1IE	CSOIE	CTIE	0000
4070	7	31:16	DMA3IE	<b>DMA2IE</b>	DMA1IE	DMA0IE	CTMUIE	I2C2MIE	12C2SIE	12C2BIE	U2TXIE	UZRXIE	NZEIE	SPI2TXIE	SPI2RXIE	SPIZEIE PMPEIE		PMPIE	0000
0/01	<u> </u>	15:0	CNCIE	CNBIE	CNAIE	I2C1MIE	I2C1SIE	I2C1BIE	U1TXIE	U1RXIE	U1EIE	SPI1TXIE	<b>SPI1RXIE</b>	SPI1EIE	USBIE(2)	CMP3IE	CMP3IE CMP2IE CMP1IE	:MP1IE	0000
1000	UJai	31:16	I	I	I		INT0IP<2:0>		INT0IS<1:0>	<1:0>	I	Ι	I	ű _	CS1IP<2:0>		CS11S<1:0>	1:0>	0000
OSO!	3	15:0	I	I	Ι		CS0IP<2:0>		CS0IS<1:0>	<1:0>	I	Ι	Ι	J	CTIP<2:0>		CTIS<1:0>	<0:	0000
1000	1001	31:16	I	I	I	_	INT11P<2:0>		INT1IS<1:0>	<1:0>	I	-	Ι	Õ	OC1IP<2:0>		OC11S<1:0>	1:0>	0000
040	5	15:0	1	Ι	1		IC1IP<2:0>		IC1IS<1:0>	:1:0>	I	Ι	Ι		T11P<2:0>		T11S<1:0>	<0:	0000
4000	COOL	31:16	_	I	_	-	INT2IP<2:0>		INT2IS<1:0>	<1:0>	1	_	_	Õ	OC2IP<2:0>		OC2IS<1:0>	1:0>	0000
0001	<u> </u>	15:0	I	I	l		IC2IP<2:0>		IC2IS<1:0>	:1:0>	I	Ι	Ι		T2IP<2:0>		T2IS<1:0>	<0:	0000
4000	CJai	31:16	Ι	Ι	Ι	_	INT3IP<2:0>		NT3IS<1:0>	<1:0>	Ι	Ι	Ι	Õ	OC3IP<2:0>		OC3IS<1:0>	1:0>	0000
	3	15:0	Ι	I	_		IC3IP<2:0>		IC3IS<1:0>	:1:0>	I	Ι	1		T3IP<2:0>		T3IS<1:0>	<0:	0000
4000	r Jai	31:16	I	Ι	I		INT4IP<2:0>		INT4IS<1:0>	<1:0>	I	I	Ι	Ō	OC4IP<2:0>		OC4IS<1:0>	1:0>	0000
200	<u>7</u>	15:0	1	I	1		IC4IP<2:0>		IC4IS<1:0>	:1:0>	I	1	Ι		T4IP<2:0>		T4IS<1:0>	<b>.</b>	0000
1010	3001	31:16	I	I	_		AD11P<2:0>		AD11S<1:0>	<1:0>	I	-	Ι	Õ	OC5IP<2:0>		OC5IS<1:0>	1:0>	0000
	3	15:0	Ι	Ι	Ι		IC5IP<2:0>		IC5IS<1:0>	:1:0>	I	I	Ι		T5IP<2:0>		T5IS<1:0>	<0:	0000
1050	aal	31:16	-	Ι	-	)	CMP1IP<2:0>		CMP1IS<1:0>	<1:0>	Ι	-	-	F(	FCEIP<2:0>		FCEIS<1:0>	1:0>	0000
	2	15:0	1	1	I	Ά.	TCCIP<2:0>		RTCCIS<1:0>	<0:1>	I	I	1	FS	FSCMIP<2:0>		FSCMIS<1:0>	<1:0>	0000
Legend:		unknowr	x = unknown value on Reset:	Reset: —=	unimpleme	inted, read as	S'0' Reset vs	alues are sho	— = unimplemented. read as '0'. Reset values are shown in hexadecimal	ecimal						•		÷	

m x = unknown value on Reset; — = unimplemented, read as '0'. Reset values are shown in hexadecimal. Legend:

With the exception of those noted, all registers in this table have corresponding CLR, SET and INV registers at their virtual addresses, plus offsets of 0x4 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for more information.

These bits are not available on PIC32MX1XX devices. Note

**ά** κ

	IIA steseЯ	0000	0000	0000	0000	0000	0000	0000	0000	
	16/0	:1:0>(2)	CMP2IS<1:0>	CNIS<1:0>	<1:0>	<1:0>	<1:0>	DMA2IS<1:0>	DMA0IS<1:0>	
	1/11	USBIS<1:0>(2)	CMP2IS	SINO	<0:1>SI10	<0:1>SIZOZI	<0:1>SIZIS	DMAZIS	DMAOIS	
	18/2									
	19/3	USBIP<2:0>(2)	CMP2IP<2:0>	CNIP<2:0>	U11P<2:0>	I2C2IP<2:0>	SPI2IP<2:0>	DMA2IP<2:0>	DMA0IP<2:0>	
	20/4	SN	C	0	٦	12	S	NO	NO	
	21/5	I	I	I	I	Ι	Ι	I	I	
	22/6	I	Ι	Ι	Ι	Ι	Ι	I	Ι	
	23/7	I	Ι	Ι	Ι	Ι	Ι	I	Ι	
Bits	24/8	SPI11S<1:0>	CMP3IS<1:0>	PMPIS<1:0>	I2C11S<1:0>	CTMUIS<1:0>	U2IS<1:0>	DMA3IS<1:0>	DMA11S<1:0>	
	25/9	SPI1IS	CMP3	SIdWd	12C118	INWLO	-SIZN	DMA3	IIVAMO	
	26/10					•				
	27/11	SPI11P<2:0>	CMP3IP<2:0>	PMPIP<2:0>	I2C1IP<2:0>	CTMUIP<2:0>	U2IP<2:0>	DMA3IP<2:0>	DMA1IP<2:0>	
	28/12		0			0				
	29/13	I	I	Ι	I	I	I	Ι	_	
	30/14	I	I	Ι	I	I	I	I	Ι	
	31/15	I	I	Ι	I	Ι	Ι	I	Ι	
Bit Range		31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	
	Register Name <sup>(1)</sup>	1001	) L	000	<u>}</u>		2	0,000	2	
	nbbA IsutriV (#_8878)	5	3	77	2	7,00	07	00 77	0011	

x = unknown value on Reset; — = unimplemented, read as '0'. Reset values are shown in hexadecimal. Legend: Note

With the exception of those noted, all registers in this table have corresponding CLR, SET and INV registers at their virtual addresses, plus offsets of 0x4 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for more information.

These bits are not available on PIC32MX1XX devices.

This register does not have associated CLR, SET, INV registers.

INTERRUPT REGISTER MAP (CONTINUED)

**TABLE 7-2:** 

#### REGISTER 7-1: INTCON: INTERRUPT CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31.24	_		_	_	1		_	_
23:16	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23.10	_	_		_	1			_
45.0	U-0	U-0	U-0	R/W-0	U-0	R/W-0	R/W-0	R/W-0
15:8	_	_	_	MVEC			TPC<2:0>	
7.0	U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
7:0	_	_	_	INT4EP	INT3EP	INT2EP	INT1EP	INT0EP

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 **Unimplemented:** Read as '0' bit 15-13 **Unimplemented:** Read as '0'

bit 12 MVEC: Multi Vector Configuration bit

1 = Interrupt controller configured for Multi-vectored mode
 0 = Interrupt controller configured for Single-vectored mode

bit 11 Unimplemented: Read as '0'

bit 10-8 TPC<2:0>: Interrupt Proximity Timer Control bits

111 = Interrupts of group priority 7 or lower start the Interrupt Proximity timer 110 = Interrupts of group priority 6 or lower start the Interrupt Proximity timer

101 = Interrupts of group priority 5 or lower start the Interrupt Proximity timer

100 = Interrupts of group priority 4 or lower start the Interrupt Proximity timer

011 = Interrupts of group priority 3 or lower start the Interrupt Proximity timer

010 = Interrupts of group priority 2 or lower start the Interrupt Proximity timer

001 = Interrupts of group priority 1 start the Interrupt Proximity timer

000 = Disables Interrupt Proximity timer

bit 7-5 **Unimplemented:** Read as '0'

bit 4 INT4EP: External Interrupt 4 Edge Polarity Control bit

1 = Rising edge0 = Falling edge

bit 3 INT3EP: External Interrupt 3 Edge Polarity Control bit

1 = Rising edge0 = Falling edge

bit 2 INT2EP: External Interrupt 2 Edge Polarity Control bit

1 = Rising edge0 = Falling edge

bit 1 INT1EP: External Interrupt 1 Edge Polarity Control bit

1 = Rising edge0 = Falling edge

bit 0 **INT0EP:** External Interrupt 0 Edge Polarity Control bit

1 = Rising edge0 = Falling edge

#### REGISTER 7-2: INTSTAT: INTERRUPT STATUS REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31.24	_		_	_			_	_
23:16	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23.10	_	_	_	_	_	_	_	_
45.0	U-0	U-0	U-0	U-0	U-0	R/W-0	R/W-0	R/W-0
15:8	_	_	_	_	_	S	R/W-0 SRIPL<2:0> <sup>(1)</sup>	
7.0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
7:0	_	_			VEC	<5:0> <sup>(1)</sup>		

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-11 Unimplemented: Read as '0'

bit 10-8 SRIPL<2:0>: Requested Priority Level bits<sup>(1)</sup>

111-000 = The priority level of the latest interrupt presented to the CPU

bit 7-6 **Unimplemented:** Read as '0'

bit 5-0 **VEC<5:0>:** Interrupt Vector bits<sup>(1)</sup>

11111-00000 = The interrupt vector that is presented to the CPU

Note 1: This value should only be used when the interrupt controller is configured for Single Vector mode.

#### REGISTER 7-3: IPTMR: INTERRUPT PROXIMITY TIMER REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0			
24.24	R/W-0	R/W-0									
31:24				IPTMF	?<31:24>						
23:16	R/W-0	R/W-0									
23.10	IPTMR<23:16>										
15:8	R/W-0	R/W-0									
13.6				IPTMI	R<15:8>		<b>25/17/9/1</b> R/W-0  R/W-0				
7:0	R/W-0	R/W-0									
7.0				IPTM	R<7:0>	_					

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### bit 31-0 IPTMR<31:0>: Interrupt Proximity Timer Reload bits

Used by the Interrupt Proximity Timer as a reload value when the Interrupt Proximity timer is triggered by an interrupt event.

#### REGISTER 7-4: IFSx: INTERRUPT FLAG STATUS REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.04	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
31:24	IFS31	IFS30	IFS29	IFS28	IFS27	IFS26	IFS25	IFS24
23:16	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
23.10	IFS23	IFS22	IFS21	IFS20	IFS19	IFS18	IFS17	IFS16
15:8	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
15.6	IFS15	IFS14	IFS13	IFS12	IFS11	IFS10	IFS09	IFS08
7:0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
7.0	IFS07	IFS06	IFS05	IFS04	IFS03	IFS02	IFS01	IFS00

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-0 IFS31-IFS00: Interrupt Flag Status bits

1 = Interrupt request has occurred

0 = No interrupt request has occurred

Note: This register represents a generic definition of the IFSx register. Refer to Table 7-1 for the exact bit

definitions.

#### REGISTER 7-5: IECx: INTERRUPT ENABLE CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.04	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
31:24	IEC31	IEC30	IEC29	IEC28	IEC27	IEC26	IEC25	IEC24
23:16	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
23.10	IEC23	IEC22	IEC21	IEC20	IEC19	IEC18	IEC17	IEC16
15:8	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
15.6	IEC15	IEC14	IEC13	IEC12	IEC11	IEC10	IEC09	IEC08
7:0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
7.0	IEC07	IEC06	IEC05	IEC04	IEC03	IEC02	IEC01	IEC00

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-0 IEC31-IEC00: Interrupt Enable bits

1 = Interrupt is enabled 0 = Interrupt is disabled

**Note:** This register represents a generic definition of the IECx register. Refer to Table 7-1 for the exact bit definitions.

#### REGISTER 7-6: IPCx: INTERRUPT PRIORITY CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
31:24	_	_	1		IP03<2:0>		IS03	<1:0>
23:16	U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
23.10	_	_	_		IP02<2:0>		IS02	<1:0>
15:8	U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
13.6	_	_	_		IP01<2:0>		IS01	<1:0>
7:0	U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
7.0	_	_	_		IP00<2:0>		IS00	<1:0>

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-29 **Unimplemented:** Read as '0' bit 28-26 **IP03<2:0>:** Interrupt Priority bits

111 = Interrupt priority is 7

:

010 = Interrupt priority is 2

001 = Interrupt priority is 1

000 = Interrupt is disabled

bit 25-24 IS03<1:0>: Interrupt Subpriority bits

11 = Interrupt subpriority is 3

10 = Interrupt subpriority is 2

01 = Interrupt subpriority is 1

00 = Interrupt subpriority is 0

bit 23-21 Unimplemented: Read as '0'

bit 20-18 IP02<2:0>: Interrupt Priority bits

111 = Interrupt priority is 7

•

010 = Interrupt priority is 2

001 = Interrupt priority is 1

000 = Interrupt is disabled

bit 17-16 IS02<1:0>: Interrupt Subpriority bits

11 = Interrupt subpriority is 3

10 = Interrupt subpriority is 2

01 = Interrupt subpriority is 1

00 = Interrupt subpriority is 0

bit 15-13 Unimplemented: Read as '0'

bit 12-10 IP01<2:0>: Interrupt Priority bits

111 = Interrupt priority is 7

•

.

010 = Interrupt priority is 2

001 = Interrupt priority is 1

000 = Interrupt is disabled

**Note:** This register represents a generic definition of the IPCx register. Refer to Table 7-1 for the exact bit definitions.

#### REGISTER 7-6: IPCx: INTERRUPT PRIORITY CONTROL REGISTER (CONTINUED)

```
bit 9-8
          IS01<1:0>: Interrupt Subpriority bits
          11 = Interrupt subpriority is 3
          10 = Interrupt subpriority is 2
          01 = Interrupt subpriority is 1
          00 = Interrupt subpriority is 0
bit 7-5
          Unimplemented: Read as '0'
bit 4-2
          IP00<2:0>: Interrupt Priority bits
          111 = Interrupt priority is 7
          010 = Interrupt priority is 2
          001 = Interrupt priority is 1
          000 = Interrupt is disabled
bit 1-0
          IS00<1:0>: Interrupt Subpriority bits
          11 = Interrupt subpriority is 3
           10 = Interrupt subpriority is 2
           01 = Interrupt subpriority is 1
           00 = Interrupt subpriority is 0
```

**Note:** This register represents a generic definition of the IPCx register. Refer to Table 7-1 for the exact bit definitions.

# 8.0 OSCILLATOR CONFIGURATION

Note:


This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To complement the information in this data sheet, refer to Section 6. "Oscillator Configuration" (DS60001112), which is available from the Documentation > Reference Manual section of the PIC32 Microchip web site (www.microchip.com/pic32).

The PIC32MX1XX/2XX 28/36/44-pin Family oscillator system has the following modules and features:

- Four external and internal oscillator options as clock sources
- On-Chip PLL with user-selectable input divider, multiplier and output divider to boost operating frequency on select internal and external oscillator sources
- On-Chip user-selectable divisor postscaler on select oscillator sources
- Software-controllable switching between various clock sources
- A Fail-Safe Clock Monitor (FSCM) that detects clock failure and permits safe application recovery or shutdown
- · Dedicated On-Chip PLL for USB peripheral

A block diagram of the oscillator system is provided in Figure 8-1.

FIGURE 8-1: OSCILLATOR DIAGRAM



- Notes: 1. A series resistor, Rs, may be required for AT strip cut crystals or eliminate clipping. Alternately, to increase oscillator circuit gain, add a parallel resistor, RP, with a value of 1 MΩ.
  - Refer to Section 6. "Oscillator Configuration" (DS60001112) in the "PIC32 Family Reference Manual" for help in determining the best oscillator components.
  - 3. The PBCLK out is only available on the OSC2 pin in certain clock modes.
  - 4. The USB PLL is only available on PIC32MX2XX devices.

# **Oscillator Control Regiters**

**OSCILLATOR CONTROL REGISTER MAP TABLE 8-1:** 

s	teseЯ IIA	$\times 1 \times \times (2)$	xxxx(2)	0000	0000	0000	0000	0000	0000	
	16/0		OSWEN	_				Ι	_	
	17/1	PLLMULT<2:0>	UFRCEN(3) SOSCEN OSWEN	_			ROSEL<3:0>	-	1	
	18/2	Ы	UFRCEN <sup>(3)</sup>	_	LUN<5:0>		ROSE	_	-	
	19/3	PBDIV<1:0>	CF	I	TUT			I	I	
	20/4	PBDIV	SLPEN	I			I	I	I	
	21/5	SOSCRDY PBDIVRDY	SLOCK	-			1	-	I	
	22/6	SOSCRDY	CLKLOCK ULOCK <sup>(3)</sup>	Ι	Ι	4:0>	I	I	I	
Bits	23/7	I	CLKLOCK	_	-	RODIV<14:0>	-		-	simal.
	24/8	Δ		Ι	Ι		ACTIVE		I	in hexade
	25/9	FRCDIV<2:0>	NOSC<2:0>	_	-		DIVSWEN ACTIVE		1	as '0'. Reset values are shown in hexadecimal.
	26/10	Ш		١	I		١	<0	I	eset values
	27/11	^(	Ι	Ι	Ι		RSLP	ROTRIM<8:0>	1	ld as '0'. Re
	28/12	PLLODIV<2:0>	^	Ι	Ι		OE	R	1	$\mathbf{x}$ = unknown value on Reset; — = unimplemented, read
	29/13	<u></u>	COSC<2:0>	Ι	Ι		SIDL		1	- = unimple
	30/14	I		Ι	Ι		I		1	n Reset; —
	31/15	I	I	I	I	I	NO		I	n value oi
e	Bit Range	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	nouyur
	netsigeЯ <sup>(1)</sup> emsM	LOOD OSCION	20000	MILLE	20.000 0101	14000110	F020 REFOCON		FUSU NEFO I NIM	
ssə.	Virtual Addr (#_0878)			0.40	2	ı	F020	0	F030	Legend:

All registers in this table have corresponding CLR, SET and INV registers at their virtual addresses, plus offsets of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for Note

Reset values are dependent on the DEVCFGx Configuration bits and the type of reset. This bit is only available on PIC32MX2XX devices. <u>ო</u> წ

#### REGISTER 8-1: OSCCON: OSCILLATOR CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0	U-0	R/W-y	R/W-y	R/W-y	R/W-0	R/W-0	R/W-1
31:24	_	_	Р	LLODIV<2:0	>	F	RCDIV<2:0>	
00.46	U-0	R-0	R-1	R/W-y	R/W-y	R/W-y	R/W-y	R/W-y
23:16	_	SOSCRDY	PBDIVRDY	PBDI\	/<1:0>	Р	LLMULT<2:0>	•
45.0	U-0	R-0	R-0	R-0	U-0	R/W-y	R/W-y	R/W-y
15:8	_		COSC<2:0>		_		NOSC<2:0>	
7.0	R/W-0	R-0	R-0	R/W-0	R/W-0	R/W-0	R/W-y	R/W-0
7:0	CLKLOCK	ULOCK <sup>(1)</sup>	SLOCK	SLPEN	CF	UFRCEN <sup>(1)</sup>	SOSCEN	OSWEN

Legend:y = Value set from Configuration bits on PORR = Readable bitW = Writable bitU = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

```
bit 31-30 Unimplemented: Read as '0'
```

bit 29-27 PLLODIV<2:0>: Output Divider for PLL

111 = PLL output divided by 256

110 = PLL output divided by 64

101 = PLL output divided by 32

100 = PLL output divided by 16

011 = PLL output divided by 8

010 = PLL output divided by 4

001 = PLL output divided by 2

000 = PLL output divided by 1

bit 26-24 FRCDIV<2:0>: Internal Fast RC (FRC) Oscillator Clock Divider bits

111 = FRC divided by 256

110 = FRC divided by 64

101 = FRC divided by 32

100 = FRC divided by 16

011 = FRC divided by 8

010 = FRC divided by 4

001 = FRC divided by 2 (default setting)

000 = FRC divided by 1

bit 23 Unimplemented: Read as '0'

bit 22 SOSCRDY: Secondary Oscillator (Sosc) Ready Indicator bit

1 = The Secondary Oscillator is running and is stable

0 = The Secondary Oscillator is still warming up or is turned off

bit 21 PBDIVRDY: Peripheral Bus Clock (PBCLK) Divisor Ready bit

1 = PBDIV<1:0> bits can be written

0 = PBDIV<1:0> bits cannot be written

bit 20-19 PBDIV<1:0>: Peripheral Bus Clock (PBCLK) Divisor bits

11 = PBCLK is SYSCLK divided by 8 (default)

10 = PBCLK is SYSCLK divided by 4

01 = PBCLK is SYSCLK divided by 2

00 = PBCLK is SYSCLK divided by 1

Note 1: This bit is only available on PIC32MX2XX devices.

**Note:** Writes to this register require an unlock sequence. Refer to **Section 6. "Oscillator"** (DS60001112) in the "PIC32 Family Reference Manual" for details.

#### **REGISTER 8-1:** OSCCON: OSCILLATOR CONTROL REGISTER bit 18-16 PLLMULT<2:0>: Phase-Locked Loop (PLL) Multiplier bits 111 = Clock is multiplied by 24 110 = Clock is multiplied by 21 101 = Clock is multiplied by 20 100 = Clock is multiplied by 19 011 = Clock is multiplied by 18 010 = Clock is multiplied by 17 001 = Clock is multiplied by 16 000 = Clock is multiplied by 15 bit 15 Unimplemented: Read as '0' bit 14-12 COSC<2:0>: Current Oscillator Selection bits 111 = Internal Fast RC (FRC) Oscillator divided by FRCDIV<2:0> bits (OSCCON<26:24>) 110 = Internal Fast RC (FRC) Oscillator divided by 16 101 = Internal Low-Power RC (LPRC) Oscillator 100 = Secondary Oscillator (Sosc) 011 = Primary Oscillator (Posc) with PLL module (XTPLL, HSPLL or ECPLL) 010 = Primary Oscillator (Posc) (XT, HS or EC) 001 = Internal Fast RC Oscillator with PLL module via Postscaler (FRCPLL) 000 = Internal Fast RC (FRC) Oscillator hit 11 Unimplemented: Read as '0' bit 10-8 NOSC<2:0>: New Oscillator Selection bits 111 = Internal Fast RC Oscillator (FRC) divided by OSCCON<FRCDIV> bits 110 = Internal Fast RC Oscillator (FRC) divided by 16 101 = Internal Low-Power RC (LPRC) Oscillator 100 = Secondary Oscillator (Sosc) 011 = Primary Oscillator with PLL module (XTPLL, HSPLL or ECPLL) 010 = Primary Oscillator (XT, HS or EC) 001 = Internal Fast Internal RC Oscillator with PLL module via Postscaler (FRCPLL) 000 = Internal Fast Internal RC Oscillator (FRC) On Reset, these bits are set to the value of the FNOSC Configuration bits (DEVCFG1<2:0>). bit 7 **CLKLOCK:** Clock Selection Lock Enable bit If clock switching and monitoring is disabled (FCKSM<1:0> = 1x): 1 = Clock and PLL selections are locked 0 = Clock and PLL selections are not locked and may be modified If clock switching and monitoring is enabled (FCKSM<1:0> = 0x): Clock and PLL selections are never locked and may be modified. ULOCK: USB PLL Lock Status bit(1) bit 6 1 = The USB PLL module is in lock or USB PLL module start-up timer is satisfied 0 =The USB PLL module is out of lock or USB PLL module start-up timer is in progress or the USB PLL is disabled bit 5 **SLOCK: PLL Lock Status bit** 1 = The PLL module is in lock or PLL module start-up timer is satisfied 0 = The PLL module is out of lock, the PLL start-up timer is running, or the PLL is disabled bit 4 SLPEN: Sleep Mode Enable bit 1 = The device will enter Sleep mode when a WAIT instruction is executed 0 = The device will enter Idle mode when a WAIT instruction is executed Note 1: This bit is only available on PIC32MX2XX devices.

Writes to this register require an unlock sequence. Refer to Section 6. "Oscillator" (DS60001112) in the

"PIC32 Family Reference Manual" for details.

Note:

#### REGISTER 8-1: OSCCON: OSCILLATOR CONTROL REGISTER

- - 1 = FSCM has detected a clock failure
  - 0 = No clock failure has been detected
- bit 2 UFRCEN: USB FRC Clock Enable bit<sup>(1)</sup>
  - 1 = Enable the FRC as the clock source for the USB clock source
  - 0 = Use the Primary Oscillator or USB PLL as the USB clock source
- bit 1 SOSCEN: Secondary Oscillator (Sosc) Enable bit
  - 1 = Enable the Secondary Oscillator
  - 0 = Disable the Secondary Oscillator
- bit 0 **OSWEN:** Oscillator Switch Enable bit
  - 1 = Initiate an oscillator switch to selection specified by NOSC<2:0> bits
  - 0 = Oscillator switch is complete
- Note 1: This bit is only available on PIC32MX2XX devices.

**Note:** Writes to this register require an unlock sequence. Refer to **Section 6. "Oscillator"** (DS60001112) in the "PIC32 Family Reference Manual" for details.

#### **REGISTER 8-2: OSCTUN: FRC TUNING REGISTER**

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31:24	_	_	-	_	-	_	-	_
22.46	U-0	R-0	U-0	U-0	U-0	U-0	U-0	U-0
23:16	_	_	-	_	-	_	-	_
15.0	U-0	R-0	U-0	U-0	U-0	U-0	U-0	U-0
15:8	_	_	-	_	-	_	-	_
7.0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
7:0	_	_			TUN<	5:0> <sup>(1)</sup>		

Legend:W = Writable bitU = Unimplemented bit, read as '0'-n = Value at POR'1' = Bit is set'0' = Bit is clearedx = Bit is unknown

011111 = Center frequency +12.5%

**Note 1:** OSCTUN functionality has been provided to help customers compensate for temperature effects on the FRC frequency over a wide range of temperatures. The tuning step size is an approximation, and is neither characterized, nor tested.

**Note:** Writes to this register require an unlock sequence. Refer to **Section 6. "Oscillator"** (DS60001112) in the "PIC32 Family Reference Manual" for details.

#### REGISTER 8-3: REFOCON: REFERENCE OSCILLATOR CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
04.04	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
31:24	_			R	ODIV<14:8> <sup>(</sup>	1,3)		
00.40	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
23:16				RODIV<	7:0> <sup>(1,3)</sup>			
45.0	R/W-0	U-0	R/W-0	R/W-0	R/W-0	U-0	R/W-0, HC	R-0, HS, HC
15:8	ON		SIDL	OE	RSLP <sup>(2)</sup>		DIVSWEN	ACTIVE
7.0	U-0	U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0
7:0	_		_	_		ROSEL	.<3:0> <sup>(1)</sup>	

Legend:HC = Hardware ClearableHS = Hardware SettableR = Readable bitW = Writable bitU = Unimplemented bit, read as '0'-n = Value at POR'1' = Bit is set'0' = Bit is clearedx = Bit is unknown

bit 31 Unimplemented: Read as '0'

bit 30-16 RODIV<14:0> Reference Clock Divider bits(1,3)

The value selects the reference clock divider bits. See Figure 8-1 for information.

bit 15 **ON:** Output Enable bit

bit 14

1 = Reference Oscillator module is enabled

0 = Reference Oscillator module is disabled

bit 13 SIDL: Peripheral Stop in Idle Mode bit

Unimplemented: Read as '0'

1 = Discontinue module operation when the device enters Idle mode

0 = Continue module operation when the device enters Idle mode

bit 12 **OE:** Reference Clock Output Enable bit

1 = Reference clock is driven out on REFCLKO pin

0 = Reference clock is not driven out on REFCLKO pin

bit 11 RSLP: Reference Oscillator Module Run in Sleep bit (2)

1 = Reference Oscillator module output continues to run in Sleep

0 = Reference Oscillator module output is disabled in Sleep

bit 10 Unimplemented: Read as '0'

bit 9 **DIVSWEN:** Divider Switch Enable bit

1 = Divider switch is in progress

0 = Divider switch is complete

bit 8 ACTIVE: Reference Clock Request Status bit

1 = Reference clock request is active

0 = Reference clock request is not active

bit 7-4 Unimplemented: Read as '0'

Note 1: The ROSEL and RODIV bits should not be written while the ACTIVE bit is '1', as undefined behavior may result.

2: This bit is ignored when the ROSEL<3:0> bits = 0000 or 0001.

3: While the ON bit is set to '1', writes to these bits do not take effect until the DIVSWEN bit is also set to '1'.

#### REGISTER 8-3: REFOCON: REFERENCE OSCILLATOR CONTROL REGISTER

bit 3-0 ROSEL<3:0>: Reference Clock Source Select bits<sup>(1)</sup>

```
1111 = Reserved; do not use
```

•

•

1001 = Reserved; do not use

1000 = REFCLKI

0111 = System PLL output

0110 = USB PLL output

0101 = Sosc

0100 = LPRC

0011 = FRC

0010 = Posc

0001 = PBCLK

0000 = SYSCLK

- Note 1: The ROSEL and RODIV bits should not be written while the ACTIVE bit is '1', as undefined behavior may result.
  - 2: This bit is ignored when the ROSEL<3:0> bits = 0000 or 0001.
  - 3: While the ON bit is set to '1', writes to these bits do not take effect until the DIVSWEN bit is also set to '1'.

#### REGISTER 8-4: REFOTRIM: REFERENCE OSCILLATOR TRIM REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.04	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
31:24				ROTRIN	Л<8:1>			
00.40	R/W-0	R-0	U-0	U-0	U-0	U-0	U-0	U-0
23:16	ROTRIM<0>	_	_	_	_	_	_	_
45.0	U-0	R-0	U-0	U-0	U-0	U-0	U-0	U-0
15:8	_	_	_	_	_	_	_	_
7.0	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
7:0	_	_	_	_	_	_	_	_

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-23 ROTRIM<8:0>: Reference Oscillator Trim bits

111111111 = 511/512 divisor added to RODIV value

111111110 = 510/512 divisor added to RODIV value

.

.

100000000 = 256/512 divisor added to RODIV value

•

.

000000010 = 2/512 divisor added to RODIV value

000000001 = 1/512 divisor added to RODIV value

000000000 = 0/512 divisor added to RODIV value

bit 22-0 Unimplemented: Read as '0'

**Note:** While the ON (REFOCON<15>) bit is '1', writes to this register do not take effect until the DIVSWEN bit is also set to '1'.

# 9.0 DIRECT MEMORY ACCESS (DMA) CONTROLLER

Note: This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To complement the information in this data sheet, refer to Section 31. "Direct Memory Access (DMA) Controller" (DS60001117), which is available from the Documentation > Reference Manual section of the Microchip PIC32 web site

The PIC32 Direct Memory Access (DMA) controller is a bus master module useful for data transfers between different devices without CPU intervention. The source and destination of a DMA transfer can be any of the memory mapped modules existent in the PIC32, such as Peripheral Bus devices: SPI, UART, PMP, etc., or memory itself. Figure 9-1 show a block diagram of the DMA Controller module.


(www.microchip.com/pic32).

The DMA Controller module has the following key features:

- · Four identical channels, each featuring:
  - Auto-increment source and destination address registers
  - Source and destination pointers
  - Memory to memory and memory to peripheral transfers
- · Automatic word-size detection:
  - Transfer granularity, down to byte level
  - Bytes need not be word-aligned at source and destination

- · Fixed priority channel arbitration
- · Flexible DMA channel operating modes:
- Manual (software) or automatic (interrupt)
   DMA requests
- One-Shot or Auto-Repeat Block Transfer modes
- Channel-to-channel chaining
- · Flexible DMA requests:
  - A DMA request can be selected from any of the peripheral interrupt sources
  - Each channel can select any (appropriate) observable interrupt as its DMA request source
  - A DMA transfer abort can be selected from any of the peripheral interrupt sources
  - Pattern (data) match transfer termination
- · Multiple DMA channel status interrupts:
  - DMA channel block transfer complete
  - Source empty or half empty
  - Destination full or half full
  - DMA transfer aborted due to an external event
  - Invalid DMA address generated
- · DMA debug support features:
  - Most recent address accessed by a DMA channel
  - Most recent DMA channel to transfer data
- · CRC Generation module:
  - CRC module can be assigned to any of the available channels
  - CRC module is highly configurable





9.1 DMA Control Registers

TABLE 9-1: DMA GLOBAL REGISTER MAP

s	steseR IIA	0000	0000	0000	0000	0000
	16/0	1	Ι	Ι	(2)	
	17/1	1	Ι	Ι	DMACH<2:0>(2)	
	18/2	1	Ι	Ι	۵	
	19/3	1	Ι	_	RDWR	
	20/4	1	Ι	_	_	
	21/5	1	Ι	_	Ι	
	22/6	1	Ι	-	Ι	
Bits	23/7	1	Ι	_	-	DMAADDR<31:0>
B	24/8	1	Ι	Ι	Ι	DMAADE
	25/9	1	Ι	-	Ι	
	26/10	1	1	-	Ι	
	27/11	1	DMABUSY	_	_	
	28/12	1	SUSPEND	-	Ι	
	29/13	1	Ι	_	-	
	30/14	1	Ι	_	-	
	31/15	I	NO	I	Ι	
•	Bit Range	31:16	15:0	31:16	15:0	31:16
	Register Name <sup>(1)</sup>	200	N N N N N N N N N N N N N N N N N N N	TATOAMA	I CENIO	3020 DMAADDR
ssə	Virtual Addr (#_8878)		2000	0,00	20.00	3020

**Legend:** x = unknown value on Reset; - = unimplemented, read as '0'. Reset values are shown in hexadecimal.

**DMA CRC REGISTER MAP** 

**TABLE 9-2:** 

All registers in this table have corresponding CLR, SET and INV registers at its virtual address, plus an offset of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for more information. ÷

s	steseЯ IIA	0000	0000	0000	0000	0000	0000	
	16/0	1	,					
	17/1	I	CRCCH<2:0>					
	18/2	I	O					
	19/3	I	-					
	20/4	I	-					
	21/5	1						
	22/6	I	CRCEN CRCAPP CRCTYP					
Bits	23/7	1		70.107	70.1677			
8	24/8	BITO		DCRCXOR<31:0>				
	25/9	I						
	26/10	I						
	27/11	WBO						
	28/12	BYTO<1:0>						
	29/13	BYTC						
	30/14	1						
	31/15	1						
	Bit Range	31:16	15:0	31:16	15:0	31:16	15:0	
	Register Name <sup>(1)</sup>	1000000	2000200	DCRCDATA		acyclac	אטאטאטט	
	Virtual Addr (#_8878)		2020	3040		2050	ococ	

**-egend:** x = unknown value on Reset; — = unimplemented, read as '0'. Reset values are shown in hexadecimal.

All registers in this table have corresponding CLR, SET and INV registers at their virtual addresses, plus offsets of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for more information.

TAB	TABLE 9-3:	Δ	DMA CHANNELS 0-3 REGISTER	NNELS	0-3 RE	GISTER	MAP												
SSƏ		(								Bits	ts								9
vittual Addr (#_8878)	Register ( <sup>1)</sup>	Bit Range	31/15	30/14	29/13	28/12	27/11	26/10	25/9	24/8	23/7	22/6	21/5	20/4	19/3	18/2	17/1	16/0	steseЯ IIA
		31:16	I	1	1	I	I	1	1	I	I	1	1	ı	1	1	1	1	0000
3060	DCHOCON	15:0	CHBUSY	_	1	-	-	-	_	CHCHNS	CHEN	CHAED	CHCHN	CHAEN	-	CHEDET	CHPRI<1:0>		0000
0206	NODECON.	31:16	1	1	1	-	1	1	1	Ι				CHAIRQ<7:0>	3<7:0>			)	00FF
3070	NOCHOECON	15:0				CHSIRC	Q<7:0>				CFORCE	CABORT	PATEN	SIRGEN	AIRGEN	I	Ι	-	FF00
000	TIVIOLOG	31:16	_	_	-	_	-	_	_	-	CHSDIE	CHSHIE	CHDDIE		CHBCIE	CHCCIE	CHTAIE	CHERIE	0000
2000		15:0	1	1	1	-	-	1	1	Ι	CHSDIF	CHSHIF	CHDDIF	CHDHIF	CHBCIF	CHCCIF	CHTAIF	CHERIF	0000
3090	DCH0SSA	31:16								CHSSA<31:0>	<31:0>							0 0	0000
30A0	DCHODSA	31:16								CHDSA<31:0>	<31:0>							0,0	0000
0000	710001100	31:16	I	I	I	I	I	1	I	I	I	I	I	I	Ι	I	I	1	0000
3080		15:0						•		CHSSIZ<15:0>	:<15:0>								0000
0000	DCHODS17	31:16	_	1	I	-	-	_	Ι	Ι	-	-	_	1	Ι	_	_	_	0000
3		15:0								CHDSIZ<15:0>	<15:0>							)	0000
000	a Fason Co	31:16	Ι	1	I	I	1	-	I	I	-	I	_	1	I	1	l		0000
3000		15:0								CHSPTR<15:0>	<<15:0>							)	0000
2000	Tadona	31:16	Ι	Ι	Ι	1	Ι	Ι	Ι	Ι	Ι	I	Ι	I	I	Ι	ı		0000
30F		15:0								CHDPTR<15:0>	<b>&lt;</b> 15:0>						•	Ü	0000
30E0	VISCHOUS IN	31:16	I	Ι	I	l	Ι	Ι	Ι	Ι	Ι	Ι	1	I	I	Ι	1		0000
5		15:0		•		•			·	CHCSIZ<15:0>	:<15:0>			·		•	•	U	0000
3100	ALGOUNDER	31:16	1	Ι	I	Ι	Ι	1	1	Ι	I	Ī	1	Ι	1	1	1	-	0000
5		15:0		•		•			·	CHCPTR<15:0>	<b>&lt;&lt;15:0&gt;</b>			·		•	•	U	0000
3110	DCH0DAT	31:16	I	I	I	I	I	I	I	I	-		1	——————————————————————————————————————	1/7/0/	1	1	1	0000
		-												5	0.77				
3120	DCH1CON		CHBUSY	l	l				1 1	CHCHNS	CHEN	CHAED	CHCHN	CHAEN		CHEDET	CHPRI<1:0>		0000
3		` '	I	I	I	I	I	1	I	I				CHAIRQ<7:0>	3<7:0>				00FF
3130	DCHIECON	15:0				CHSIRQ<7:0>	<0:∠>₹				CFORCE	CABORT	PATEN		AIRGEN	I	Ι		FF00
3140	DCH1INT	31:16	I	1	I	1	I	1	1	I	CHSDIE		CHDDIE	-	CHBCIE	CHCCIE	CHTAIE		0000
5		15:0	I	1	I	I	1	1	1	I	CHSDIF	CHSHIF	CHDDIF	CHDHIF	CHBCIF	CHCCIF	CHTAIF	CHERIF	0000
3150	DCH1SSA	31:16								CHSSA<31:0>	<31:0>							0 0	0000
3160	DCH1DSA	31:16								CHDSA<31:0>	<31:0>							0 0	0000
Legend:		ınknown	x = unknown value on Reset; — = unimplemented, read as '0'. Reset values are shown in hexadecimal	eset; — = L	unimplemer	ited, read as	s '0'. Reset	values are	shown in he	exadecimal.									

All registers in this table have corresponding CLR, SET and INV registers at their virtual addresses, plus offsets of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" more information. ÷ Note

TABLE	LE 9-3:	ā	DMA CHANNELS 0-3 REGISTER	NNELS	0-3 RE(	GISTER		MAP (CONTINUED)	JED)										
ssə		•								Bits	γo								9
Virtual Addr (#_8878)	Register Name <sup>(1)</sup>	Bit Range	31/15	30/14	29/13	28/12	27/11	26/10	25/9	24/8	23/7	22/6	21/5	20/4	19/3	18/2	17/1	16/0	steseR IIA
24.70	71331170	31:16	1	Ι	I	1	-	-	-	Ι	Ι	I	I	-	-	1	_	-	0000
0/16		15:0								CHSSIZ<15:0>	<15:0>								0000
2		31:16	I	I	1	I	I	1	ı	1	1	I	I	ı	ı	ı	I	ı	0000
3180	DCH IDSIZ	15:0								CHDSIZ<15:0>	<15:0>								0000
		31:16	I	I	1	I	I	I	I	I	I	I	I	I	I	I	I	I	0000
3180	אושפוחטט	15:0								CHSPTR<15:0>	<15:0>								0000
	araakhaa	31:16	Ι	Ι	I	Ι	Ι	I	1	I	1	Ι	Ι	_	Ι	I	-	I	0000
3 I AU	או ייון אטו אטט	15:0								CHDPTR<15:0>	:<15:0>								0000
7		31:16	I	I	I	I	_	I	I	I	1	I	1	_	I	I	Ι	1	0000
3160	DCHICSIZ	15:0								CHCSIZ<15:0>	<15:0>								0000
3	1 20 2	31:16	I	1	I	1	1	1	1	1	I	I	I	1	1	1	1	1	0000
ري ا	31 CO DCH1CP18	15:0								CHCPTR<15:0>	:<15:0>								0000
2		31:16	I	I	1	I	I	I	I	I	I	I	I	I	I	I	I	I	0000
3100	DCHIDAL	15:0	1	-	-	-	-	_	_	_				CHPDAT<7:0>	T<7:0>				0000
31E0	NOJCHJU	31:16	Ι	1	1	-	1	1	1	1	-	1	Ι	1	1	1	1	-	0000
3150		15:0	CHBUSY	1	Ι	1	-	1	1	CHCHNS	CHEN	CHAED	CHCHN	CHAEN	-	CHEDET	CHPRI<1:0>		0000
0110	140036134	31:16	Ι	I	I	Ι	Ι	Ι	Ι	Ι				CHAIRQ<7:0>	<0:7>¢				4400
		15:0				CHSIR	:Q<7:0>					CABORT	PATEN	SIRQEN	AIRQEN	1	_		FF00
3200	INICHOU	31:16	Ι	I	1	Ι	Ι	Ι	Ι	I	CHSDIE	CHSHIE	CHDDIE	CHDHIE	CHBCIE	CHCCIE	CHTAIE		0000
2500		15:0	1	I	I	1	Ι	Ι	Ι	I	CHSDIF	CHSHIF	CHDDIF	CHDHIF	CHBCIF	CHCCIF	CHTAIF	CHERIF	0000
3210	DCH2SSA	31:16								CHSSA<31:0>	<31:0>								0000
3220	DCH2DSA	31:16								CHDSA<31:0>	<31:0>								0000
3230	213361134	31:16	Ι	1	Ι	1	_	_	_	-	-	Ι	Ι	_	1	Ι	_	1	0000
2230	DCUZOSIZ	15:0			1					CHSSIZ<15:0>	<15:0>								0000
07.00	213461134	31:16	Ι	Ι	I	Ι	Ι	Ι	Ι	I	Ι	Ι	Ι	_	I	I	_	I	0000
3240		15:0			1					CHDSIZ<15:0>	<15:0>								0000
3250	3250 DCH2SETE	31:16	Ι	1	I		1	1	_	1		1	1	_	-		_		0000
0220	5 5 5 5	15:0								CHSPTR<15:0>	<15:0>	•		•		•	•		0000
3260	пснопртв	(.)	Ι	I	Ι	Ι	Ι	1	Ι	Ι	Ι	1	1	_	1	Ι	Ι	-	0000
0200										CHDPTR<15:0>	<15:0>								0000
3270	DCH2CS17	(.)	I	1	I	1	I	1	I	1	I	I	I	I	1	I	I	I	0000
21.0		15:0								CHCSIZ<15:0>	<15:0>								0000
Legend:		unknowr	${f x}$ = unknown value on Reset; — = unimplemented, read as '0'. Reset values are shown in hexadecimal	eset; — = u	ınimplemen	ted, read a	s '0'. Reset	values are	shown in he	xadecimal.									

x = unknown value on Reset; — = unimplemented, read as '0 : Reset values are snown in nexadecimal.

All registers in this table have corresponding CLR, SET and INV registers at their virtual addresses, plus offsets of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for more information.

ф

All registers in this table have corresponding CLR, SET and INV registers at their virtual addresses, plus offsets of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" more information.

TAB	TABLE 9-3:	D	IA CHA	DMA CHANNELS 0-3 REGISTE	0-3 RE	GISTER	MAP (C	R MAP (CONTINUED)	UED)									•	
SSƏ		•								Bits	ts								S
Virtual Addr (#_8878)	Register Name <sup>(†)</sup>	Bit Range	31/15	30/14	29/13	28/12	27/11	26/10	25/9	24/8	23/7	22/6	21/5	20/4	19/3	18/2	17/1	16/0	All Reset
0000	1000	31:16	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1		0000
3280	DCHZCPIR	15:0								CHCPTR<15:0>	R<15:0>							0	0000
0000		31:16	_	_	_	1	_	-	_	_	_	_	_	Ι	_	_	_		0000
3230	DCTZDA	15:0	I	Ι	I	1	Ι	1	1	1				CHPDAT<7:0>	\T<7:0>			)	0000
0		31:16	1	Ι	Ι	1	Ι	1	1	1	I	I	I	1	I	I	I	-	0000
32A0	DCH3CON	15:0	CHBUSY	Ι	Ι	Ι	Ι	Ι	1	CHCHNS	CHEN	CHAED	CHCHN	CHAEN	I	CHEDET	CHPRI<1:0>		0000
0000	SOD DCHOECON	31:16	-	-	-	1	_	-	1	I				CHAIR	CHAIRQ<7:0>			)	00FF
3ZB0	NO JECTOR	15:0				CHSIR	IRQ<7:0>				CFORCE	CABORT	PATEN	SIRGEN	AIRQEN	-	Ι	-	FF00
		31:16	I	I	Ι	Ι	1	Ι	I	I	CHSDIE	CHSHIE	CHDDIE	CHDHIE	CHBCIE	CHCCIE	CHTAIE	CHERIE	0000
3200	DCHSIN	15:0	I	Ι	Ι	Ι	Ι	Ι	1	1	CHSDIF	CHSHIF	CHDDIF	CHDHIF	CHBCIF	CHCCIF	CHTAIF	CHERIF	0000
32D0	DCH3SSA	31:16								CHSSA<31:0>	<31:0>							0 0	0000
32E0	DCH3DSA	31:16								CHDSA<31:0>	<31:0>							0,0	0000
CLCC	1000100	31:16	1	1	I	1	I	1	ı	I	I	I	I	1	I	1	ı	1	0000
32FU		15:0								CHSSIZ<15:0>	<15:0>								0000
0000	בוסטמרוסט	31:16	I	Ι	Ι	I	I	Ι	I	1	I	I	I	I	I	I	I	1	0000
2200		15:0								CHDSIZ<15:0>	<15:0>	•						0	0000
2240	атазспол	31:16	Ι	Ι	Ι	Ι	_	Ι	Ι	I	Ι	Ι	_	Ι	-	1	ı		0000
2		15:0								CHSPTR<15:0>	<<15:0>							)	0000
3330	3320 DCH3DDTD	31:16	1	I	1	I	-	I	1	I	I	I		I	I	1	ı		0000
0250	בו וסכו וסט	15:0								CHDPTR<15:0>	<<15:0>							)	0000
0000	רוסטינוטט	31:16	I	I	1	Ι	I	I	I	I	I	I	I	I	I	I	1		0000
0000		15:0								CHCSIZ<15:0>	<15:0>							)	0000
3340	DCH3CDTB	31:16	1	1	Ι	Ι	1	Ι	1	1	I	I	I	I	Ī	1	1		0000
t S		15:0								CHCPTR<15:0>	<15:0>							Ü	0000
3350	DCH3DAT	31:16	1	1	I	1	-	I	I	1	I	I	I	1	Ι	1	1	1	0000
)	2	15:0	1	1	1	1	1	I	1	1				CHPDAT<7:0>	/T<7:0>				0000
Legend:		ınknown	value on R	leset; — = 1	unimplemer	$\mathbf{x}$ = unknown value on Reset; — = unimplemented, read as '0'. Reset values are shown in hexadecimal	s '0'. Reset	values are	shown in he	xadecimal.								Ì	

© 2011-2019 Microchip Technology Inc.

#### REGISTER 9-1: DMACON: DMA CONTROLLER CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31:24	-	_	-		-	_	-	-
22.46	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23:16	-	_	_			_	_	_
45.0	R/W-0	U-0	U-0	R/W-0	R/W-0	U-0	U-0	U-0
15:8	ON <sup>(1)</sup>	_	_	SUSPEND	DMABUSY	_	_	_
7.0	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
7:0		_		_		_		_

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

bit 15 **ON:** DMA On bit<sup>(1)</sup>

1 = DMA module is enabled 0 = DMA module is disabled bit 14-13 **Unimplemented:** Read as '0'

bit 12 SUSPEND: DMA Suspend bit

1 = DMA transfers are suspended to allow CPU uninterrupted access to data bus

0 = DMA operates normally

bit 11 **DMABUSY:** DMA Module Busy bit

1 = DMA module is active

0 = DMA module is disabled and not actively transferring data

bit 10-0 Unimplemented: Read as '0'

**Note 1:** When using 1:1 PBCLK divisor, the user's software should not read/write the peripheral's SFRs in the SYSCLK cycle immediately following the instruction that clears the module's ON bit.

#### **REGISTER 9-2: DMASTAT: DMA STATUS REGISTER**

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31.24	_	_	_	_	_	_	_	_
22.46	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23:16	-	_		-	_	_	_	_
45.0	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
15:8	_	_	_	_	_	_	_	_
7.0	U-0	U-0	U-0	U-0	R-0	R-0	R-0	R-0
7:0	_	_	_	_	RDWR		DMACH<2:0>	

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-4 **Unimplemented:** Read as '0' bit 3 **RDWR:** Read/Write Status bit

1 = Last DMA bus access was a read 0 = Last DMA bus access was a write

bit 2-0 DMACH<2:0>: DMA Channel bits

These bits contain the value of the most recent active DMA channel.

#### REGISTER 9-3: DMAADDR: DMA ADDRESS REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	R-0	R-0	R-0	R-0	R-0	R-0	R-0	R-0
31:24				DMAADDF	?<31:24>			
22.40	R-0	R-0	R-0	R-0	R-0	R-0	R-0	R-0
23:16				DMAADDF	?<23:16>			
45.0	R-0	R-0	R-0	R-0	R-0	R-0	R-0	R-0
15:8				DMAADDI	R<15:8>			
7.0	R-0	R-0	R-0	R-0	R-0	R-0	R-0	R-0
7:0				DMAADD	R<7:0>			

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### bit 31-0 DMAADDR<31:0>: DMA Module Address bits

These bits contain the address of the most recent DMA access.

#### REGISTER 9-4: DCRCCON: DMA CRC CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
04:04	U-0	U-0	R/W-0	R/W-0	R/W-0	U-0	U-0	R/W-0
31:24		_	BYTO	<1:0>	WBO <sup>(1)</sup>	_	-	BITO
00:40	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23:16	_	_	_	_	_	_	_	_
45.0	U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
15:8	_	_	_			PLEN<4:0>		
7.0	R/W-0	R/W-0	R/W-0	U-0	U-0	R/W-0	R/W-0	R/W-0
7:0	CRCEN	CRCAPP <sup>(1)</sup>	CRCTYP	_	_	(	CRCCH<2:0>	•

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

- bit 31-30 Unimplemented: Read as '0'
- bit 29-28 BYTO<1:0>: CRC Byte Order Selection bits
  - 11 = Endian byte swap on half-word boundaries (i.e., source half-word order with reverse source byte order per half-word)
  - 10 = Swap half-words on word boundaries (i.e., reverse source half-word order with source byte order per half-word)
  - 01 = Endian byte swap on word boundaries (i.e., reverse source byte order)
  - 00 = No swapping (i.e., source byte order)
- bit 27 WBO: CRC Write Byte Order Selection bit(1)
  - 1 = Source data is written to the destination re-ordered as defined by BYTO<1:0>
  - 0 = Source data is written to the destination unaltered
- bit 26-25 Unimplemented: Read as '0'
- bit 24 BITO: CRC Bit Order Selection bit

When CRCTYP (DCRCCON<15>) = 1 (CRC module is in IP Header mode):

- 1 = The IP header checksum is calculated Least Significant bit (LSb) first (i.e., reflected)
- 0 = The IP header checksum is calculated Most Significant bit (MSb) first (i.e., not reflected)

#### When CRCTYP (DCRCCON<15>) = 0 (CRC module is in LFSR mode):

- 1 = The LFSR CRC is calculated Least Significant bit first (i.e., reflected)
- 0 = The LFSR CRC is calculated Most Significant bit first (i.e., not reflected)
- bit 23-13 Unimplemented: Read as '0'
- bit 12-8 PLEN<4:0>: Polynomial Length bits

When CRCTYP (DCRCCON<15>) = 1 (CRC module is in IP Header mode):

These bits are unused.

#### When CRCTYP (DCRCCON<15>) = 0 (CRC module is in LFSR mode):

Denotes the length of the polynomial – 1.

- bit 7 CRCEN: CRC Enable bit
  - 1 = CRC module is enabled and channel transfers are routed through the CRC module
  - 0 = CRC module is disabled and channel transfers proceed normally
- Note 1: When WBO = 1, unaligned transfers are not supported and the CRCAPP bit cannot be set.

#### DCRCCON: DMA CRC CONTROL REGISTER (CONTINUED) **REGISTER 9-4:**

- CRCAPP: CRC Append Mode bit(1) bit 6
  - 1 = The DMA transfers data from the source into the CRC but NOT to the destination. When a block transfer completes the DMA writes the calculated CRC value to the location given by CHxDSA
  - 0 = The DMA transfers data from the source through the CRC obeying WBO as it writes the data to the destination
- bit 5 CRCTYP: CRC Type Selection bit
  - 1 = The CRC module will calculate an IP header checksum
  - 0 = The CRC module will calculate a LFSR CRC
- bit 4-3 Unimplemented: Read as '0'
- bit 2-0 CRCCH<2:0>: CRC Channel Select bits
  - 111 = CRC is assigned to Channel 7
  - 110 = CRC is assigned to Channel 6

  - 101 = CRC is assigned to Channel 5 100 = CRC is assigned to Channel 4

  - 011 = CRC is assigned to Channel 3 010 = CRC is assigned to Channel 2
  - 001 = CRC is assigned to Channel 1
  - 000 = CRC is assigned to Channel 0

Note 1: When WBO = 1, unaligned transfers are not supported and the CRCAPP bit cannot be set.

#### REGISTER 9-5: DCRCDATA: DMA CRC DATA REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
31:24				DCRCDATA	A<31:24>			
22.46	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
23:16				DCRCDATA	A<23:16>			
45.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
15:8				DCRCDAT	A<15:8>			
7.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
7:0				DCRCDA	ΓA<7:0>			

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### bit 31-0 DCRCDATA<31:0>: CRC Data Register bits

Writing to this register will seed the CRC generator. Reading from this register will return the current value of the CRC. Bits greater than PLEN will return '0' on any read.

When CRCTYP (DCRCCON<15>) =  $\underline{1}$  (CRC module is in IP Header mode):

Only the lower 16 bits contain IP header checksum information. The upper 16 bits are always '0'. Data written to this register is converted and read back in 1's complement form (i.e., current IP header checksum value).

When CRCTYP (DCRCCON<15>) = 0 (CRC module is in LFSR mode):

Bits greater than PLEN will return '0' on any read.

#### REGISTER 9-6: DCRCXOR: DMA CRCXOR ENABLE REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
31:24				DCRCXOR	?<31:24>			
22.40	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
23:16				DCRCXOF	?<23:16>			
45.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
15:8				DCRCXO	R<15:8>			
7.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
7:0				DCRCXO	R<7:0>			

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### bit 31-0 DCRCXOR<31:0>: CRC XOR Register bits

When CRCTYP (DCRCCON<15>) =  $\frac{1}{2}$  (CRC module is in IP Header mode):

This register is unused.

When CRCTYP (DCRCCON<15>) = 0 (CRC module is in LFSR mode):

- 1 = Enable the XOR input to the Shift register
- 0 = Disable the XOR input to the Shift register; data is shifted in directly from the previous stage in the register

#### REGISTER 9-7: DCHxCON: DMA CHANNEL 'x' CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31.24	_	_	_	-	_	_	_	_
00.40	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23:16	_	_	_	_	_	_	_	_
45.0	R/W-0	U-0	U-0	U-0	U-0	U-0	U-0	R/W-0
15:8	CHBUSY	_	_	_	_	_	_	CHCHNS <sup>(1)</sup>
7.0	R/W-0	R/W-0	R/W-0	R/W-0	U-0	R-0	R/W-0	R/W-0
7:0	CHEN <sup>(2)</sup>	CHAED	CHCHN	CHAEN	_	CHEDET	CHPF	RI<1:0>

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

bit 15 CHBUSY: Channel Busy bit

1 = Channel is active or has been enabled

0 = Channel is inactive or has been disabled

bit 14-9 Unimplemented: Read as '0'

bit 8 **CHCHNS:** Chain Channel Selection bit<sup>(1)</sup>

1 = Chain to channel lower in natural priority (CH1 will be enabled by CH2 transfer complete)

0 = Chain to channel higher in natural priority (CH1 will be enabled by CH0 transfer complete)

bit 7 **CHEN:** Channel Enable bit<sup>(2)</sup>

1 = Channel is enabled

0 = Channel is disabled

bit 6 CHAED: Channel Allow Events If Disabled bit

1 = Channel start/abort events will be registered, even if the channel is disabled

0 = Channel start/abort events will be ignored if the channel is disabled

bit CHCHN: Channel Chain Enable bit

1 = Allow channel to be chained

0 = Do not allow channel to be chained

bit 4 CHAEN: Channel Automatic Enable bit

1 = Channel is continuously enabled, and not automatically disabled after a block transfer is complete

0 = Channel is disabled on block transfer complete

bit 3 **Unimplemented:** Read as '0'

bit 2 CHEDET: Channel Event Detected bit

1 = An event has been detected

0 = No events have been detected

bit 1-0 CHPRI<1:0>: Channel Priority bits

11 = Channel has priority 3 (highest)

10 = Channel has priority 2

01 = Channel has priority 1

00 = Channel has priority 0

Note 1: The chain selection bit takes effect when chaining is enabled (i.e., CHCHN = 1).

2: When the channel is suspended by clearing this bit, the user application should poll the CHBUSY bit (if available on the device variant) to see when the channel is suspended, as it may take some clock cycles to complete a current transaction before the channel is suspended.

#### REGISTER 9-8: DCHxECON: DMA CHANNEL 'x' EVENT CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31.24	_	_	_	_	_	_	_	_
22.46	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
23:16				CHAIRQ<	<7:0> <sup>(1)</sup>			
45.0	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
15:8				CHSIRQ<	<7:0> <sup>(1)</sup>			
7:0	S-0	S-0	R/W-0	R/W-0	R/W-0	U-0	U-0	U-0
7.0	CFORCE	CABORT	PATEN	SIRQEN	AIRQEN	_	_	_

Legend:S = Settable bitR = Readable bitW = Writable bitU = Unimplemented bit, read as '0'-n = Value at POR'1' = Bit is set'0' = Bit is clearedx = Bit is unknown

bit 31-24 Unimplemented: Read as '0'

bit 23-16 CHAIRQ<7:0>: Channel Transfer Abort IRQ bits(1)

11111111 = Interrupt 255 will abort any transfers in progress and set CHAIF flag

•

00000001 = Interrupt 1 will abort any transfers in progress and set CHAIF flag 00000000 = Interrupt 0 will abort any transfers in progress and set CHAIF flag

bit 15-8 CHSIRQ<7:0>: Channel Transfer Start IRQ bits<sup>(1)</sup>

11111111 = Interrupt 255 will initiate a DMA transfer

•

00000001 = Interrupt 1 will initiate a DMA transfer 00000000 = Interrupt 0 will initiate a DMA transfer

1 = A DMA transfer is forced to begin when this bit is written to a '1'

0 = This bit always reads '0'

bit 6 CABORT: DMA Abort Transfer bit

1 = A DMA transfer is aborted when this bit is written to a '1'

0 = This bit always reads '0'

bit 5 PATEN: Channel Pattern Match Abort Enable bit

1 = Abort transfer and clear CHEN on pattern match

0 = Pattern match is disabled

bit 4 SIRQEN: Channel Start IRQ Enable bit

1 = Start channel cell transfer if an interrupt matching CHSIRQ occurs

0 = Interrupt number CHSIRQ is ignored and does not start a transfer

bit 3 AIRQEN: Channel Abort IRQ Enable bit

1 = Channel transfer is aborted if an interrupt matching CHAIRQ occurs

0 = Interrupt number CHAIRQ is ignored and does not terminate a transfer

bit 2-0 Unimplemented: Read as '0'

Note 1: See Table 7-1: "Interrupt IRQ, Vector and Bit Location" for the list of available interrupt IRQ sources.

#### REGISTER 9-9: DCHxINT: DMA CHANNEL 'x' INTERRUPT CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31.24	_	_	_	-	_	_	_	_
00:40	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
23:16	CHSDIE	CHSHIE	CHDDIE	CHDHIE	CHBCIE	CHCCIE	CHTAIE	CHERIE
45.0	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
15:8	_	_	_	_	_	_	_	_
7.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
7:0	CHSDIF	CHSHIF	CHDDIF	CHDHIF	CHBCIF	CHCCIF	CHTAIF	CHERIF

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-24 Unimplemented: Read as '0'

bit 23 CHSDIE: Channel Source Done Interrupt Enable bit

1 = Interrupt is enabled

0 = Interrupt is disabled

bit 22 CHSHIE: Channel Source Half Empty Interrupt Enable bit

1 = Interrupt is enabled0 = Interrupt is disabled

bit 21 CHDDIE: Channel Destination Done Interrupt Enable bit

1 = Interrupt is enabled

0 = Interrupt is disabled

bit 20 CHDHIE: Channel Destination Half Full Interrupt Enable bit

1 = Interrupt is enabled

0 = Interrupt is disabled

bit 19 CHBCIE: Channel Block Transfer Complete Interrupt Enable bit

1 = Interrupt is enabled

0 = Interrupt is disabled

bit 18 CHCCIE: Channel Cell Transfer Complete Interrupt Enable bit

1 = Interrupt is enabled

0 = Interrupt is disabled

bit 17 CHTAIE: Channel Transfer Abort Interrupt Enable bit

1 = Interrupt is enabled

0 = Interrupt is disabled

bit 16 CHERIE: Channel Address Error Interrupt Enable bit

1 = Interrupt is enabled

0 = Interrupt is disabled

bit 15-8 **Unimplemented:** Read as '0'

bit 7 CHSDIF: Channel Source Done Interrupt Flag bit

1 = Channel Source Pointer has reached end of source (CHSPTR = CHSSIZ)

0 = No interrupt is pending

bit 6 CHSHIF: Channel Source Half Empty Interrupt Flag bit

1 = Channel Source Pointer has reached midpoint of source (CHSPTR = CHSSIZ/2)

0 = No interrupt is pending

bit 5 CHDDIF: Channel Destination Done Interrupt Flag bit

1 = Channel Destination Pointer has reached end of destination (CHDPTR = CHDSIZ)

0 = No interrupt is pending

#### REGISTER 9-9: DCHxINT: DMA CHANNEL 'x' INTERRUPT CONTROL REGISTER (CONTINUED)

- bit 4 **CHDHIF:** Channel Destination Half Full Interrupt Flag bit
  - 1 = Channel Destination Pointer has reached midpoint of destination (CHDPTR = CHDSIZ/2)
  - 0 = No interrupt is pending
- bit 3 CHBCIF: Channel Block Transfer Complete Interrupt Flag bit
  - 1 = A block transfer has been completed (the larger of CHSSIZ/CHDSIZ bytes has been transferred), or a pattern match event occurs
  - 0 = No interrupt is pending
- bit 2 CHCCIF: Channel Cell Transfer Complete Interrupt Flag bit
  - 1 = A cell transfer has been completed (CHCSIZ bytes have been transferred)
  - 0 = No interrupt is pending
- bit 1 CHTAIF: Channel Transfer Abort Interrupt Flag bit
  - 1 = An interrupt matching CHAIRQ has been detected and the DMA transfer has been aborted
  - 0 = No interrupt is pending
- bit 0 CHERIF: Channel Address Error Interrupt Flag bit
  - 1 = A channel address error has been detected (either the source or the destination address is invalid)
  - 0 = No interrupt is pending

#### REGISTER 9-10: DCHxSSA: DMA CHANNEL 'x' SOURCE START ADDRESS REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
21.24	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
31:24				CHSSA<	31:24>			
22.46	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
23:16				CHSSA<	23:16>			
45.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
15:8				CHSSA<	<15:8>			
7.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
7:0				CHSSA	<7:0>			

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-0 CHSSA<31:0> Channel Source Start Address bits

Channel source start address.

Note: This must be the physical address of the source.

#### REGISTER 9-11: DCHxDSA: DMA CHANNEL 'x' DESTINATION START ADDRESS REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
04.04	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
31:24				CHDSA<	31:24>			
00.40	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
23:16				CHDSA<	23:16>			
45.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
15:8				CHDSA-	<15:8>			
7.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
7:0				CHDSA	<7:0>			

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-0 CHDSA<31:0>: Channel Destination Start Address bits

Channel destination start address.

Note: This must be the physical address of the destination.

#### REGISTER 9-12: DCHxSSIZ: DMA CHANNEL 'x' SOURCE SIZE REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31:24	_	_	_	_		_	_	_
22.46	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23:10	23:16		-	_		_	_	_
45.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
15:8				CHSSIZ-	<15:8>			
7.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
7:0				CHSSIZ	<7:0>			

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

bit 15-0 CHSSIZ<15:0>: Channel Source Size bits

1111111111111111 = 65,535 byte source size

:

•

00000000000000010 = 2 byte source size

00000000000000001 = 1 byte source size

0000000000000000 = 65,536 byte source size

#### REGISTER 9-13: DCHxDSIZ: DMA CHANNEL 'x' DESTINATION SIZE REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31:24		_	_	_	_	_	_	_
22.46	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23:16	_	_	_	_	_	_	_	_
15:8	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
13.6				CHDSIZ	<15:8>			
7.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
7:0				CHDSIZ	·<7:0>			

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

bit 15-0 CHDSIZ<15:0>: Channel Destination Size bits

111111111111111 = 65,535 byte destination size

•

0000000000000010 = 2 byte destination size

00000000000000001 = 1 byte destination size

0000000000000000 = 65,536 byte destination size

#### REGISTER 9-14: DCHxSPTR: DMA CHANNEL 'x' SOURCE POINTER REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31.24		_	_	_	_		_	-
00.46	U-0 U-0		U-0	U-0	U-0	U-0	U-0	U-0
23:10	23:16		_	_	_	_	_	_
45.0	R-0	R-0	R-0	R-0	R-0	R-0	R-0	R-0
15:8				CHSPTR	<15:8>			
7.0	R-0	R-0	R-0	R-0	R-0	R-0	R-0	R-0
7:0				CHSPTF	R<7:0>			

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

bit 15-0 CHSPTR<15:0>: Channel Source Pointer bits

111111111111111 = Points to byte 65,535 of the source

.

0000000000000000 = Points to byte 1 of the source 000000000000000 = Points to byte 0 of the source

Note: When in Pattern Detect mode, this register is reset on a pattern detect.

#### REGISTER 9-15: DCHxDPTR: DMA CHANNEL 'x' DESTINATION POINTER REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31.24	_	_	_	_	_	_	_	_
00.40	U-0	U-0 U-0		U-0	U-0	U-0	U-0	U-0
23:16	_	_		_	_	_	_	_
45.0	R-0	R-0	R-0	R-0	R-0	R-0	R-0	R-0
15:8				CHDPTR	<15:8>			
7.0	R-0	R-0	R-0	R-0	R-0	R-0	R-0	R-0
7:0				CHDPTF	R<7:0>			

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

bit 15-0 CHDPTR<15:0>: Channel Destination Pointer bits

•

000000000000000 = Points to byte 1 of the destination 00000000000000 = Points to byte 0 of the destination

#### REGISTER 9-16: DCHxCSIZ: DMA CHANNEL 'x' CELL-SIZE REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31:24	_	_		_	_	_	_	_
22.46	U-0 U-0		U-0	U-0	U-0	U-0	U-0	U-0
23:16		_	_	_	_	_	_	_
45.0	R/W-0 R/W-0		R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
15:8				CHCSIZ	<15:8>			
7.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
7:0				CHCSIZ	<7:0>			

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

bit 15-0 CHCSIZ<15:0>: Channel Cell Size bits

111111111111111 = 65,535 bytes transferred on an event

:

0000000000000000 = 2 bytes transferred on an event

0000000000000001= 1 byte transferred on an event

000000000000000 = 65,536 bytes transferred on an event

#### REGISTER 9-17: DCHxCPTR: DMA CHANNEL 'x' CELL POINTER REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31:24	_	_	_	_	_	_	_	_
22.40	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23:16			_	_	_	_	_	_
15:8	R-0	R-0	R-0	R-0	R-0	R-0	R-0	R-0
13.6				CHCPTR	<15:8>			
7:0	R-0	R-0	R-0	R-0	R-0	R-0	R-0	R-0
7.0		-		CHCPTF	R<7:0>	•	•	•

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 **Unimplemented:** Read as '0'

bit 15-0 CHCPTR<15:0>: Channel Cell Progress Pointer bits

11111111111111 = 65,535 bytes have been transferred since the last event

•

0000000000000000 = 1 byte has been transferred since the last event 000000000000000 = 0 bytes have been transferred since the last event

Note: When in Pattern Detect mode, this register is reset on a pattern detect.

#### REGISTER 9-18: DCHxDAT: DMA CHANNEL 'x' PATTERN DATA REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31.24		_			_	_	_	_
22.46	23:16		U-0	U-0	U-0	U-0	U-0	U-0
23:10		_	_	_	_	_	_	_
45.0	15.0 U-0 U-0		U-0	U-0	U-0	U-0	U-0	U-0
15:8			_	_	_	_	_	_
7.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
7:0				CHPDAT	Γ<7:0>			

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-8 Unimplemented: Read as '0'

bit 7-0 CHPDAT<7:0>: Channel Data Register bits

Pattern Terminate mode:

Data to be matched must be stored in this register to allow a "terminate on match".

All other modes: Unused.

NOTES:			

#### 10.0 USB ON-THE-GO (OTG)

Note:

This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To complement the information in this data sheet, refer to **Section 27. "USB On-The-Go (OTG)"** (DS60001126), which is available from the *Documentation > Reference Manual* section of the Microchip PIC32 web site (www.microchip.com/pic32).

The Universal Serial Bus (USB) module contains analog and digital components to provide a USB 2.0 Full-Speed and Low-Speed embedded host, Full-Speed device or OTG implementation with a minimum of external components. This module in Host mode is intended for use as an embedded host and therefore does not implement a UHCI or OHCI controller.

The USB module consists of the clock generator, the USB voltage comparators, the transceiver, the Serial Interface Engine (SIE), a dedicated USB DMA controller, pull-up and pull-down resistors, and the register interface. A block diagram of the PIC32 USB OTG module is presented in Figure 10-1.


The clock generator provides the 48 MHz clock required for USB Full-Speed and Low-Speed communication. The voltage comparators monitor the voltage on the VBUS pin to determine the state of the bus. The transceiver provides the analog translation between the USB bus and the digital logic. The SIE is a state machine that transfers data to and from the endpoint buffers and generates the hardware protocol for data transfers. The USB DMA controller transfers data between the data buffers in RAM and the SIE. The integrated pull-up and pull-down resistors eliminate the need for external signaling components. The register interface allows the CPU to configure and communicate with the module.

The PIC32 USB module includes the following features:

- · USB Full-Speed support for Host and Device
- · Low-Speed Host support
- · USB OTG support
- · Integrated signaling resistors
- Integrated analog comparators for VBUS monitoring
- · Integrated USB transceiver
- · Transaction handshaking performed by hardware
- · Endpoint buffering anywhere in system RAM
- · Integrated DMA to access system RAM and Flash

Note:

The implementation and use of the USB specifications, as well as other third party specifications or technologies, may require licensing; including, but not limited to, USB Implementers Forum, Inc., also referred to as USB-IF (www.usb.org). The user is fully responsible for investigating and satisfying any applicable licensing obligations.



10.1 USB Control Registers
TABLE 10-1: USB REGISTER MAP

s	Pll Reset	0000	0000	0000	0000			0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	vely.
	16/0	I	VBUSVDIF	1	VBUSVDIE	I	VBUSVD	I	VBUSDIS	-	USBPWR	1	URSTIF	DETACHIF		URSTIE DETACHIE	I	PINEF	- - -	1	PIDEE	1	I	I	USBEN	I		I	I	OxC respecti
	17/1	1	1	1	1	1	I	1	VBUSCHG	-	USUSPEND	1	IFRRIF			UERRIE	I	CRC5EF	EOFEF	1	CRC5EE EOFEE	1	I	I	PPBRST	I		I		x = unknown value on Reset; — = unimplemented, read as '0'. Reset values are shown in hexadecimal. With the exception of those noted, all registers in this table (except as noted) have corresponding CLR, SET and INV registers at their virtual address, plus an offset of 0x4, 0x8, and 0xC respectively.
	18/2	I	SESENDIF	ı	SESENDIE	I	SESEND	I	OTGEN	-	1	1	SOFIF	=	1	SOFIE	I	CRC16EE		1	CRC16EE	1	PPBI	I	RESUME	I	^	I		an offset of 0;
	19/3	1	SESVDIF	I	SESVDIE	1	SESVD	1	VBUSON	I	USBBUSY	I	TRNIF		1	TRNIE	I	DENBEE	בו אפרו	I	DFN8EE	I	DIR	I	HOSTEN	I	DEVADDR<6:0>	I	_	dress, plus a
	20/4	1	ACTVIF	1	ACTVIE	I	I	I	DMPULDWN	_	USLPGRD	I	IDI FIF	ב ו	1	IDLEIE	I	RTOFF	ם כ	I	BTOEE	1		I	USBRST	I	30	I	BDTPTRL<15:9>	eir virtual ad
	21/5	1	LSTATEIF	1	LSTATEIE	1	LSTATE	_	DMPULUP DPPULDWN DMPULDWN	-	1	-	RESIMEIE		-	RESUMEIE	_	DMAFF			DMAEE	1	F<3:0>	_	PKTDIS TOKBUSY	1		_	.DB	egisters at th
s	22/6	1	T1MSECIF	1	T1MSECIE	I	I	I	DMPULUP	-	I	1	ATTACHIE		1	ATTACHIE	I	RMXEE	בואל	1	BMXEE	1	ENDPT<3:0>	I	SE0	I		I		ET and INV r
Bits	23/7	I	IDIF	1	IDIE	_	OI	1	DPPULUP	1	UACTPND(4)	1	STALLIF	0.755	_	STALLIE	I	RTSEE	ם כר	1	BTSEE	I		I	JSTATE	-	LSPDEN	1		<ul> <li>unimplemented, read as '0'. Reset values are shown in hexadecimal.</li> <li>d, all registers in this table (except as noted) have corresponding CLR, S</li> </ul>
	24/8	1	I	I	I	I	I	Ι	1	I		I	I		I	ı	I	ı		1	I	I	I	I	ı	I	I	I	I	own in he
	25/9	1	1	I	I	I	Ι	1	1	I	I	I	ı		1	I	I	ı		1	1	1	I	Ι	I	1	I	I	1	es are sh
	26/10	1	1	1	1	I	I	I	1	I	I	I	ı		1	1	I	ı		I	-	1	I	I	_	I	1	I	I	Reset value
	27/11	1	1	I	-	_	I	Ι	_	I	-	I	١		_	I	I			I	I	1	-	I	I	1	-	1	1	id as '0'. F able (exce
	28/12	1	1	1	Ι	_	Ι	I	_	ı	1	1	ı		_	I	I			1	I	1	1	Ι	-	1	Ι	I	Ι	ented, rea
	29/13	I	I	I	I	I	-	_	1	Ι	I	I	I		I	I	_			I	1	I	I	-	I	I	I	-	I	unimplem all register
	30/14	1	1	1	I	I	1	Ι	1	I	I	I	I		1	ı	I	ı		1	I	1	I	1	ı	I	I	I	I	set; — = 1
	31/15	1	I	I	I	I	Ι	-	1	I	I	I	I		I	I	I	ı		I	I	I	I	Ι	ı	I	I	I	I	x = unknown value on Reset; With the exception of those no
•	Bit Range	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15.0	2	31:16	15:0	31:16	15.0	2.0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	own val excepti
	Register Name <sup>(1)</sup>		0101GIR		0.00	110705701(3)	2180000		UIUIGCON		) Y		U1IR <sup>(2)</sup>			U1E		U1EIR <sup>(2)</sup>			U1EIE	1100000	CISIAIS		U1CON		UIADDK		O IBUIL	<u></u>
55 50 50 60 10 Virtual Address (BF88_#)			0	0000		5200			5210		5220			5230	0,000	0770		5250	C	0976	0	0776	Legend: Note							

© 2011-2019 Microchip Technology Inc.

With the exception of those noted, all registers in this table (except as noted) have corresponding CLR, SET and INV registers at their virtual address, plus an offset of 0x4, 0x8, and 0xC respectively. See Section 11.2 "CLR, SET and INV Registers" for more information. This register does not have associated SET and INV registers.

This register does not have associated CLR, SET and INV registers. Reset value for this bit is undefined.

ყ ფ 4

TABLE	LE 10-1:	USB	REGI	STER !	MAP (C	<b>USB REGISTER MAP (CONTIN</b>	(UED)												
ssə		(									Bits	Ş.							9
Virtual Addr (#_8878)	Register <sup>(†)</sup> emsN	Bit Range	31/15	30/14	29/13	28/12	27/11	26/10	25/9	24/8	23/7	22/6	21/5	20/4	19/3	18/2	17/1	16/0	steseЯ IIA
C	114 11 (3)	31:16	1	1	1	1	1	1	1	1	1	1	1	I	1	1	1	1	0000
2280	UTERME	15:0	I	I	1	I	Ι	1	I	-				FRML<7:0>	<0:2				0000
000	114 F D M L (3)	31:16	I	I	I	I	Ι	1	ı	1	I	I	Ι	I	I	I	I	I	0000
0876		15:0	I	I	I	I	1	I	1	-	1	I	I	I	I		FRMH<2:0>		0000
0 4 0	10H	31:16	I	I	I	I	I	I	1	1	I	I	I	I	I	I	1	I	0000
22A0	200	15:0	I	I	Ι	Ι	Ι	I	1	-		PID	PID<3:0>			EP	EP<3:0>		0000
0	- 0 1	31:16	1	1	1	1	I	1	ı	1	1	I	I	1	ı	I	ı	I	0000
2280	OTSOF	15:0	I	I	I	I	I	1	ı	-		İ		CNT<7:0>	<0:				0000
C		31:16	I	I	I	I	I	1	ı	-	I	I	1	1	ı	I	1	ı	0000
2200	UIBUIPZ	15:0	I	I	I	I	I	1	1	1				BDTPTRH<7:0>	<0:2>				0000
0	0.00	31:16	I	I	I	I	I	1	1	1	I	I	1	1	I	I	1	I	0000
2ZD0	UIBDIP3	15:0	I	I	I	I	I	1	ı	-	1			BDTPTRU<7:0>	<0:2>				0000
C	0 1	31:16	I	I	I	I	I	1	1	1	I	I	1	1	I	I	1	I	0000
0376	UICINFGI	15:0	1	-	1	_	_	1	-	_	UTEYE	NOWBON	-	USBSIDL	1	_		UASUSPND	0001
2000	14500	31:16	1	1	1	1	-	1	1	-	1	-	-	1	1	-	-	1	0000
0000		15:0	I	I	I	Ι	I	1	-	1	LSPD	RETRYDIS	1	<b>EPCONDIS</b>	EPRXEN	EPTXEN	EPSTALL	EPHSHK	0000
6240	14504	31:16	1	1	1	1	-	1	1	-	1	-	-	1	1	-	-	1	0000
01.00		15:0	1	1	1	-	Ι	1	-	-	1	Ι	1	EPCONDIS	EPRXEN	EPTXEN	EPSTALL	EPHSHK	0000
5320	111500	31:16	I	I	I	I	Ι	1	I	1	1	I	1	1	-	I	_	1	0000
0000	0 1 2	15:0	I	I	I	I	Ι	1	1	1	Ι	Ι	I	EPCONDIS	EPRXEN	EPTXEN	EPSTALL	EPHSHK	0000
5330	111503	31:16	1	1	1	1	1	1	1	1	1	Ι	1	1	1	I	1	I	0000
		15:0	I	Ι	I	I	I	1	1	1	I	1	1	<b>EPCONDIS</b>	EPRXEN	EPTXEN	EPSTALL	EPHSHK	0000
2370	110	31:16	I	I	I	I	1	1	-	-	I	I	1	1	ı	I		I	0000
2	100	15:0	I	Ι	1	Ι	1	1	-	1	1	1	1	<b>EPCONDIS</b>	EPRXEN	EPTXEN	EPSTALL	EPHSHK	0000
5350	11505	31:16	I	Ι	Ι	I	Ι	1	1	Ι	I	I	Ι	1	1	Ι	-	1	0000
		15:0	I	I	I	I	1	1	1	1	I	I	I	EPCONDIS	EPRXEN	EPTXEN	EPSTALL	EPHSHK	0000
5260	111	31:16	I	I	I	I	1	1	1	-	I	I	1	1	ı	I		I	0000
		15:0	I	I	I	I	Ι	1	1	1	I	I	Ι	EPCONDIS	EPRXEN	EPTXEN	EPSTALL	EPHSHK	0000
5370	111507	31:16	I	Ι	Ι	I	Ι	1	1	Ι	I	I	Ι	1	1	Ι	-	1	0000
		15:0	I	I	I	I	1	1	1	1	I	I	I	EPCONDIS	EPRXEN	EPTXEN	EPSTALL	EPHSHK	0000
5380	11108	31:16	I	I	I	I	Ι	1	I	1	1	I	1	1	-	I	_	1	0000
5		15:0	1	1	1	1	1	1	1	1	1	1	1	<b>EPCONDIS</b>	EPRXEN	EPTXEN	EPSTALL	EPHSHK	0000
Legend:		nown va	lue on Re	set; — = 1	unimplem	x = unknown value on Reset; — = unimplemented, read		as '0'. Reset values are shown in hexadecimal	s are sho	wn in hex	adecimal.				]				

x = unknown value on Reset; — = unimplemented, read as '0'. Reset values are snown in nexadecimal.

With the exception of those noted, all registers in this table (except as noted) have corresponding CLR, SET and INV registers at their virtual address, plus an offset of 0x4, 0x8, and 0xC respectively. See Section 11.2 "CLR, SET and INV Registers" for more information.

This register does not have associated SET and INV registers.

This register does not have associated CLR, SET and INV registers.

Reset value for this bit is undefined.

ყ ფ 4

9	etseЯ IIA	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	
	16/0	1	EPHSHK	1	EPHSHK	I	EPHSHK	1	EPHSHK	1	EPHSHK	I	EPHSHK	1	EPHSHK	
	17/1	1	EPSTALL	1	EPSTALL	I	EPSTALL	Ι	EPSTALL	Ι	EPSTALL	I	EPSTALL	Ι	EPSTALL	
	18/2	1	EPTXEN	I	EPTXEN	I	EPTXEN	1	EPTXEN	1	EPTXEN	1	EPTXEN	1	EPTXEN	
	19/3	1	EPRXEN	I	EPRXEN	I	EPRXEN	Ι	EPRXEN	Ι	EPRXEN	1	EPRXEN	Ι	EPRXEN	
	20/4	I	EPCONDIS	Ι	EPCONDIS	Ι	EPCONDIS	Ι	EPCONDIS	Ι	EPCONDIS	Ι	EPCONDIS	ı	EPCONDIS	
	21/5	-	Ι	I	Ι	I	_	_	_	_	_	_	_	_	_	
Ņ	22/6	-	I	I	I	I	_	_	_	_	_	_	_	_	_	
Bits	23/7	1	1	1	1	1	Ι	I	I	I	I	1	I	I	I	${\bf x}$ = unknown value on Reset; — = unimplemented, read as '0'. Reset values are shown in hexadecimal.
	24/8	1	I	I	I	I	_	_	_	_	_	-	_	_	_	h ui uwo
	25/9	1	1	1	1	1	-	_	_	_	_	1	Ι	Ι	Ι	ies are sh
	26/10	1	1	I	1	I	-	Ι	Ι	Ι	Ι	-	-	-	-	Reset valu
	27/11	-	I	1	I	1	_	_	_	_	_	-	_	_	_	1,0,sept
	28/12	_	1	I	1	1	_	_	_	_	_	_	—	—	—	ented, rea
	29/13	1	Ι	1	Ι	I	_	_	_	_	_	Ι	_	_	_	unimplem
	30/14	I	1	1	1	I	I	I	I	I	I	I	Ι	Ι	Ι	eset; — =
	31/15	1	I	1	I	I	Ι	Ι	Ι	Ι	Ι	1	Ι	Ι	Ι	alue on R
(	Bit Range	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	own va
	Register Name <sup>(1)</sup>	7	ם ה		5	11		1145542	Z .	1145542	2 1	140			5	
	Virtual Addro (#_8878)	000	0850	0	D3AU	0003	0000	2002	0000	טרכז	0000		2250	0101	0100	Legend:

With the exception of those noted, all registers in this table (except as noted) have corresponding CLR, SET and INV registers at their virtual address, plus an offset of 0x4, 0x8, and 0xC respectively. See Section 11.2 "CLR, SET and INV Registers" for more information.

This register does not have associated SET and INV registers.

This register does not have associated CLR, SET and INV registers.

Reset value for this bit is undefined.

<u>ოფ</u>

**USB REGISTER MAP (CONTINUED)** 

**TABLE 10-1**:

#### REGISTER 10-1: U10TGIR: USB OTG INTERRUPT STATUS REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0                U-0							
31.24	_	_	-	-	_	_	_	_
23:16	U-0                U-0							
23.10	_	_	_	_	_	_	_	_
15:8	U-0                U-0							
15.6	_	_	_	_	_	_	_	_
7.0	R/WC-0, HS	U-0	R/WC-0, HS					
7:0	IDIF	T1MSECIF	LSTATEIF	ACTVIF	SESVDIF	SESENDIF	_	VBUSVDIF

Legend:WC = Write '1' to clearHS = Hardware Settable bitR = Readable bitW = Writable bitU = Unimplemented bit, read as '0'-n = Value at POR'1' = Bit is set'0' = Bit is clearedx = Bit is unknown

bit 31-8 Unimplemented: Read as '0'

bit 7 IDIF: ID State Change Indicator bit

1 = A change in the ID state was detected0 = No change in the ID state was detected

bit 6 **T1MSECIF:** 1 Millisecond Timer bit

**T1MSECIF:** 1 Millisecond Timer bit 1 = 1 millisecond timer has expired

0 = 1 millisecond timer has not expired

bit 5 LSTATEIF: Line State Stable Indicator bit

1 = USB line state has been stable for 1 ms, but different from last time

0 = USB line state has not been stable for 1 ms

bit 4 ACTVIF: Bus Activity Indicator bit

1 = Activity on the D+, D-, ID or VBUS pins has caused the device to wake-up

0 = Activity has not been detected

bit 3 SESVDIF: Session Valid Change Indicator bit

1 = VBUS voltage has dropped below the session end level

0 = VBUS voltage has not dropped below the session end level

bit 2 SESENDIF: B-Device VBUS Change Indicator bit

1 = A change on the session end input was detected

0 = No change on the session end input was detected

bit 1 Unimplemented: Read as '0'

bit 0 VBUSVDIF: A-Device VBUS Change Indicator bit

1 = A change on the session valid input was detected

0 = No change on the session valid input was detected

#### REGISTER 10-2: U10TGIE: USB OTG INTERRUPT ENABLE REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0                U-0							
31.24	-		-	-	-	-	_	_
23:16	U-0                U-0							
23.10	_	_	_	_	_	_	_	_
15:8	U-0                U-0							
15.6	_		_	_	_	_	_	_
7:0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	U-0	R/W-0
7.0	IDIE	T1MSECIE	LSTATEIE	ACTVIE	SESVDIE	SESENDIE	_	VBUSVDIE

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-8 Unimplemented: Read as '0'

bit 7 IDIE: ID Interrupt Enable bit

1 = ID interrupt is enabled0 = ID interrupt is disabled

bit 6 T1MSECIE: 1 Millisecond Timer Interrupt Enable bit

1 = 1 millisecond timer interrupt is enabled0 = 1 millisecond timer interrupt is disabled

bit 5 LSTATEIE: Line State Interrupt Enable bit

1 = Line state interrupt is enabled0 = Line state interrupt is disabled

bit 4 ACTVIE: Bus Activity Interrupt Enable bit

1 = Activity interrupt is enabled

0 = Activity interrupt is disabled

bit 3 SESVDIE: Session Valid Interrupt Enable bit

1 = Session valid interrupt is enabled

0 = Session valid interrupt is disabled

bit 2 SESENDIE: B-Device Session End Interrupt Enable bit

1 = B-Device session end interrupt is enabled

0 = B-Device session end interrupt is disabled

bit 1 Unimplemented: Read as '0'

bit 0 VBUSVDIE: A-Device VBUS Valid Interrupt Enable bit

1 = A-Device VBUS valid interrupt is enabled

0 = A-Device VBUS valid interrupt is disabled

#### REGISTER 10-3: U10TGSTAT: USB OTG STATUS REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0                U-0							
31.24	_	_	_	_	-	_	_	_
23:16	U-0                U-0							
23.10	-	_	_	_	-	_	_	_
15:8	U-0                U-0							
13.0	_	_	_	_	-	_	_	_
7:0	R-0	U-0	R-0	U-0	R-0	R-0	U-0	R-0
7.0	ID	_	LSTATE	_	SESVD	SESEND	_	VBUSVD

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-8 Unimplemented: Read as '0'

bit 7 ID: ID Pin State Indicator bit

1 = No cable is attached or a "type B" cable has been inserted into the USB receptacle

0 = A "type A" OTG cable has been inserted into the USB receptacle

bit 6 Unimplemented: Read as '0'

bit 5 LSTATE: Line State Stable Indicator bit

1 = USB line state (SE0 (U1CON<6>) bit and JSTATE (U1CON<7>)) bit has been stable for previous 1 ms

0 = USB line state (SE0 and JSTATE) has not been stable for previous 1 ms

bit 4 Unimplemented: Read as '0'

bit 3 SESVD: Session Valid Indicator bit

1 = VBUS voltage is above Session Valid on the A or B device

0 = VBUS voltage is below Session Valid on the A or B device

bit 2 SESEND: B-Device Session End Indicator bit

1 = VBUS voltage is below Session Valid on the B device

0 = VBUS voltage is above Session Valid on the B device

bit 1 Unimplemented: Read as '0'

bit 0 VBUSVD: A-Device VBUS Valid Indicator bit

1 = VBUS voltage is above Session Valid on the A device

0 = VBUS voltage is below Session Valid on the A device

#### REGISTER 10-4: U10TGCON: USB OTG CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0                U-0							
31.24	_	_	_			_		
23:16	U-0                U-0							
23.10	_	_	_	_	_	_	_	_
15:8	U-0                U-0							
15.6	_	_	_	_	_	_	-	_
7:0	R/W-0              R/W-0							
7:0	DPPULUP	DMPULUP	DPPULDWN	DMPULDWN	VBUSON	OTGEN	VBUSCHG	VBUSDIS

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-8 Unimplemented: Read as '0'

bit 7 DPPULUP: D+ Pull-Up Enable bit

1 = D+ data line pull-up resistor is enabled0 = D+ data line pull-up resistor is disabled

bit 6 **DMPULUP:** D- Pull-Up Enable bit

1 = D- data line pull-up resistor is enabled0 = D- data line pull-up resistor is disabled

bit 5 DPPULDWN: D+ Pull-Down Enable bit

1 = D+ data line pull-down resistor is enabled0 = D+ data line pull-down resistor is disabled

bit 4 DMPULDWN: D- Pull-Down Enable bit

1 = D- data line pull-down resistor is enabled0 = D- data line pull-down resistor is disabled

bit 3 VBUSON: VBUS Power-on bit

1 = VBUS line is powered

0 = VBUS line is not powered

bit 2 **OTGEN:** OTG Functionality Enable bit

1 = DPPULUP, DMPULUP, DPPULDWN and DMPULDWN bits are under software control

0 = DPPULUP, DMPULUP, DPPULDWN and DMPULDWN bits are under USB hardware control

bit 1 VBUSCHG: VBUS Charge Enable bit

1 = VBUS line is charged through a pull-up resistor

0 = VBUS line is not charged through a resistor

bit 0 VBUSDIS: VBUS Discharge Enable bit

1 = VBUS line is discharged through a pull-down resistor

0 = VBUS line is not discharged through a resistor

#### REGISTER 10-5: U1PWRC: USB POWER CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31.24				_			_	_
23:16	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23.10	_	-	-	_		-	_	_
15:8	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
13.0				_			_	_
7:0	R-0	U-0	U-0	R/W-0	R/W-0	U-0	R/W-0	R/W-0
7.0	UACTPND	_	_	USLPGRD	USBBUSY <sup>(1)</sup>		USUSPEND	USBPWR

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-8 Unimplemented: Read as '0'

bit 7 **UACTPND:** USB Activity Pending bit

1 = USB bus activity has been detected; however, an interrupt is pending, which has yet to be generated

0 = An interrupt is not pending

bit 6-5 Unimplemented: Read as '0'

bit 4 USLPGRD: USB Sleep Entry Guard bit

1 = Sleep entry is blocked if USB bus activity is detected or if a notification is pending

0 = USB module does not block Sleep entry

bit 3 **USBBUSY:** USB Module Busy bit<sup>(1)</sup>

1 = USB module is active or disabled, but not ready to be enabled

0 = USB module is not active and is ready to be enabled

bit 2 Unimplemented: Read as '0'

bit 1 USUSPEND: USB Suspend Mode bit

1 = USB module is placed in Suspend mode

(The 48 MHz USB clock will be gated off. The transceiver is placed in a low-power state.)

0 = USB module operates normally

bit 0 USBPWR: USB Operation Enable bit

1 = USB module is turned on

0 = USB module is disabled

(Outputs held inactive, device pins not used by USB, analog features are shut down to reduce power consumption.)

**Note 1:** When USBPWR = 0 and USBBUSY = 1, status from all other registers is invalid and writes to all USB module registers produce undefined results.

#### REGISTER 10-6: U1IR: USB INTERRUPT REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31.24		_			_			_
22,16	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23:16		_			_			_
15:8	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
15.6	_	_			_			_
	R/WC-0, HS	R/WC-0, HS	R/WC-0, HS	R/WC-0, HS	R/WC-0, HS	R/WC-0, HS	R-0	R/WC-0, HS
7:0	STALLIF	ATTACHIF <sup>(1)</sup>	RESUMEIF(2)	IDLEIF	TRNIF <sup>(3)</sup>	SOFIF	UERRIF <sup>(4)</sup>	URSTIF <sup>(5)</sup>
	OTALLII	711 17101111	REGOIVIEII	IDLLII	1131411	00111	OLIVIVII	DETACHIF <sup>(6)</sup>

Legend:	WC = Write '1' to clear	HS = Hardware Settable bit
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared x = Bit is unknown

### bit 31-8 Unimplemented: Read as '0'

- bit 7 STALLIF: STALL Handshake Interrupt bit
  - 1 = In Host mode a STALL handshake was received during the handshake phase of the transaction In Device mode a STALL handshake was transmitted during the handshake phase of the transaction
  - 0 = STALL handshake has not been sent
- bit 6 ATTACHIF: Peripheral Attach Interrupt bit<sup>(1)</sup>
  - 1 = Peripheral attachment was detected by the USB module
  - 0 = Peripheral attachment was not detected
- bit 5 **RESUMEIF:** Resume Interrupt bit<sup>(2)</sup>
  - 1 = K-State is observed on the D+ or D- pin for  $2.5 \mu s$
  - 0 = K-State is not observed
- bit 4 IDLEIF: Idle Detect Interrupt bit
  - 1 = Idle condition detected (constant Idle state of 3 ms or more)
  - 0 = No Idle condition detected
- bit 3 TRNIF: Token Processing Complete Interrupt bit (3)
  - 1 = Processing of current token is complete; a read of the U1STAT register will provide endpoint information
  - 0 = Processing of current token not complete
- bit 2 **SOFIF:** SOF Token Interrupt bit
  - 1 = SOF token received by the peripheral or the SOF threshold reached by the host
  - 0 = SOF token was not received nor threshold reached
- bit 1 **UERRIF**: USB Error Condition Interrupt bit<sup>(4)</sup>
  - 1 = Unmasked error condition has occurred
  - 0 = Unmasked error condition has not occurred
- bit 0 **URSTIF:** USB Reset Interrupt bit (Device mode)<sup>(5)</sup>
  - 1 = Valid USB Reset has occurred
  - 0 = No USB Reset has occurred

**DETACHIF:** USB Detach Interrupt bit (Host mode)<sup>(6)</sup>

- 1 = Peripheral detachment was detected by the USB module
- 0 = Peripheral detachment was not detected
- **Note 1:** This bit is valid only if the HOSTEN bit is set (see Register 10-11), there is no activity on the USB for 2.5 µs, and the current bus state is not SE0.
  - 2: When not in Suspend mode, this interrupt should be disabled.
  - 3: Clearing this bit will cause the STAT FIFO to advance.
  - **4:** Only error conditions enabled through the U1EIE register will set this bit.
  - 5: Device mode.
  - 6: Host mode.

#### REGISTER 10-7: U1IE: USB INTERRUPT ENABLE REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0	U-0						
31.24	_	_	_	_	_	_	_	_
23:16	U-0	U-0						
23.10		_	_	1	_	_	_	
15:8	U-0	U-0						
13.0		_	_	1	_	_	_	
	R/W-0	R/W-0						
7:0	STALLIE	ATTACHIE	RESUMEIE	IDLEIE	TRNIE	SOFIE	UERRIE <sup>(1)</sup>	URSTIE <sup>(2)</sup>
	OTALLIL	ATTAOTTIL	TEOOMEIL	IDLLIL	IIXIVIL	OOLIE	OLIVIVIL	DETACHIE <sup>(3)</sup>

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-8 Unimplemented: Read as '0'

bit 7 STALLIE: STALL Handshake Interrupt Enable bit

1 = STALL interrupt is enabled0 = STALL interrupt is disabled

bit 6 ATTACHIE: ATTACH Interrupt Enable bit

1 = ATTACH interrupt is enabled 0 = ATTACH interrupt is disabled

bit 5 RESUMEIE: RESUME Interrupt Enable bit

1 = RESUME interrupt is enabled0 = RESUME interrupt is disabled

bit 4 IDLEIE: Idle Detect Interrupt Enable bit

1 = Idle interrupt is enabled0 = Idle interrupt is disabled

bit 3 TRNIE: Token Processing Complete Interrupt Enable bit

1 = TRNIF interrupt is enabled0 = TRNIF interrupt is disabled

bit 2 **SOFIE:** SOF Token Interrupt Enable bit

1 = SOFIF interrupt is enabled0 = SOFIF interrupt is disabled

bit 1 **UERRIE:** USB Error Interrupt Enable bit<sup>(1)</sup>

1 = USB Error interrupt is enabled0 = USB Error interrupt is disabled

bit 0 **URSTIE**: USB Reset Interrupt Enable bit<sup>(2)</sup>

1 = URSTIF interrupt is enabled0 = URSTIF interrupt is disabled

**DETACHIE:** USB Detach Interrupt Enable bit<sup>(3)</sup>

1 = DATTCHIF interrupt is enabled0 = DATTCHIF interrupt is disabled

Note 1: For an interrupt to propagate USBIF, the UERRIE (U1IE<1>) bit must be set.

2: Device mode.

3: Host mode.

#### REGISTER 10-8: U1EIR: USB ERROR INTERRUPT STATUS REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31:24	_	-		-	-	_		_
23:16	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23.10	_	_	_	_	_	_	_	_
15:8	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
15.6	_	_	_	_	_	_	_	_
	R/WC-0, HS	R/WC-0, HS	R/WC-0, HS	R/WC-0, HS	R/WC-0, HS	R/WC-0, HS	R/WC-0, HS	R/WC-0, HS
7:0	BTSEF	BMXEF	DMAEF <sup>(1)</sup>	BTOEF <sup>(2)</sup>	DFN8EF	CRC16EF	CRC5EF <sup>(4)</sup>	PIDEF
	DISEF	DIVINE	DIVINEL,	DIOEL,	DINOEF	CINCIDE	EOFEF <sup>(3,5)</sup>	IDEF

Legend:WC = Write '1' to clearHS = Hardware Settable bitR = Readable bitW = Writable bitU = Unimplemented bit, read as '0'-n = Value at POR'1' = Bit is set'0' = Bit is clearedx = Bit is unknown

bit 31-8 Unimplemented: Read as '0'

bit 7 BTSEF: Bit Stuff Error Flag bit

1 = Packet rejected due to bit stuff error

0 = Packet accepted

bit 6 BMXEF: Bus Matrix Error Flag bit

1 = The base address, of the Buffer Descriptor Table, or the address of an individual buffer pointed to by a Buffer Descriptor Table entry, is invalid.

0 = No address error

bit 5 **DMAEF:** DMA Error Flag bit<sup>(1)</sup>

1 = USB DMA error condition detected

0 = No DMA error

bit 4 BTOEF: Bus Turnaround Time-Out Error Flag bit (2)

1 = Bus turnaround time-out has occurred

0 = No bus turnaround time-out

bit 3 **DFN8EF:** Data Field Size Error Flag bit

1 = Data field received is not an integral number of bytes

0 = Data field received is an integral number of bytes

bit 2 CRC16EF: CRC16 Failure Flag bit

1 = Data packet rejected due to CRC16 error

0 = Data packet accepted

- **Note 1:** This type of error occurs when the module's request for the DMA bus is not granted in time to service the module's demand for memory, resulting in an overflow or underflow condition, and/or the allocated buffer size is not sufficient to store the received data packet causing it to be truncated.
  - 2: This type of error occurs when more than 16-bit-times of Idle from the previous End-of-Packet (EOP) has elapsed.
  - **3:** This type of error occurs when the module is transmitting or receiving data and the SOF counter has reached zero.
  - 4: Device mode.
  - 5: Host mode.

### REGISTER 10-8: U1EIR: USB ERROR INTERRUPT STATUS REGISTER (CONTINUED)

bit 1 CRC5EF: CRC5 Host Error Flag bit (4)

1 = Token packet rejected due to CRC5 error

0 = Token packet accepted **EOFEF:** EOF Error Flag bit<sup>(3,5)</sup>

1 = An EOF error condition was detected0 = No EOF error condition was detected

bit 0 PIDEF: PID Check Failure Flag bit

1 = PID check failed0 = PID check passed

- **Note 1:** This type of error occurs when the module's request for the DMA bus is not granted in time to service the module's demand for memory, resulting in an overflow or underflow condition, and/or the allocated buffer size is not sufficient to store the received data packet causing it to be truncated.
  - 2: This type of error occurs when more than 16-bit-times of Idle from the previous End-of-Packet (EOP) has elapsed.
  - **3:** This type of error occurs when the module is transmitting or receiving data and the SOF counter has reached zero.
  - 4: Device mode.
  - 5: Host mode.

#### REGISTER 10-9: U1EIE: USB ERROR INTERRUPT ENABLE REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
04.04	U-0	U-0						
31:24	_	_	_	_	_	_	_	_
00.46	U-0	U-0						
23:16	_	_	_	_	_	_	_	_
15:8	U-0	U-0						
15.6	_	_	_	_	_	_	_	
	R/W-0	R/W-0						
7:0	BTSEE	BMXEE	DMAEE	BTOEE	DFN8EE	CRC16EE	CRC5EE <sup>(1)</sup> EOFEE <sup>(2)</sup>	PIDEE

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-8 Unimplemented: Read as '0'

bit 7 BTSEE: Bit Stuff Error Interrupt Enable bit

1 = BTSEF interrupt is enabled0 = BTSEF interrupt is disabled

bit 6 BMXEE: Bus Matrix Error Interrupt Enable bit

1 = BMXEF interrupt is enabled0 = BMXEF interrupt is disabled

bit 5 **DMAEE:** DMA Error Interrupt Enable bit

1 = DMAEF interrupt is enabled

0 = DMAEF interrupt is disabled

bit 4 BTOEE: Bus Turnaround Time-out Error Interrupt Enable bit

1 = BTOEF interrupt is enabled0 = BTOEF interrupt is disabled

bit 3 **DFN8EE:** Data Field Size Error Interrupt Enable bit

1 = DFN8EF interrupt is enabled

0 = DFN8EF interrupt is disabled

bit 2 CRC16EE: CRC16 Failure Interrupt Enable bit

1 = CRC16EF interrupt is enabled

0 = CRC16EF interrupt is disabled

bit 1 **CRC5EE**: CRC5 Host Error Interrupt Enable bit<sup>(1)</sup>

1 = CRC5EF interrupt is enabled

0 = CRC5EF interrupt is disabled

**EOFEE:** EOF Error Interrupt Enable bit<sup>(2)</sup>

1 = EOF interrupt is enabled

0 = EOF interrupt is disabled

bit 0 PIDEE: PID Check Failure Interrupt Enable bit

1 = PIDEF interrupt is enabled

0 = PIDEF interrupt is disabled

Note 1: Device mode.

2: Host mode.

Note: For an interrupt to propagate the USBIF register, the UERRIE (U1IE<1>) bit must be set.

#### **REGISTER 10-10: U1STAT: USB STATUS REGISTER**

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0                U-0							
31.24	-	_	-	_	_	1	-	_
23:16	U-0                U-0							
23.10	-	_	-	_	_	1	-	_
15:8	U-0                U-0							
13.0	-	_	-	_	_	1	-	_
7:0	R-x	R-x	R-x	R-x	R-x	R-x	U-0	U-0
7:0		ENDP.	T<3:0>		DIR	PPBI		_

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-8 Unimplemented: Read as '0'

bit 7-4 **ENDPT<3:0>:** Encoded Number of Last Endpoint Activity bits

(Represents the number of the Buffer Descriptor Table, updated by the last USB transfer.)

1111 = Endpoint 15

1110 = Endpoint 14

0001 = Endpoint 1

0000 = Endpoint 0

- bit 3 **DIR:** Last Buffer Descriptor Direction Indicator bit
  - 1 = Last transaction was a transmit (TX) transfer
  - 0 = Last transaction was a receive (RX) transfer
- bit 2 PPBI: Ping-Pong Buffer Descriptor Pointer Indicator bit
  - 1 = The last transaction was to the ODD Buffer Descriptor bank
  - 0 = The last transaction was to the EVEN Buffer Descriptor bank
- bit 1-0 Unimplemented: Read as '0'

The U1STAT register is a window into a 4-byte FIFO maintained by the USB module. U1STAT value is only Note: valid when the TRNIF (U1IR<3>) bit is active. Clearing the TRNIF bit advances the FIFO. Data in register

is invalid when the TRNIF bit = 0.

#### **REGISTER 10-11: U1CON: USB CONTROL REGISTER**

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31:24	_	_			_	_	_	_
23:16	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23.10	_	_			_	_	_	_
15:8	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
13.6		-	_	-	_		-	
	R-x	R-x	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
7:0	JSTATE	SE0	PKTDIS <sup>(4)</sup>	USBRST	HOSTEN <sup>(2)</sup>	RESUME <sup>(3)</sup>	PPBRST	USBEN <sup>(4)</sup>
	JOIAIE	350	TOKBUSY <sup>(1,5)</sup>	USDRST	HOSTEN,	RESUME	FFDRSI	SOFEN <sup>(5)</sup>

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-8 Unimplemented: Read as '0'

1 = JSTATE was detected on the USB

0 = No JSTATE was detected

bit 6 SE0: Live Single-Ended Zero flag bit

1 = Single-Ended Zero was detected on the USB

0 = No Single-Ended Zero was detected

bit 5 **PKTDIS:** Packet Transfer Disable bit<sup>(4)</sup>

1 = Token and packet processing is disabled (set upon SETUP token received)

0 = Token and packet processing is enabled

TOKBUSY: Token Busy Indicator bit (1,5)

1 = Token is being executed by the USB module

0 = No token is being executed

bit 4 USBRST: Module Reset bit<sup>(5)</sup>

1 = USB reset generated

0 = USB reset terminated

bit 3 HOSTEN: Host Mode Enable bit<sup>(2)</sup>

1 = USB host capability is enabled

0 = USB host capability is disabled

bit 2 RESUME: RESUME Signaling Enable bit(3)

1 = RESUME signaling is activated

0 = RESUME signaling is disabled

- **Note 1:** Software is required to check this bit before issuing another token command to the U1TOK register (see Register 10-15).
  - 2: All host control logic is reset any time that the value of this bit is toggled.
  - 3: Software must set RESUME for 10 ms if the part is a function, or for 25 ms if the part is a host, and then clear it to enable remote wake-up. In Host mode, the USB module will append a Low-Speed EOP to the RESUME signaling when this bit is cleared.
  - 4: Device mode.
  - 5: Host mode.

### REGISTER 10-11: U1CON: USB CONTROL REGISTER (CONTINUED)

- bit 1 PPBRST: Ping-Pong Buffers Reset bit
  - 1 = Reset all Even/Odd buffer pointers to the EVEN Buffer Descriptor banks
  - 0 = Even/Odd buffer pointers are not Reset
- bit 0 USBEN: USB Module Enable bit (4)
  - 1 = USB module and supporting circuitry is enabled
  - 0 = USB module and supporting circuitry is disabled

**SOFEN:** SOF Enable bit<sup>(5)</sup>

- 1 = SOF token is sent every 1 ms
- 0 = SOF token is disabled
- **Note 1:** Software is required to check this bit before issuing another token command to the U1TOK register (see Register 10-15).
  - **2:** All host control logic is reset any time that the value of this bit is toggled.
  - 3: Software must set RESUME for 10 ms if the part is a function, or for 25 ms if the part is a host, and then clear it to enable remote wake-up. In Host mode, the USB module will append a Low-Speed EOP to the RESUME signaling when this bit is cleared.
  - 4: Device mode.
  - 5: Host mode.

#### **REGISTER 10-12: U1ADDR: USB ADDRESS REGISTER**

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0                U-0							
31:24	_	-	-	_	_	_	_	_
23:16	U-0                U-0							
23.10	_	_	_	_	_	_	_	_
15:8	U-0                U-0							
15.6	_	_	_	_	_	_	_	_
7.0	R/W-0              R/W-0							
7:0	LSPDEN			D	EVADDR<6:0	)>		

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-8 Unimplemented: Read as '0'

bit 7 LSPDEN: Low-Speed Enable Indicator bit

1 = Next token command to be executed at Low-Speed0 = Next token command to be executed at Full-Speed

bit 6-0 **DEVADDR<6:0>:** 7-bit USB Device Address bits

### REGISTER 10-13: U1FRML: USB FRAME NUMBER LOW REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0                U-0							
31.24	-	_	_	_	-	_	_	
23:16	U-0                U-0							
23.10	-	_	_	_	-	_	_	
15:8	U-0                U-0							
15.6	1	_	_	_	-	_	-	
7.0	R-0                R-0							
7:0				FRML	.<7:0>			

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-8 Unimplemented: Read as '0'

bit 7-0 FRML<7:0>: The 11-bit Frame Number Lower bits

The register bits are updated with the current frame number whenever a SOF TOKEN is received.

### REGISTER 10-14: U1FRMH: USB FRAME NUMBER HIGH REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0	
21.24	U-0                U-0								
31:24	_	_	-	_	_	_	_	_	
23:16	U-0                U-0								
23.10	_	_	-	_	_	_	_	_	
15:8	U-0                U-0								
15.6	_	_	_	_	_	_	_	_	
7:0	U-0	U-0	U-0	U-0	U-0	R-0	R-0	R-0	
	_	_		_	_		FRMH<2:0>	U-0 U-0 U-0 U-0 U-0 U-0 R-0 R-0	

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-3 Unimplemented: Read as '0'

bit 2-0 FRMH<2:0>: The Upper 3 bits of the Frame Numbers bits

The register bits are updated with the current frame number whenever a SOF TOKEN is received.

### **REGISTER 10-15: U1TOK: USB TOKEN REGISTER**

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0		
31:24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0		
31.24	1	_	-	-	1	1	_	_		
23:16	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0		
23.10	_	_	_	_	_	_	_	_		
15:8	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0		
13.6	_	_	_	_	_	_	_	_		
7.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0		
7:0		PID<	3:0> <sup>(1)</sup>			EP<	3:0>	0 U-0 - — — 0 U-0 - — U-0 - — — 0 U-0		

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-8 Unimplemented: Read as '0'

bit 7-4 PID<3:0>: Token Type Indicator bits<sup>(1)</sup>

1101 = SETUP (TX) token type transaction 1001 = IN (RX) token type transaction

0001 = OUT (TX) token type transaction

Note: All other values are reserved and must not be used.

bit 3-0 **EP<3:0>:** Token Command Endpoint Address bits

The four bit value must specify a valid endpoint.

Note 1: All other values are reserved and must not be used.

#### REGISTER 10-16: U1SOF: USB SOF THRESHOLD REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0                U-0							
31:24	-		-	-	-	_	_	_
23:16	U-0                U-0							
23.10	_	_	_	_	_	_	_	_
15:8	U-0                U-0							
15.6	_		_	_	_	_	_	_
7:0	R/W-0              R/W-0							
		_		CNT	<7:0>	_		

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-8 Unimplemented: Read as '0'

bit 7-0 CNT<7:0>: SOF Threshold Value bits

Typical values of the threshold are:

01001010 = 64-byte packet

00101010 = 32-byte packet

000101010 = 32-byte packet

00010010 = 8-byte packet

#### REGISTER 10-17: U1BDTP1: USB BUFFER DESCRIPTOR TABLE PAGE 1 REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0                U-0							
31.24	_	_	-	-	_	_	-	_
23:16	U-0                U-0							
23.10	_	_	-	-	_	_	-	_
45.0	U-0                U-0							
15:8	_	_	_	_	_	_	_	_
7.0	R/W-0              U-0							
7:0			В	DTPTRL<15:	9>			_

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR  $(1)^2$  = Bit is set  $(0)^2$  = Bit is cleared  $(0)^2$  = Bit is cleared  $(0)^2$  = Bit is cleared  $(0)^2$  = Bit is cleared

bit 31-8 Unimplemented: Read as '0'

bit 7-1 BDTPTRL<15:9>: Buffer Descriptor Table Base Address bits

This 7-bit value provides address bits 15 through 9 of the Buffer Descriptor Table base address, which defines the starting location of the Buffer Descriptor Table in system memory.

The 32-bit Buffer Descriptor Table base address is 512-byte aligned.

bit 0 **Unimplemented:** Read as '0'

### REGISTER 10-18: U1BDTP2: USB BUFFER DESCRIPTOR TABLE PAGE 2 REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0						
31:24	U-0                U-0													
31.24	_	_	_	_	-		_	_						
23:16	U-0                U-0													
23.10	_	_	_	_	-	_	_	_						
15:8	U-0                U-0													
15.6	_	_	_	_	_	_	_	_						
7.0	R/W-0              R/W-0													
7:0				BDTPTR	H<23:16>			U-0 U-0 —						

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-8 Unimplemented: Read as '0'

bit 7-0 BDTPTRH<23:16>: Buffer Descriptor Table Base Address bits

This 8-bit value provides address bits 23 through 16 of the Buffer Descriptor Table base address, which defines the starting location of the Buffer Descriptor Table in system memory.

The 32-bit Buffer Descriptor Table base address is 512-byte aligned.

#### REGISTER 10-19: U1BDTP3: USB BUFFER DESCRIPTOR TABLE PAGE 3 REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0                U-0							
31.24	-	-	1	-	-	1		_
22:46	U-0                U-0							
23:16		_		_	-	-	_	_
15:8	U-0                U-0							
15.6	_	_	_	_	_	_	_	_
7.0	R/W-0              R/W-0							
7:0				BDTPTR	U<31:24>			

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-8 Unimplemented: Read as '0'

bit 7-0 BDTPTRU<31:24>: Buffer Descriptor Table Base Address bits

This 8-bit value provides address bits 31 through 24 of the Buffer Descriptor Table base address, defines the starting location of the Buffer Descriptor Table in system memory.

The 32-bit Buffer Descriptor Table base address is 512-byte aligned.

#### REGISTER 10-20: U1CNFG1: USB CONFIGURATION 1 REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0                U-0							
31.24	-	_	-	_	_	_	_	_
23:16	U-0                U-0							
23.10	-	_	-	_	_	_	_	_
15:8	U-0                U-0							
13.6	_	_	_	_	_	_	_	_
7:0	R/W-0	R/W-0	U-0	R/W-0	U-0	U-0	U-0	R/W-0
	UTEYE	UOEMON	-	USBSIDL	-	-	-	UASUSPND

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-8 Unimplemented: Read as '0'

bit 7 UTEYE: USB Eye-Pattern Test Enable bit

1 = Eye-Pattern Test is enabled0 = Eye-Pattern Test is disabled

bit 6 **UOEMON:** USB OE Monitor Enable bit

1 = OE signal is active; it indicates intervals during which the D+/D- lines are driving

0 = OE signal is inactive

bit 5 Unimplemented: Read as '0'

bit 4 USBSIDL: Stop in Idle Mode bit

1 = Discontinue module operation when the device enters Idle mode

0 = Continue module operation when the device enters Idle mode

bit 3-1 Unimplemented: Read as '0'

bit 0 **UASUSPND:** Automatic Suspend Enable bit

- 1 = USB module automatically suspends upon entry to Sleep mode. See the USUSPEND bit (U1PWRC<1>) in Register 10-5.
- 0 = USB module does not automatically suspend upon entry to Sleep mode. Software must use the USUSPEND bit (U1PWRC<1>) to suspend the module, including the USB 48 MHz clock.

#### REGISTER 10-21: U1EP0-U1EP15: USB ENDPOINT CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0                U-0							
31.24	-	_	-	_	-	_	_	-
23:16	U-0                U-0							
23.10	_	_	_	_	_	_	_	_
15:8	U-0                U-0							
15.6	_	_	_	_	_	_	_	_
7:0	R/W-0	R/W-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
	LSPD	RETRYDIS	_	EPCONDIS	EPRXEN	EPTXEN	EPSTALL	EPHSHK

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-8 Unimplemented: Read as '0'

bit 7 LSPD: Low-Speed Direct Connection Enable bit (Host mode and U1EP0 only)

1 = Direct connection to a Low-Speed device enabled

0 = Direct connection to a Low-Speed device disabled; hub required with PRE\_PID

bit 6 **RETRYDIS:** Retry Disable bit (Host mode and U1EP0 only)

1 = Retry NAKed transactions disabled

0 = Retry NAKed transactions enabled; retry done in hardware

bit 5 **Unimplemented:** Read as '0'

bit 4 EPCONDIS: Bidirectional Endpoint Control bit

If EPTXEN = 1 and EPRXEN = 1:

1 = Disable Endpoint n from Control transfers; only TX and RX transfers allowed

0 = Enable Endpoint n for Control (SETUP) transfers; TX and RX transfers also allowed

Otherwise, this bit is ignored.

bit 3 EPRXEN: Endpoint Receive Enable bit

1 = Endpoint n receive is enabled

0 = Endpoint n receive is disabled

bit 2 **EPTXEN:** Endpoint Transmit Enable bit

1 = Endpoint n transmit is enabled

0 = Endpoint n transmit is disabled

bit 1 EPSTALL: Endpoint Stall Status bit

1 = Endpoint n was stalled

0 = Endpoint n was not stalled

bit 0 EPHSHK: Endpoint Handshake Enable bit

1 = Endpoint Handshake is enabled

0 = Endpoint Handshake is disabled (typically used for isochronous endpoints)

### 11.0 I/O PORTS

Note:

This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To complement the information in this data sheet, refer to **Section 12.** "I/O **Ports**" (DS60001120), which is available from the *Documentation* > *Reference Manual* section of the Microchip PIC32 web site (www.microchip.com/pic32).

General purpose I/O pins are the simplest of peripherals. They allow the PIC® MCU to monitor and control other devices. To add flexibility and functionality, some pins are multiplexed with alternate functions.


These functions depend on which peripheral features are on the device. In general, when a peripheral is functioning, that pin may not be used as a general purpose I/O pin.

Key features of this module include:

- · Individual output pin open-drain enable/disable
- · Individual input pin weak pull-up and pull-down
- Monitor selective inputs and generate interrupt when change in pin state is detected
- · Operation during Sleep and Idle modes
- Fast bit manipulation using CLR, SET, and INV registers

Figure 11-1 illustrates a block diagram of a typical multiplexed I/O port.

FIGURE 11-1: BLOCK DIAGRAM OF A TYPICAL MULTIPLEXED PORT STRUCTURE



### 11.1 Parallel I/O (PIO) Ports

All port pins have 10 registers directly associated with their operation as digital I/O. The data direction register (TRISx) determines whether the pin is an input or an output. If the data direction bit is a '1', then the pin is an input. All port pins are defined as inputs after a Reset. Reads from the latch (LATx) read the latch. Writes to the latch write the latch. Reads from the port (PORTx) read the port pins, while writes to the port pins write the latch.

#### 11.1.1 OPEN-DRAIN CONFIGURATION

In addition to the PORTx, LATx, and TRISx registers for data control, some port pins can also be individually configured for either digital or open-drain output. This is controlled by the Open-Drain Control register, ODCx, associated with each port. Setting any of the bits configures the corresponding pin to act as an open-drain output.

The open-drain feature allows the generation of outputs higher than VDD (e.g., 5V) on any desired 5V-tolerant pins by using external pull-up resistors. The maximum open-drain voltage allowed is the same as the maximum VIH specification.

See the "Pin Diagrams" section for the available pins and their functionality.

# 11.1.2 CONFIGURING ANALOG AND DIGITAL PORT PINS

The ANSELx register controls the operation of the analog port pins. The port pins that are to function as analog inputs must have their corresponding ANSEL and TRIS bits set. In order to use port pins for I/O functionality with digital modules, such as Timers, UARTs, etc., the corresponding ANSELx bit must be cleared.

The ANSELx register has a default value of 0xFFFF; therefore, all pins that share analog functions are analog (not digital) by default.

If the TRIS bit is cleared (output) while the ANSELx bit is set, the digital output level (VOH or VOL) is converted by an analog peripheral, such as the ADC module or Comparator module.

When the PORT register is read, all pins configured as analog input channels are read as cleared (a low level).

Pins configured as digital inputs do not convert an analog input. Analog levels on any pin defined as a digital input (including the ANx pins) can cause the input buffer to consume current that exceeds the device specifications.

### 11.1.3 I/O PORT WRITE/READ TIMING

One instruction cycle is required between a port direction change or port write operation and a read operation of the same port. Typically this instruction would be a  $\mathtt{NOP}$ .

#### 11.1.4 INPUT CHANGE NOTIFICATION

The input change notification function of the I/O ports allows the PIC32MX1XX/2XX 28/36/44-pin Family devices to generate interrupt requests to the processor in response to a change-of-state on selected input pins. This feature can detect input change-of-states even in Sleep mode, when the clocks are disabled. Every I/O port pin can be selected (enabled) for generating an interrupt request on a change-of-state.

Five control registers are associated with the CN functionality of each I/O port. The CNENx registers contain the CN interrupt enable control bits for each of the input pins. Setting any of these bits enables a CN interrupt for the corresponding pins.

The CNSTATx register indicates whether a change occurred on the corresponding pin since the last read of the PORTx bit.

Each I/O pin also has a weak pull-up and a weak pull-down connected to it. The pull-ups act as a current source or sink source connected to the pin, and eliminate the need for external resistors when push-button or keypad devices are connected. The pull-ups and pull-downs are enabled separately using the CNPUx and the CNPDx registers, which contain the control bits for each of the pins. Setting any of the control bits enables the weak pull-ups and/or pull-downs for the corresponding pins.

Note:

Pull-ups and pull-downs on change notification pins should always be disabled when the port pin is configured as a digital output.

An additional control register (CNCONx) is shown in Register 11-3.

### 11.2 CLR, SET and INV Registers

Every I/O module register has a corresponding CLR (clear), SET (set) and INV (invert) register designed to provide fast atomic bit manipulations. As the name of the register implies, a value written to a SET, CLR or INV register effectively performs the implied operation, but only on the corresponding base register and only bits specified as '1' are modified. Bits specified as '0' are not modified.

Reading SET, CLR and INV registers returns undefined values. To see the affects of a write operation to a SET, CLR, or INV register, the base register must be read.

### 11.3 Peripheral Pin Select

A major challenge in general purpose devices is providing the largest possible set of peripheral features while minimizing the conflict of features on I/O pins. The challenge is even greater on low pin-count devices. In an application where more than one peripheral needs to be assigned to a single pin, inconvenient workarounds in application code or a complete redesign may be the only option.

The Peripheral Pin Select (PPS) configuration provides an alternative to these choices by enabling peripheral set selection and their placement on a wide range of I/O pins. By increasing the pinout options available on a particular device, users can better tailor the device to their entire application, rather than trimming the application to fit the device.

The PPS configuration feature operates over a fixed subset of digital I/O pins. Users may independently map the input and/or output of most digital peripherals to these I/O pins. PPS is performed in software and generally does not require the device to be reprogrammed. Hardware safeguards are included that prevent accidental or spurious changes to the peripheral mapping once it has been established.

#### 11.3.1 AVAILABLE PINS

The number of available pins is dependent on the particular device and its pin count. Pins that support the PPS feature include the designation "RPn" in their full pin designation, where "RP" designates a remappable peripheral and "n" is the remappable port number.

### 11.3.2 AVAILABLE PERIPHERALS

The peripherals managed by the PPS are all digitalonly peripherals. These include general serial communications (UART and SPI), general purpose timer clock inputs, timer-related peripherals (input capture and output compare) and interrupt-on-change inputs.

In comparison, some digital-only peripheral modules are never included in the PPS feature. This is because the peripheral's function requires special I/O circuitry on a specific port and cannot be easily connected to multiple pins. These modules include I<sup>2</sup>C among others. A similar requirement excludes all modules with analog inputs, such as the Analog-to-Digital Converter (ADC).

A key difference between remappable and non-remappable peripherals is that remappable peripherals are not associated with a default I/O pin. The peripheral must always be assigned to a specific I/O pin before it can be used. In contrast, non-remappable peripherals are always available on a default pin, assuming that the peripheral is active and not conflicting with another peripheral.

When a remappable peripheral is active on a given I/O pin, it takes priority over all other digital I/O and digital communication peripherals associated with the pin.

Priority is given regardless of the type of peripheral that is mapped. Remappable peripherals never take priority over any analog functions associated with the pin.

# 11.3.3 CONTROLLING PERIPHERAL PIN SELECT

PPS features are controlled through two sets of SFRs: one to map peripheral inputs, and one to map outputs. Because they are separately controlled, a particular peripheral's input and output (if the peripheral has both) can be placed on any selectable function pin without constraint.

The association of a peripheral to a peripheral-selectable pin is handled in two different ways, depending on whether an input or output is being mapped.

#### 11.3.4 INPUT MAPPING

The inputs of the PPS options are mapped on the basis of the peripheral. That is, a control register associated with a peripheral dictates the pin it will be mapped to. The [pin name]R registers, where [pin name] refers to the peripheral pins listed in Table 11-1, are used to configure peripheral input mapping (see Register 11-1). Each register contains sets of 4 bit fields. Programming these bit fields with an appropriate value maps the RPn pin with the corresponding value to that peripheral. For any given device, the valid range of values for any bit field is shown in Table 11-1.

For example, Figure 11-2 illustrates the remappable pin selection for the U1RX input.

FIGURE 11-2: REMAPPABLE INPUT EXAMPLE FOR U1RX




TABLE 11-1: INPUT PIN SELECTION

Peripheral Pin	[pin name]R SFR	[pin name]R bits	[pin name]R Value to RPn Pin Selection					
INT4	INT4R	INT4R<3:0>	0000 = RPA0 0001 = RPB3					
T2CK	T2CKR	T2CKR<3:0>	0010 = RPB4 0011 = RPB15 0100 = RPB7					
IC4	IC4R	IC4R<3:0>	0101 = RPC7 <sup>(2)</sup> 0110 = RPC0 <sup>(1)</sup> 0111 = RPC5 <sup>(2)</sup>					
SS1	SS1R	SS1R<3:0>	1000 = Reserved					
REFCLKI	REFCLKIR	REFCLKIR<3:0>	1111 = Reserved					
INT3	INT3R	INT3R<3:0>	0000 = RPA1 0001 = RPB5					
T3CK	T3CKR	T3CKR<3:0>	0010 = RPB1 0011 = RPB11					
IC3	IC3R	IC3R<3:0>	0100 = RPB8 0101 = RPA8 <sup>(2)</sup>					
U1CTS	U1CTSR	U1CTSR<3:0>	0110 = RPC8 <sup>(2)</sup> 0111 = RPA9 <sup>(2)</sup> 1000 = Reserved					
U2RX	U2RXR	U2RXR<3:0>	• .					
SDI1	SDI1R	SDI1R<3:0>	1111 = Reserved					
INT2	INT2R	INT2R<3:0>	0000 = RPA2					
T4CK	T4CKR	T4CKR<3:0>	0001 = RPB6 0010 = RPA4					
IC1	IC1R	IC1R<3:0>	0011 = RPB13 0100 = RPB2					
IC5	IC5R	IC5R<3:0>	0101 = RPC6 <sup>(2)</sup>					
U1RX	U1RXR U2CTSR	U1RXR<3:0>	0110 = RPC1 <sup>(1)</sup> 0111 = RPC3 <sup>(1)</sup>					
U2CTS		U2CTSR<3:0>	1000 = Reserved					
SDI2	SDI2R	SDI2R<3:0>	·					
OCFB	OCFBR	OCFBR<3:0>	1111 = Reserved					
INT1	INT1R	INT1R<3:0>	0000 = RPA3 0001 = RPB14					
T5CK	T5CKR	T5CKR<3:0>	0010 = RPB0 0011 = RPB10 0100 = RPB9					
IC2	IC2R	IC2R<3:0>	0101 = RPC9 <sup>(1)</sup> 0110 = RPC2 <sup>(2)</sup> 0111 = RPC4 <sup>(2)</sup>					
<u>SS2</u>	SS2R	SS2R<3:0>	1000 = Reserved					
OCFA	OCFAR	OCFAR<3:0>	· · 1111 = Reserved					

Note 1: This pin is not available on 28-pin devices.


<sup>2:</sup> This pin is only available on 44-pin devices.

#### 11.3.5 OUTPUT MAPPING

In contrast to inputs, the outputs of the PPS options are mapped on the basis of the pin. In this case, a control register associated with a particular pin dictates the peripheral output to be mapped. The RPnR registers (Register 11-2) are used to control output mapping. Like the [pin name]R registers, each register contains sets of 4 bit fields. The value of the bit field corresponds to one of the peripherals, and that peripheral's output is mapped to the pin (see Table 11-2 and Figure 11-3).

A null output is associated with the output register reset value of '0'. This is done to ensure that remappable outputs remain disconnected from all output pins by default.

FIGURE 11-3: EXAMPLE OF MULTIPLEXING OF REMAPPABLE OUTPUT



# 11.3.6 CONTROLLING CONFIGURATION CHANGES

Because peripheral remapping can be changed during run time, some restrictions on peripheral remapping are needed to prevent accidental configuration changes. PIC32 devices include two features to prevent alterations to the peripheral map:

- · Control register lock sequence
- · Configuration bit select lock

#### 11.3.6.1 Control Register Lock Sequence

Under normal operation, writes to the RPnR and [pin name]R registers are not allowed. Attempted writes appear to execute normally, but the contents of the registers remain unchanged. To change these registers, they must be unlocked in hardware. The register lock is controlled by the Configuration bit, IOLOCK (CFGCON<13>). Setting IOLOCK prevents writes to the control registers; clearing IOLOCK allows writes.

To set or clear the IOLOCK bit, an unlock sequence must be executed. Refer to **Section 6. "Oscillator"** (DS60001112) in the "PIC32 Family Reference Manual" for details.

#### 11.3.6.2 Configuration Bit Select Lock

As an additional level of safety, the device can be configured to prevent more than one write session to the RPnR and [pin name]R registers. The Configuration bit, IOL1WAY (DEVCFG3<29>), blocks the IOLOCK bit from being cleared after it has been set once. If IOLOCK remains set, the register unlock procedure does not execute, and the PPS control registers cannot be written to. The only way to clear the bit and reenable peripheral remapping is to perform a device Reset.

In the default (unprogrammed) state, IOL1WAY is set, restricting users to one write session.

**TABLE 11-2: OUTPUT PIN SELECTION** 

RPn Port Pin	RPnR SFR	RPnR bits	RPnR Value to Peripheral Selection				
RPA0	RPA0R	RPA0R<3:0>	0000 = No Connect				
RPB3	RPB3R	RPB3R<3:0>	0001 = <u>U1TX</u> 0010 = <u>U2RTS</u>				
RPB4	RPB4R	RPB4R<3:0>	0011 = SS1				
RPB15	RPB15R	RPB15R<3:0>	0100 = Reserved 0101 = OC1				
RPB7	RPB7R	RPB7R<3:0>	0110 = Reserved 0111 = C2OUT				
RPC7	RPC7R	RPC7R<3:0>	1000 = Reserved				
RPC0	RPC0R	RPC0R<3:0>	<b></b> :				
RPC5	RPC5R	RPC5R<3:0>	1111 = Reserved				
RPA1	RPA1R	RPA1R<3:0>	0000 = No Connect				
RPB5	RPB5R	RPB5R<3:0>	0001 = Reserved 0010 = Reserved				
RPB1	RPB1R	RPB1R<3:0>	0011 = SDO1				
RPB11	RPB11R	RPB11R<3:0>	0100 = SDO2 0101 = OC2				
RPB8	RPB8R	RPB8R<3:0>	0110 = Reserved				
RPA8	RPA8R	RPA8R<3:0>	0111 = C3OUT				
RPC8	RPC8R	RPC8R<3:0>	<b></b> :				
RPA9	RPA9R	RPA9R<3:0>	1111 = Reserved				
RPA2	RPA2R	RPA2R<3:0>	0000 = No Connect 0001 = Reserved				
RPB6	RPB6R	RPB6R<3:0>	0001 - Reserved				
RPA4	RPA4R	RPA4R<3:0>	0011 = SDO1 0100 = SDO2				
RPB13	RPB13R	RPB13R<3:0>	0101 = OC4				
RPB2	RPB2R	RPB2R<3:0>	0110 = OC5 0111 = REFCLKO				
RPC6	RPC6R	RPC6R<3:0>	1000 = Reserved				
RPC1	RPC1R	RPC1R<3:0>	<b>∃</b> :				
RPC3	RPC3R	RPC3R<3:0>	1111 = Reserved				
RPA3	RPA3R	RPA3R<3:0>	1111 = Reserved 0000 = No Connect 0001 = U1RTS 0010 = U2TX				
RPB14	RPB14R	RPB14R<3:0>					
RPB0	RPB0R	RPB0R<3:0>	0011 = Reserved				
RPB10	RPB10R	RPB10R<3:0>	0100 = SS2 0101 = OC3				
RPB9	RPB9R	RPB9R<3:0>	0110 = Reserved 0111 = C1OUT				
RPC9	RPC9R	RPC9R<3:0>	1000 = Reserved				
RPC2	RPC2R	RPC2R<3:0>					
RPC4	RPC4R	RPC4R<3:0>	1111 = Reserved				

**PORTA REGISTER MAP Ports Control Registers TABLE 11-3:** 11.4

s	HI Reset	0000	0003	0000	079F	0000	XXXX	0000	XXXX	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	
	16/0	I	ANSA0	Ι	TRISA0		RA0	1	LATA0	_	ODCA0	Ι	CNPUA0	1	CNPDA0	Ι	Ι	Ι	CNIEA0	I	CNSTATAO 0000	
	17/1	1	ANSA1	I	TRISA1		RA1	I	LATA1	I	ODCA1	I	CNPUA1	1	CNPDA1	I	I	I	CNIEA1	I		
	18/2	1	-	I	TRISA2		RA2	I	LATA2	I	ODCA2	I	CNPUA2	1	CNPDA2	I	I	I	CNIEA2	I	CNSTATA2	
	19/3	1	1	Ι	TRISA3		RA3	Ι	LATA3	Ι	ODCA3	Ι	CNPUA3	1	CNPDA3	Ι	Ι	Ι	CNIEA3	I	CNSTATA4 CNSTATA3 CNSTATA2 CNSTATA1	
	20/4	1	1	Ι	TRISA4		RA4	Ι	LATA4	1	ODCA4	1	CNPUA4	1	CNPDA4	1	1	1	CNIEA4	I	CNSTATA4	
	21/5	1	1	_	-	_	I	_	_	_	-	-	-	1	-	-	-	-	_	1	-	
	22/6	1	1	Ι	Ι	Ι	1	Ι	1	I	Ι	Ι	1	1	1	Ι	Ι	Ι	1	I	1	
	23/7	1	1	1	TRISA7 <sup>(2)</sup>	1	RA7 <sup>(2)</sup>	1	LATA7 <sup>(2)</sup>	1	ODCA7 <sup>(2)</sup>	1	CNPUA7 <sup>(2)</sup>	1	CNPDA7 <sup>(2)</sup>	1	1	1	CNIEA7 <sup>(2)</sup>	1	CNSTATA7 <sup>(2)</sup>	
Bits	24/8	1	1	1	TRISA8 <sup>(2)</sup>	1	RA8 <sup>(2)</sup>	1	LATA8 <sup>(2)</sup>	1	ODCA8(2)	1	CNPUA8 <sup>(2)</sup>	1	CNPDA8 <sup>(2)</sup>	1	1	1	CNIEA8 <sup>(2)</sup>	1	CNSTATA8 <sup>(2)</sup>	hexadecimal.
	25/9	1	-	1	TRISA9 <sup>(2)</sup>	1	RA9(2)	1	LATA9 <sup>(2)</sup>	1	ODCA9 <sup>(2)</sup>	1	CNPUA9 <sup>(2)</sup>	1	CNPDA9 <sup>(2)</sup>	1	1	1	CNIEA9(2)	1	CNSTATA9 <sup>(2)</sup>	s are shown in
	26/10	I	1	-	TRISA10 <sup>(2)</sup>	-	RA10 <sup>(2)</sup>	-	LATA10 <sup>(2)</sup>	I	ODCA10 <sup>(2)</sup>	I	CNPUA10 <sup>(2)</sup>	_	CNPDA10 <sup>(2)</sup>	I	I	I	CNIEA10 <sup>(2)</sup>	1	CNSTATA10 <sup>(2)</sup> CNSTATA9 <sup>(2)</sup> CNSTATA8 <sup>(2)</sup> CNSTATA7 <sup>(2)</sup>	as '0'. Reset values are shown in hexadecimal
	27/11	1	1	1	Ι	1	I	1	-	_	Ι	Ι	1	1	1	Ι	Ι	Ι	-	Ι	1	
	28/12	1	1	Ι	Ι	Ι	Ι	Ι	Ι	-	Ι	Ι	1	Ι	Ι	Ι	Ι	Ι	Ι	Ι	1	x = unknown value on Reset; — = unimplemented, read
	29/13	1	_	-	-	-	_	-	_	_	-	-	_	_	_	-	SIDL	-	_	I	-	— = unim
	30/14	1	_	_	_	_	-	_	_	_	_	_	_	-	-	_	_	_	_	_	1	on Reset:
	31/15	1	_	Ι	Ι	Ι	1	Ι	-	I	Ι	Ι	_	1	1	Ι	NO	Ι	-	I	1	vn value o
e	Bit Range	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	unknov
	Register Name <sup>(1)</sup>	L	ANSELA	YOIGH	¥012	A T a C a	7 7 7	V±V -	5	0	ODCA		CNPUA	40	CNPDA		CNCONA	L	CNENA	+ 4 + O	CNSTALA	
SSƏ.	Virtual Addr (#_8878)	+	0000	040	0.00	0000	0700	0000	0000	0,00	0040	i c	0609	0	nana	_	0/09	000	0809	_	0609	Legend:

All registers in this table have corresponding CLR, SET and INV registers at their virtual addresses, plus offsets of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for more information.

This bit is only available on 44-pin devices. Note

9	stəsəЯ IIA	0000	EOOF	0000	FFFF	0000	XXXX	0000	XXXX	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	1
		0		00		00		00		0		00	-	0		00	00	0		00		-
	16/0	1	ANSB0	1	TRISB0		RB0	_	LATB0	-	ODCB0	_	CNPUB0	-	CNPDB0	_	_	-	CNIEB0	_	CN STATB0	
	1//1	1	ANSB1	I	TRISB1		RB1	_	LATB1	_	ODCB1	_	CNPUB1	_	CNPDB1	_	_	_	CNIEB1	_	CN STATB1	
	18/2	I	ANSB2	I	TRISB2		RB2	Ι	LATB2	I	ODCB2	Ι	CNPUB2	I	CNPDB2	Ι	Ι	I	CNIEB2	Ι	CN STATB2	
	19/3	1	ANSB3	-	<b>TRISB3</b>		RB3	_	LATB3	_	ODCB3	_	<b>CNPUB3</b>	_	CNPDB3	_	_	_	CNIEB3	_	CN STATB3	
	20/4	1	_	1	TRISB4		RB4	1	LATB4	1	ODCB4	1	CNPUB4	1	CNPDB4	1	1	1	CNIEB4	1	CN STATB4	
	21/5	I	I	I	TRISB5	I	RB5	I	LATB5	I	ODCB5	I	CNPUB5	I	CNPDB5	I	I	I	CNIEB5	I	CN STATB5	
	22/6	I	I	I	TRISB6 <sup>(2)</sup>	I	RC6 <sup>(2)</sup>	1	LATB6 <sup>(2)</sup>	1	ODCB6	1	CNPUB6(2)	ı	CNPDB6(2)	1	I	ı	CNIEB6 <sup>(2)</sup>	I	CN STATB6 <sup>(2)</sup>	
	23/7	ı	I	I	TRISB7	I	RB7	_	LATB7	_	ODCB7	_	CNPUB7	_	CNPDB7	_	_	_	CNIEB7	_	CN STATB7	•
Bits	24/8	I	I	I	TRISB8	I	RB8	Ι	LATB8	Ι	ODCB8	Ι	CNPUB8	Ι	CNPDB8	Ι	Ι	Ι	CNIEB8	Ι	CN STATB8	- Income
	25/9	I	I	I	TRISB9	I	RB9	I	LATB9	I	ODCB9	I	CNPUB9	I	CNPDB9	I	I	I	CNIEB9	I	CN STATB9	and and annual
	26/10	1	1	I	TRISB10	I	RB10	-	LATB10	_	ODCB10	-	CNPUB10	_	CNPDB10	-	-	_	CNIEB10	-	CN STATB10	
	27/11	1	1	1	TRISB11	1	RB11	I	LATB11	I	ODCB11	I	CNPUB11	I	CNPDB11	I	I	I	CNIEB11	I	CN STATB11	, ,
	28/12	1	ANSB12 <sup>(2)</sup>	1	TRISB12 <sup>(2)</sup>	1	RB12 <sup>(2)</sup>	-	LATB12 <sup>(2)</sup>	-	ODCB12 <sup>(2)</sup>	-	CNPUB12 <sup>(2)</sup>	-	CNPDB12 <sup>(2)</sup>	-	-	-	CNIEB11 <sup>(2)</sup>	-	CN STATB12 <sup>(2)</sup>	
	29/13	I	ANSB13	I	TRISB13	I	RB13	_	LATB13	_	ODCB13	_	CNPUB13	_	CNPDB13	_	TOIS	_	CNIEB13	_	CN STATB13	a a a a a a a a a a a a a a a a a a a
	30/14	1	ANSB14	I	TRISB14	1	RB14	1	LATB14	Ι	ODCB14	1	CNPUB14	_	CNPDB14	1	-	_	CNIEB14	1	CN STATB14	
	31/15	I	ANSB15	I	TRISB15	I	RB15	I	LATB15	I	ODCB15	I	CNPUB15	I	CNPDB15	I	NO	I	CNIEB15	I	CN STATB15	and or dear are
•	Bit Range	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	- and an
	Register Name	(	ANSELB		ממצו		202	S OTV			anno		CNFOB		CNPUB		CINCONE		CNENB		CNSTATB	
	Virtual Addr (#_8878)		001.9	7	0 0		071.0	6120	0010	9	0.140		ncia		091.9		0/10		081.9		6190 C	1 2 2 2 4

All registers in this table have corresponding CLR, SET and INV registers at their virtual addresses, plus offsets of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for more information.

This bit is not available on PIC32MX2XX devices. The reset value for the TRISB register when this bit is not available is 0x0000EFBF. x = unknown value on Reset; -- = unimplemented, read as '0'. Reset values are shown in hexadecimal. Note

PORTB REGISTER MAP

**TABLE 11-4**:

s	JeseR IIA	0000	000F	0000	03FF	0000	XXXX	0000	XXXX	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	
	16/0	I	ANSC0	_	TRISC0		RC0	_	LATC0	_	ODCC0	_	CNPUC0	-	CNPDC0	-	-	-	CNIEC0	-	CNSTATC0 0000	
	17/1	I	ANSC1	_	TRISC1		RC1	_	LATC1	_	ODCC1	_	CNPUC1	-	CNPDC1	I	-	-	CNIEC1	I	CNSTATC1	
	18/2	1	ANSC2(3)	1	TRISC2 <sup>(3)</sup>		RC2 <sup>(3)</sup>	1	LATC2 <sup>(3)</sup>	1	ODCC2 <sup>(3)</sup>	1	CNPUC2 <sup>(3)</sup>	-	CNPDC2 <sup>(3)</sup>	-	-	-	CNIEC2 <sup>(3)</sup>	_	CNSTATC3 CNSTATC2 <sup>(3)</sup>	
	19/3	1	ANSC3(4)	1	TRISC3		RC3	1	LATC3	1	ODCC3	1	CNPUC3	_	CNPDC3	1	_	_	CNIEC3	1	CNSTATC3	
	20/4	1	1	I	TRISC4 <sup>(3)</sup>		RC4 <sup>(3)</sup>	I	LATC4 <sup>(3)</sup>	I	ODCC4(3)	I	CNPUC4(3)	1	CNPDC4 <sup>(3)</sup>	1	1	1	CNIEC4 <sup>(3)</sup>	-	CNSTATC4 <sup>(3)</sup>	
	21/5	1	ı	I	TRISC5 <sup>(3)</sup>	I	RC5 <sup>(3)</sup>	I	LATC5 <sup>(3)</sup>	I	ODCC5(3)	I	CNPUC5(3)	1	CNPDC5(3)	1	1	1	CNIEC5(3)	-	CNSTATC8 <sup>(3)</sup> CNSTATC7 <sup>(3)</sup> CNSTATC6 <sup>(3)</sup> CNSTATC5 <sup>(3)</sup> CNSTATC4 <sup>(3)</sup>	
Bits	22/6	1	1	_	TRISC6 <sup>(3)</sup>	_	RC6 <sup>(3)</sup>	_	LATC6 <sup>(3)</sup>	_	(E)90000	_	CNPUC6 <sup>(3)</sup>	_	CNPDC6 <sup>(3)</sup>	_	_	_	CNIECe(3)	_	CNSTATC6 <sup>(3)</sup>	nal.
	23/7	1	I	1	TRISC7 <sup>(3)</sup>	1	RC7 <sup>(3)</sup>	1	LATC7 <sup>(3)</sup>	1	ODCC7(3)	1	CNPUC7(3)	1	CNPDC7(3)	1	1	1	CNIEC7(3)	-	CNSTATC7 <sup>(3)</sup>	n in hexadecir
	24/8	I	1	I	TRISC8 <sup>(3)</sup>	I	RC8 <sup>(3)</sup>	I	LATC8 <sup>(3)</sup>	I	ODCC8(3)	I	CNPUC8 <sup>(3)</sup>	1	CNPDC8 <sup>(3)</sup>	1	1	1	CNIEC8 <sup>(3)</sup>	1	CNSTATC8(3)	${ m x}$ = unknown value on Reset; — = unimplemented, read as '0'. Reset values are shown in hexadecimal
	25/9	1	-	1	TRISC9	1	RC9	1	LATC9	1	ൊവഠ	1	CNPUC9	-	CNPDC9	-	-	-	CNIEC9	_	CNSTATC9	as '0'. Reset va
	26/10	1	1	I	I	I	I	I	I	I	I	I	I	I	1	I	I	I	1	I	1	d, read
	27/11	1	1	I	I	I	I	I	I	I	I	I	I	I	1	Ι	I	I	1	I	1	emente
	28/12	1	I	_	_	_	I	_	I	_	I	_	I	_	_	_	_	_	_	_	1	- unimp
	29/13	1	I	_	_	_	Ι	_	Ι	_	Ι	_	Ι	-	_	1	SIDF	-	_	-	1	set; — :
	30/14	1	I	_	_	_	I	_	1	_	1	_	1	_	-	-	_	_	-	_	1	e on Re
	31/15	I	Ι	I	Ι	I	Ι	I	Ι	I	Ι	I	Ι	١	Ι	I	NO	١	Ι	I	Ι	wn valu
e	gnsA jia	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	unkno
(	Register <sup>C,1)</sup> emsM		ANSELC	Color	2012	OFFICE		CE	2	0	2200		CNFOC		CNPDC			L	CNENC		CNSIAIC	
	nbbA IsuhiV (#_8878)	C	0020	0,70	0770	0000	0220	0000	0520	0	6240	Ĺ	0529	C C	0200		0/79	0	0280		0829	Legend:

All registers in this table have corresponding CLR, SET and INV registers at their virtual addresses, plus offsets of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for more information. Note

<u>ოფ</u>

PORTC is not available on 28-pin devices. This bit is only available on 44-pin devices. This bit is only available on USB-enabled devices with 36 or 44 pins.

PORTC REGISTER MAP

**TABLE 11-5:** 

<b>TABLE 11-6</b> :	: 11-6:	PER	IPHER/	YL PIN	PERIPHERAL PIN SELECT INPU	T INPUT	REGIS	T REGISTER MAP	٩										
sse		,								Bits	S								9
Virtual Addr (#_0878)	Register Mame	Bit Range	31/15	30/14	29/13	28/12	27/11	26/10	25/9	24/8	23/7	22/6	21/5	20/4	19/3	18/2	1//1	16/0	eteseЯ IIA
20		31:16	Ι	_	1	1	1	_	-	-	1	_	1	1	Ι	1	_	1	0000
FA04	Y Z	15:0	I	I	Ι	1	Ι	-	I	I	1	Ι	I	I		INT1R<3:0>	<3:0>		0000
Č		31:16	I	Ι	I	I	Ι	Ι	I	I	I	1	I	I	I	ı	I	I	0000
FAUS	IN I ZK	15:0	Ι	_	Ι	_	Ι	_	Ι	_	-	1	-	-		INT2R<3:0>	<3:0>		0000
C		31:16	1	-	Ι	-	Ι	_	Ι	1	-	Ι	-	1	1	-	-	-	0000
LACC	AS I NI	15:0	1	1	1			1	I	I		Ι	1	1		INT3R<3:0>	<3:0>		0000
ŗ		31:16	I	I	Ι	1	Ι	-	I	I	1	Ι	I	Ι	Ι	I	I	I	0000
LA IO	NI 4K	15:0	-	_	1	_	Ι	_	1	_	_	1	_	-		INT4R<3:0>	<3:0>		0000
ŗ		31:16	I	I	Ι	I	Ι	-	I	I	1	Ι	I	Ι	Ι	I	I	I	0000
1A 10	IZCAR	15:0	1	-	Ι	-	Ι	_	Ι	1	-	Ι	-	-		T2CKR<3:0>	<3:0>		0000
7		31:16	1	-	-	-	Ι	_	Ι	1	-	1	-	1	1	-	-	-	0000
2	ISCAR	15:0	1	-	Ι	-	Ι	_	Ι	1	-	Ι	-	-		T3CKR<3:0>	<3:0>		0000
		31:16	1	-	-	-	Ι	_	1	-	-	1	-	1	1	-	-	-	0000
LAZ0	14CAR	15:0	1	-	Ι	-	Ι	_	Ι	1	-	Ι	-	-		T4CKR<3:0>	<3:0>		0000
70 41		31:16	1	1	Ι			1	I	I		Ι	1	1	1	-	-	1	0000
FA24	ISCAR	15:0	1	1	Ι			1	I	I		Ι	1	1		T5CKR<3:0>	<3:0>		0000
00 41	9,0	31:16	1	1	Ι			1	I	I		-	-	1	1	-	-	1	0000
1A20	ב	15:0	1	1	1	1	1	Τ	1	1	Ι	1	1	1		IC1R<3:0>	3:0>		0000
000	٥٥٥	31:16	1	Ī	I	1	1	Ι	Ī	I	1	Ī	I	1	1	1	1	I	0000
) Y	איטו	15:0	1	Ī	I	Ι	1	Ι	Ī	I	1	Ī	I	1		IC2R<3:0>	3:0>		0000
00		31:16	1	I	I	I	1	1	Ι	I	1	Ι	1	1	1	1	1	1	0000
000	אנט	15:0	1	1	I	1	1	1	I	I	1	Ι	1	1		IC3R<3:0>	3:0>		0000
1 × × ×	970	31:16	1	I	I	Ι	1	1	Ī	I	1	Ī	I	1	1	I	I	I	0000
ţ	5	15:0	Ι	1	I	1	I	1	I	I	1	I	1	1		IC4R<3:0>	3:0>		0000
Č	Ç	31:16	I	I	I	I	I	-	I	I	1	I	1	I	I	1		I	0000
0247	אנטו	15:0	I	I	I	I	I	-	I	I	1	I	1	I		IC5R<3:0>	3:0>		0000
	2 4 10 0	31:16	1	1	1	-	I	_	1	1	1	1	1	1	1	1	1	ı	0000
17440	Z AL	15:0	1	1	I	1	1	1	I	I	1	1	1	1		OCFAR<3:0>	<3:0>		0000
		31:16	1	-	1	-	I	_	1	1	1	1	1	1	1	1	1	ı	0000
7	NGLOO	15:0	1	1	I	1	1	1	I	I	1	1	1	1		OCFBR<3:0>	<3:0>		0000
		31:16	1	I	I	1	1	1	I	I	1	I	1	1	Ι	1	1	1	0000
000	K K K K	15:0	1	I	I	I	I	Ι	I	I	1	I	Ι	I		U1RXR<3:0>	<3:0>		0000

0000 0000 0000 0000 0000 0000 0000 0000 0000 0000 0000 0000 0000 0000 0000 All Resets 9/9 REFCLKIR<3:0> 17/1 — — — SDI2R<3:0> U1CTSR<3:0> U2CTSR<3:0> U2RXR<3:0> SS1R<3:0> 18/2 19/3 20/4 22/6 23/7 PERIPHERAL PIN SELECT INPUT REGISTER MAP (CONTINUED) 25/9 28/12 30/14 31:16 15:0 15:0 15:0 15:0 15:0 15:0 15:0 15:0 Bit Range REFCLKIR **U1CTSR TABLE 11-6**: Register Name SS1R **SDI2R** FAB8 Virtual Address (#\_0878) FA94

TABLE	E 11-7:		PERIPHERAL PIN SELECT OUT	AL PIN	SELEC		PUT REGISTER MAP	SISTER	MAP										
SS										Bits	ø								
Virtual Addre (#_0878)	Register Name	Bit Range	31/15	30/14	29/13	28/12	27/11	26/10	25/9	24/8	23/7	22/6	21/5	20/4	19/3	18/2	1//1	16/0	etsea IIA
000	0	31:16	I	Ι	I	I	I	Ι	I	Ι	Ι	Ι	Ι	I	I	I	I	Ι	0000
0094	Y ACK	15:0	I	1	I	I	1	1	1	1	1	1	I	I		RPA0<3:0>	3:0>		0000
7001	01400	31:16	1	Ι	1	1	-	1	1	1	1	Ι	I	1	1	1	1	1	0000
F B 04	KFAIK	15:0	I	Ι	I	Ι	-	1	1	1	1	Ι	I	1		RPA1<3:0>	3:0>		0000
0000	acvaa	31:16	I	1	I	I	Ι	1	Ι	1	Ι	1	I	I	1	1	I	1	0000
000	אאאא	15:0	I	1	I	I	1	I	1	I	1	I	I	I		RPA2<3:0>	3:0>		0000
0	0	31:16	I	1	I	I	1	1	1	I	1	1	I	I	ı	I	I	I	0000
- PBOC	XFASK X	15:0	I	1	I	I	1	1	1	I	1	1	I	I		RPA3<3:0>	3:0>		0000
0,70	0.400	31:16	I	1	I	I	1	1	1	1	1	1	I	I	1	1	I	I	0000
2 2	744Y	15:0	I	1	I	I	1	1	1	I	1	1	I	I		RPA4<3:0>	3:0>		0000
_	(1)	31:16	I	1	I	I	1	1	1	I	I	1	I	ı	ı	I	I	I	0000
L DZO	LAORY	15:0	I	1	I	I	1	I	1	I	1	I	I	I		RPA8<3:0>	3:0>		0000
_	(1)00000	31:16	I	1	I	I	1	I	1	I	1	I	I	I	1	I	I	I	0000
1 D24	N LANGE	15:0	I	I	I	I	1	I	1	I	I	1	I	I		RPA9<3:0>	3:0>		0000
000		31:16	1	1	1	1	1	1	1	1	1	1	1	Ι	1	1	I	Ι	0000
7070	אַסקאַ	15:0	I	1	I	I	1	I	1	I	1	I	I	I		RPB0<3:0>	:3:0>		0000
000	0,00	31:16	I	1	I	I	I	1	1	1	1	1	I	I	I	I	I	Ι	0000
F B30	אר ה	15:0	I	1	I	I	1	1	1	I	I	1	I	I	Ī	RPB1<3:0>	3:0>		0000
700		31:16	I	1	I	I	1	I	1	I	1	1	I	ı	1	I	I	I	0000
T 20 4	AP DZA	15:0	1	1	1	1	1	1	1	1	1	1	1	Ι		RPB2<3:0>	:3:0>		0000
000	000	31:16	I	1	I	I	1	I	1	I	I	1	I	ı	1	I	I	I	0000
1030	RFBSR	15:0	1	1	1	Ι	1	1	1	1	1	1	1	1		RPB3<3:0>	:3:0>		0000
0600	01000	31:16	I	1	1	1	Ī	1	1	1	I	1	1	1	1	1	1	1	0000
250	71017	15:0	I	Ι	I	Ι	1	1	I	I	1	Ι	I	I		RPB4<3:0>	:3:0>		0000
0,0	0	31:16	I	1	I	I	1	I	1	I	1	I	I	ı	1	I	I	I	0000
7 0 0 1	X702X	15:0	I	1	I	I	1	I	1	I	1	I	I	I		RPB5<3:0>	:3:0>		0000
L D 4.4	0.00000	31:16	1	1	1	Ι	1	1	1	1	1	1	1	1	1	1	1	1	0000
_	NDOLA	15:0	I	I	I	Ι	Ι	1	1	I	1	I	I	I		RPB6<3:0>	:3:0>		0000
FRAR	A7AGA	31:16	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	0000
7 D40	אוסוא	15:0	1	1	1	1	1	1	1	1	1	1	1	1		RPB7<3:0>	:3:0>		0000
Legend:		uwouyur	x = unknown value on Reset; — = unimplemented, read	set; — = u	nimplemen		; '0'. Reset	values are	as '0'. Reset values are shown in hexadecimal	xadecimal.									ļ

This register is only available on 44-pin devices. This register is only available on PIC32MX1XX devices. This register is only available on 36-pin and 44-pin devices. ∺ ფ ფ

0000 0000 0000 0000 0000 0000 0000 0000 0000 9/0 17 RPB14<3:0> RPB15<3:0> RPB11<3:0> RPB13<3:0> RPC1<3:0> RPC2<3:0> RPC7<3:0> RPC0<3:0> RPB8<3:0> RPB9<3:0> 19/3 20/4 22/6 PERIPHERAL PIN SELECT OUTPUT REGISTER MAP (CONTINUED) 23/7 '0'. Reset values are shown in hexadecimal 25/9 26/10 27/11 — = unimplemented, read as 28/12 29/13 30/14 x = unknown value on Reset;31/15 31:16 31:16 31:16 31:16 31:16 31:16 31:16 31:16 31:16 31:16 15:0 15:0 15:0 15:0 15:0 15:0 15:0 15:0 15:0 15:0 15:0 15:0 15:0 Bit Range RPC3R<sup>(3)</sup> RPC0R<sup>(3)</sup> RPC6R<sup>(1)</sup> RPC4R<sup>(1)</sup> RPC7R<sup>(1)</sup> 1R<sup>(3)</sup> RPC2R<sup>(1)</sup> RPB11R 13R 14R RPC5R(1) Register Name RPB1 RPB1 RPB1 RPB1 RPC1 Legend: Note 1: FB4C FB74 Virtual Address (BF80\_#) FB64

© 2011-2019 Microchip Technology Inc.

All Resets

This register is only available on 44-pin devices. This register is only available on PIC32MX1XX devices. This register is only available on 36-pin and 44-pin devices.

11-7:

**TABLE** 

	steseЯ IIA	0000	0000	0000	0000
	16/0	I			
	17/1	I	<3:0>	I	<3:0>
	18/2	I	RPC8<3:0>		RPC9<3:0>
	19/3	I			
	20/4	I	I	I	1
	21/5	I	I	I	-
	22/6	ı			_
Bits	23/7	1	1	1	_
ā	24/8	I	I	I	1
	25/9	I	ı	ı	_
	26/10	-	_	_	_
	27/11	I	_	_	_
	28/12	1	_	_	_
	29/13	I	_	_	_
	30/14	I	I	I	1
	31/15	I	I	I	I
	Bit Range	31:16	15:0	31:16	15:0
	Register Name	(1) 00000	, Yeo Li	(3)	N COLV
SS	Virtual Addre (#_0878)	0	) 0 1		0891

x = unknown value on Reset; — = unimplemented, read as '0'. Reset values are shown in hexadecimal. This register is only available on 44-pin devices. This register is only available on PIC32MX1XX devices. This register is only available on 36-pin and 44-pin devices.

Legend: Note 1: 2: 3:

**TABLE 11-7**:

PERIPHERAL PIN SELECT OUTPUT REGISTER MAP (CONTINUED)

REGISTER 11-1: [pin name]R: PERIPHERAL PIN SELECT INPUT REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.04	U-0                U-0							
31:24	_	_	-	_	_	-		_
00.40	U-0                U-0							
23:16	_	_	_	_	_	_	_	_
45.0	U-0                U-0							
15:8	_	_	_	_	_	_	_	_
7.0	U-0	U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0
7:0	_	_	_	_		[pin name	?]R<3:0>	

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-4 Unimplemented: Read as '0'

bit 3-0 [pin name]R<3:0>: Peripheral Pin Select Input bits

Where [pin name] refers to the pins that are used to configure peripheral input mapping. See Table 11-1 for input pin selection values.

Note: Register values can only be changed if the Configuration bit, IOLOCK (CFGCON<13>), = 0.

REGISTER 11-2: RPnR: PERIPHERAL PIN SELECT OUTPUT REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.04	U-0                U-0							
31:24	_	_	-	_	_		_	_
23:16	U-0                U-0							
23.10	_	_	-	_	_	_	_	_
45.0	U-0                U-0							
15:8	_	_	-	_	_	-		_
7.0	U-0	U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0
7:0	_	_	-	_		RPnR	<3:0>	

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-4 Unimplemented: Read as '0'

bit 3-0 **RPnR<3:0>:** Peripheral Pin Select Output bits See Table 11-2 for output pin selection values.

Note: Register values can only be changed if the Configuration bit, IOLOCK (CFGCON<13>), = 0.

#### REGISTER 11-3: CNCONx: CHANGE NOTICE CONTROL FOR PORTX REGISTER (x = A, B, C)

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.04	U-0                U-0							
31:24	_	_	-	_	_	_	_	
00.40	U-0                U-0							
23:16	_	_	-	_	_	_	_	_
45.0	R/W-0	U-0	R/W-0	U-0	U-0	U-0	U-0	U-0
15:8	ON	_	SIDL	_	_	_	_	_
7.0	U-0                U-0							
7:0	_	_	_	_	_	_	_	

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

ON: Change Notice (CN) Control ON bit bit 15

> 1 = CN is enabled 0 = CN is disabled

bit 14 Unimplemented: Read as '0' bit 13

SIDL: Stop in Idle Control bit

1 = Idle mode halts CN operation 0 = Idle does not affect CN operation

bit 12-0 Unimplemented: Read as '0'

#### 12.0 TIMER1

Note:

This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To complement the information in this data sheet, refer to **Section 14.** "Timers" (DS60001105), which is available from the *Documentation* > *Reference Manual* section of the Microchip PIC32 web site (www.microchip.com/pic32).

This family of PIC32 devices features one synchronous/asynchronous 16-bit timer that can operate as a free-running interval timer for various timing applications and counting external events. This timer can also be used with the Low-Power Secondary Oscillator (SOSC) for Real-Time Clock (RTC) applications.

The following modes are supported:


- · Synchronous Internal Timer
- · Synchronous Internal Gated Timer
- · Synchronous External Timer
- · Asynchronous External Timer

### 12.1 Additional Supported Features

- · Selectable clock prescaler
- Timer operation during CPU Idle and Sleep mode
- Fast bit manipulation using CLR, SET and INV registers
- Asynchronous mode can be used with the Sosc to function as a Real-Time Clock (RTC)

Figure 12-1 illustrates a general block diagram of Timer1.

FIGURE 12-1: TIMER1 BLOCK DIAGRAM



12.2 Timer1 Control Registers
TABLE 12-1: TIMER1 REGISTER MAP

s	All Reset	0000	0000	0000	0000	0000	FFFF
	16/0	I	Ι	Ι		Ι	
	17/1	I	TCS	I		I	
	18/2	I	TSYNC	_		_	
	19/3	1	Ι	-		-	
	20/4	I	TCKPS<1:0>	_		_	
	21/5	I	TCKPS	_		_	
	22/6	I	—	_		_	
Bits	23/7	I	TGATE	_	TMR1<15:0>	_	PR1<15:0>
B	24/8	I	I	Ι	TMR1	Ι	PR1<
	25/9	I	Ι	_		_	
	26/10	I	I	I		I	
	27/11	I	TWIP	I		I	
	28/12	I	TWDIS	I		I	
	29/13	I	SIDL	Ι		Ι	
	30/14	I	I	I		I	
	31/15	I	NO	I		Ι	
€	Bit Range	31:16	15:0	31:16	15:0	31:16	15:0
	Register Name <sup>(1)</sup>	14001		TANDA	<u> </u>	,00	Ľ L
SSƏ	Virtual Addr (#_0878)	0000	0000	0640	2 2	0000	0020

All registers in this table have corresponding CLR, SET and INV registers at their virtual addresses, plus offsets of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" more information.  $_{
m X}$  = unknown value on Reset; — = unimplemented, read as '0'. Reset values are shown in hexadecimal.

#### REGISTER 12-1: T1CON: TYPE A TIMER CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0                U-0							
31.24	-	_	_	_	_	_	_	_
23:16	U-0                U-0							
23.10	-	_	_	_	_	_	_	_
45.0	R/W-0	U-0	R/W-0	R/W-0	R-0	U-0	U-0	U-0
15:8	ON <sup>(1)</sup>	_	SIDL	TWDIS	TWIP	_	_	_
7.0	R/W-0	U-0	R/W-0	R/W-0	U-0	R/W-0	R/W-0	U-0
7:0	TGATE	_	TCKPS	S<1:0>	_	TSYNC	TCS	_

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

bit 15 **ON:** Timer On bit<sup>(1)</sup>

1 = Timer is enabled

0 = Timer is disabled

bit 14 **Unimplemented:** Read as '0'

bit 13 SIDL: Stop in Idle Mode bit

 $\ensuremath{\mathtt{1}}$  = Discontinue module operation when the device enters Idle mode

0 = Continue module operation when the device enters Idle mode

bit 12 TWDIS: Asynchronous Timer Write Disable bit

1 = Writes to Timer1 are ignored until pending write operation completes

0 = Back-to-back writes are enabled (Legacy Asynchronous Timer functionality)

bit 11 TWIP: Asynchronous Timer Write in Progress bit

In Asynchronous Timer mode:

1 = Asynchronous write to the Timer1 register in progress

0 = Asynchronous write to Timer1 register is complete

In Synchronous Timer mode:

This bit is read as '0'.

bit 10-8 Unimplemented: Read as '0'

bit 7 TGATE: Timer Gated Time Accumulation Enable bit

When TCS = 1: This bit is ignored.

When TCS = 0:

1 = Gated time accumulation is enabled

0 = Gated time accumulation is disabled

bit 6 Unimplemented: Read as '0'

bit 5-4 TCKPS<1:0>: Timer Input Clock Prescale Select bits

11 = 1:256 prescale value

10 = 1:64 prescale value

01 = 1:8 prescale value

00 = 1:1 prescale value

**Note 1:** When using 1:1 PBCmLK divisor, the user's software should not read/write the peripheral SFRs in the SYSCLK cycle immediately following the instruction that clears the module's ON bit.

### REGISTER 12-1: T1CON: TYPE A TIMER CONTROL REGISTER (CONTINUED)

bit 3 Unimplemented: Read as '0'

bit 2 TSYNC: Timer External Clock Input Synchronization Selection bit

When TCS = 1:

1 = External clock input is synchronized 0 = External clock input is not synchronized

When TCS = 0: This bit is ignored.

bit 1 TCS: Timer Clock Source Select bit

1 = External clock from TxCKI pin

0 = Internal peripheral clock

bit 0 Unimplemented: Read as '0'

**Note 1:** When using 1:1 PBCmLK divisor, the user's software should not read/write the peripheral SFRs in the SYSCLK cycle immediately following the instruction that clears the module's ON bit.

### 13.0 TIMER2/3, TIMER4/5

Note:

This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To complement the information in this data sheet, refer to **Section 14.** "Timers" (DS60001105), which is available from the *Documentation* > *Reference Manual* section of the Microchip PIC32 web site (www.microchip.com/pic32).

This family of PIC32 devices features four synchronous 16-bit timers (default) that can operate as a freerunning interval timer for various timing applications and counting external events. The following modes are supported:

- · Synchronous internal 16-bit timer
- · Synchronous internal 16-bit gated timer
- · Synchronous external 16-bit timer

Two 32-bit synchronous timers are available by combining Timer2 with Timer3 and Timer4 with Timer5. The 32-bit timers can operate in three modes:

- · Synchronous internal 32-bit timer
- · Synchronous internal 32-bit gated timer
- · Synchronous external 32-bit timer

Note: In this chapter, references to registers, TxCON, TMRx and PRx, use 'x' to represent Timer2 through Timer5 in 16-bit modes. In 32-bit modes, 'x' represents

Timer3 or Timer5.


### 13.1 Additional Supported Features

Timer2 or Timer4 and 'y' represents


- · Selectable clock prescaler
- · Timers operational during CPU idle
- Time base for Input Capture and Output Compare modules (Timer2 and Timer3 only)
- ADC event trigger (Timer3 in 16-bit mode, Timer2/3 in 32-bit mode)
- Fast bit manipulation using CLR, SET and INV registers

Figure 13-1 and Figure 13-2 illustrate block diagrams of Timer2/3 and Timer4/5.

FIGURE 13-1: TIMER2-TIMER5 BLOCK DIAGRAM (16-BIT)



### FIGURE 13-2: TIMER2/3, TIMER4/5 BLOCK DIAGRAM (32-BIT)



- Note 1: In this diagram, the use of 'x' in registers, TxCON, TMRx, PRx and TxCK, refers to either Timer2 or Timer4; the use of 'y' in registers, TyCON, TMRy, PRy, TyIF, refers to either Timer3 or Timer5.
  - 2: ADC event trigger is available only on the Timer2/3 pair.

13.2 Timer Control Registers
TABLE 13-1: TIMER2-TIMER5 REGISTER MAP

	əl	-	         			ı L		<del> </del>	Bits	ts			_	_				sì
요는 마일 등 대한	31/15 30/14 29/13	30/14 29/13		28/1	7	27/11	26/10	25/9	24/8	23/7	22/6	21/5	20/4	19/3	18/2	17/1	16/0	eseЯ IIA
31:16 — — — —	1	1				1	1	1	ı	1	1	1	1	1	1	1	1	0000
15:0 ON — SIDL —	- NO	_ SIDI	- SIDL -	_		I	_	1	1	TGATE	L	TCKPS<2:0>		T32	_	SOL	_	0000
TWB3 31:16 — — — — — —		-		1		I	1	1	1	I	-		1	1	_	1	1	0000
MINZ 15:0	15:0								TMR2<15:0>	<15:0>								0000
31:16 — — — — —		1		_		I	_	1	1	_	_	1	-	_	_	_	_	0000
T NZ 15:0	15:0								PR2<15:0>	15:0>								FFFF
31:16 — — — — — —		1		_		Ι	-	1	1	1	_	1	1	1	_	-	1	0000
15:0 ON — SIDL —	- NO	- SIDL -	SIDL —	_		Ι	-	1	1	TGATE	L	TCKPS<2:0>		1	_	CS	1	0000
TMB3 31:16 — — — — — —	1		1			1	1	1	-	Ι	_	1	1	-	_	1	1	0000
15:0	15:0								TMR3<15:0>	<15:0>								0000
31:16 — — — — —		1		-		1	1	1	-	1	_	1	1	-	_	1	1	0000
15:0	15:0				ı	•			PR3<15:0>	15:0>			•	•		•		FFFF
31:16 — — — — — —	1		1	1		1	1	1	1	I	_	1	1	-	_	1	1	0000
15:0 ON — SIDL —	- NO		SIDL —	I		1	1	1	1	TGATE		TCKPS<2:0>		T32	1	TCS	I	0000
31:16 — — — — — —	1	1		_	_	I	I	1	I	I	_	1	1	1	_	I	1	0000
15:0	15:0				ŀ				TMR4<15:0>	<15:0>			•	•		•		0000
31:16 — — — — — —	 	 		1		I	1	1	1	I	-	1	I	1	1	I	I	0000
15:0	15:0								PR4<15:0>	15:0>								FFFF
31:16 — — — — — —	1		-	I		I	1	I	I	Ī	_	1	_	_	_	I	1	0000
15:0 ON — SIDL —	- NO	-	SIDL —	Ι		I	1	1	ı	TGATE		TCKPS<2:0>		_	_	TCS	1	0000
TMBE 31:16 — — — — — —		1	1	I		I	l		I	I	I	l	I	I	ı	I	I	0000
MINS 15:0	15:0				1				TMR5<15:0>	<15:0>								0000
BBE 31:16 — — — — — —	·		1	_		Ι	-	1	1	Ι	_	1	1	1	_	_	-	0000
15:0	15:0								PR5<15:0>	15:0>								FFFF
	bota conclusiontocol	been between =tood as or	bota omolamia.		ľ	Č	Lowisoboyod at attorde ere soules, topolo '0' a	di di codo o	hovedooin	100								

**Legend:** x = unknown value on Reset; — = unimplemented, read as '0'. Reset values are shown in hexadecimal.

Note 1: All registers in this table have corresponding CLR, SET and INV registers at their virtual addresses, plus offsets o

All registers in this table have corresponding CLR, SET and INV registers at their virtual addresses, plus offsets of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for more information.

#### REGISTER 13-1: TXCON: TYPE B TIMER CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31.24	_	_	_	_	_	-	_	_
22,16	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23:16	_	_	_	_	_	_	_	_
45.0	R/W-0	U-0	R/W-0	U-0	U-0	U-0	U-0	U-0
15:8	ON <sup>(1,3)</sup>	_	SIDL <sup>(4)</sup>	_	_	_	_	_
7.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	U-0	R/W-0	U-0
7:0	TGATE <sup>(3)</sup>	Т	CKPS<2:0>(	3)	T32 <sup>(2)</sup>	_	TCS <sup>(3)</sup>	_

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

bit 15 **ON:** Timer On bit $^{(1,3)}$ 

1 = Module is enabled

0 = Module is disabled

bit 14 Unimplemented: Read as '0'

bit 13 SIDL: Stop in Idle Mode bit<sup>(4)</sup>

1 = Discontinue module operation when the device enters Idle mode

0 = Continue module operation when the device enters Idle mode

bit 12-8 Unimplemented: Read as '0'

bit 7 **TGATE**: Timer Gated Time Accumulation Enable bit<sup>(3)</sup>

When TCS = 1:

This bit is ignored and is read as '0'.

When TCS = 0:

1 = Gated time accumulation is enabled

0 = Gated time accumulation is disabled

bit 6-4 TCKPS<2:0>: Timer Input Clock Prescale Select bits<sup>(3)</sup>

111 = 1:256 prescale value

110 = 1:64 prescale value

101 = 1:32 prescale value

100 = 1:16 prescale value

011 = 1:8 prescale value

010 = 1:4 prescale value

001 = 1:2 prescale value

000 = 1:1 prescale value

- **Note 1:** When using 1:1 PBCLK divisor, the user's software should not read/write the peripheral SFRs in the SYSCLK cycle immediately following the instruction that clears the module's ON bit.
  - 2: This bit is available only on even numbered timers (Timer2 and Timer4).
  - **3:** While operating in 32-bit mode, this bit has no effect for odd numbered timers (Timer3, and Timer5). All timer functions are set through the even numbered timers.
  - **4:** While operating in 32-bit mode, this bit must be cleared on odd numbered timers to enable the 32-bit timer in Idle mode.

### REGISTER 13-1: TXCON: TYPE B TIMER CONTROL REGISTER (CONTINUED)

- bit 3 T32: 32-Bit Timer Mode Select bit<sup>(2)</sup>
  - 1 = Odd numbered and even numbered timers form a 32-bit timer
  - 0 = Odd numbered and even numbered timers form a separate 16-bit timer
- bit 2 Unimplemented: Read as '0'
- bit 1 TCS: Timer Clock Source Select bit<sup>(3)</sup>
  - 1 = External clock from TxCK pin
  - 0 = Internal peripheral clock
- bit 0 **Unimplemented:** Read as '0'
- **Note 1:** When using 1:1 PBCLK divisor, the user's software should not read/write the peripheral SFRs in the SYSCLK cycle immediately following the instruction that clears the module's ON bit.
  - 2: This bit is available only on even numbered timers (Timer2 and Timer4).
  - **3:** While operating in 32-bit mode, this bit has no effect for odd numbered timers (Timer3, and Timer5). All timer functions are set through the even numbered timers.
  - **4:** While operating in 32-bit mode, this bit must be cleared on odd numbered timers to enable the 32-bit timer in Idle mode.

NOTES:			

Power-up timer.

### 14.0 WATCHDOG TIMER (WDT)

Note: This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To

(www.microchip.com/pic32).


complement the information in this data sheet, refer to Section 9. "Watchdog, Deadman, and Power-up Timers" (DS60001114), which are available from the *Documentation* > Reference Manual section of the Microchip PIC32 web site

The WDT, when enabled, operates from the internal Low-Power Oscillator (LPRC) clock source and can be used to detect system software malfunctions by resetting the device if the WDT is not cleared periodically in software. Various WDT time-out periods can be selected using the WDT postscaler. The WDT can also be used to wake the device from Sleep or Idle mode.

The following are some of the key features of the WDT module:

- · Configuration or software controlled
- · User-configurable time-out period
- Can wake the device from Sleep or Idle mode Figure 14-1 illustrates a block diagram of the WDT and

FIGURE 14-1: WATCHDOG TIMER AND POWER-UP TIMER BLOCK DIAGRAM



14.1 Watchdog Timer Control Registers
TABLE 14-1: WATCHDOG TIMER CONTROL REGISTER MAP

	,,,,,,,	00	00
	16/0	I	WDTCLR
	17/1	Ι	WDTWINEN WDTCLR 00
	18/2	Ι	
	19/3	I	^(
	20/4	I	SWDTPS<4:0>
	21/5	Ι	S
	22/6	-	
Bits	23/7	I	I
	24/8	I	_
	25/9	Ι	-
	26/10 25/9	I	1
	27/11	I	I
	28/12	I	_
	29/13	I	1
	30/14	I	I
	31/15		NO
€	Bit Range	31:16	15:0
	Register Name <sup>(1)</sup>	IACOTON.	200
ssə	virtual Addr (#_0878)	000	0000

0000

steseЯ IIA

All registers in this table have corresponding CLR, SET and INV registers at their virtual addresses, plus offsets of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for more information. x = unknown value on Reset; — = unimplemented, read as '0'. Reset values are shown in hexadecimal. Legend: Note 1:

DS60001168L-page 158

#### REGISTER 14-1: WDTCON: WATCHDOG TIMER CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31:24		-	-	_	_	_	_	_
00.40	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23:16	_	_	_	_	_	_	_	_
45.0	R/W-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
15:8	ON <sup>(1,2)</sup>	_	_	_	_	_	_	_
7.0	U-0	R-y	R-y	R-y	R-y	R-y	R/W-0	R/W-0
7:0	_		S	WDTPS<4:0	>		WDTWINEN	WDTCLR

Legend:y = Values set from Configuration bits on PORR = Readable bitW = Writable bitU = Unimplemented bit, read as '0'-n = Value at POR'1' = Bit is set'0' = Bit is clearedx = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

bit 15 **ON:** Watchdog Timer Enable bit<sup>(1,2)</sup>

1 = Enables the WDT if it is not enabled by the device configuration

0 = Disable the WDT if it was enabled in software

bit 14-7 Unimplemented: Read as '0'

bit 6-2 **SWDTPS<4:0>:** Shadow Copy of Watchdog Timer Postscaler Value from Device Configuration bits On reset, these bits are set to the values of the WDTPS <4:0> of Configuration bits.

bit 1 WDTWINEN: Watchdog Timer Window Enable bit

1 = Enable windowed Watchdog Timer0 = Disable windowed Watchdog Timer

bit 0 WDTCLR: Watchdog Timer Reset bit

1 = Writing a '1' will clear the WDT

0 = Software cannot force this bit to a '0'

Note 1: A read of this bit results in a '1' if the Watchdog Timer is enabled by the device configuration or software.

2: When using the 1:1 PBCLK divisor, the user's software should not read or write the peripheral's SFRs in the SYSCLK cycle immediately following the instruction that clears the module's ON bit.

NOTES:		

### 15.0 INPUT CAPTURE

Note:

This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To complement the information in this data sheet, refer to **Section 15. "Input Capture"** (DS60001122), which is available from the *Documentation* > *Reference Manual* section of the Microchip PIC32 web site (www.microchip.com/pic32).

The Input Capture module is useful in applications requiring frequency (period) and pulse measurement.

The Input Capture module captures the 16-bit or 32-bit value of the selected Time Base registers when an event occurs at the ICx pin. The following events cause capture events:

- · Simple capture event modes:
  - Capture timer value on every rising and falling edge of input at ICx pin
  - Capture timer value on every edge (rising and falling)
  - Capture timer value on every edge (rising and falling), specified edge first.

- · Prescaler capture event modes:
  - Capture timer value on every 4th rising edge of input at ICx pin
  - Capture timer value on every 16th rising edge of input at ICx pin


Each input capture channel can select between one of two 16-bit timers (Timer2 or Timer3) for the time base, or two 16-bit timers (Timer2 and Timer3) together to form a 32-bit timer. The selected timer can use either an internal or external clock.

Other operational features include:

- Device wake-up from capture pin during Sleep and Idle modes
- · Interrupt on input capture event
- 4-word FIFO buffer for capture values (interrupt optionally generated after 1, 2, 3, or 4 buffer locations are filled)
- Input capture can also be used to provide additional sources of external interrupts

Figure 15-1 illustrates a general block diagram of the Input Capture module.

#### FIGURE 15-1: INPUT CAPTURE BLOCK DIAGRAM



15.1 Input Capture Control Registers
TABLE 15-1: INPUT CAPTURE 1-INPUT CAPTURE 5 REGISTER MAP

ę	18/2 17/1 16/0 Resets	00000	ICM<2:0> 0000	XXXXX	00000	ICM<2:0> 0000	XXXXX	00000	ICM<2:0> 0000	XXXX	00000	ICM<2:0> 0000	XXXXX			ICM<2:0>	ICM<2:0>
	19/3	ı	ICBNE		I	ICBNE		I	ICBNE		I	ICBNE		1		ICBNE	ICBNE
	20/4	I	ICOV		I	ICOV		I	ICOV		I	ICOV				ICOV	ICOV
	21/5	I	ICI<1:0>		1	ICI<1:0>		1	ICI<1:0>		I	ICI<1:0>		1		ICI<1:0>	>1<1:0>
	22/6	1			1			1			1			1			
Bits	23/7	1	ICTMR	IC1BUF<31:0>	1	ICTMR	IC2BUF<31:0>	1	ICTMR	IC3BUF<31:0>	1	ICTMR	IC4BUF<31:0>	1		ICTMR	C32 ICTMR
_	24/8	1	E C32	IC1BL	1	E C32	IC2BL	1	E C32	IC3BL	1	E C32	IC4BL	1		E C32	
	25/9	1	FEDGE		1	FEDGE		1	FEDGE		I	FEDGE		1		FEDGE	FEDGE
	26/10	1	-		1	I		1	I		I	I		1		ı	I
	27/11	1	1		1	1		1	1		-	-		1		I	I
	28/12	1	I		I	Ι		1	Ι		I	I		1		1	I
	29/13	1	SIDL		1	SIDL		1	SIDL		1	SIDL		1		SIDL	SIDL
	30/14	1	1		1	1		1	1		Ι	Ι		I		1	I
	31/15	I	NO		I	NO		I	NO		I	NO		1		NO	
•	Bit Range	31:16	15:0	31:16	31:16	15:0	31:16		15:0	31:16	31:16	15:0	31:16	31:16		15:0	, 15:0 31:16
	Register Name	,)1400701		IC1BUF	(1)		ICZBUF	(1)(4)(1)		IC3BUF	(1)(400)(1)			31:16			
SSƏ	Virtual Addr (#_0878)	000	7000	2010		7700	2210	9	2400	2410	000	2000	2610	000		2007	2810

This register has corresponding CLR, SET and INV registers at its virtual address, plus an offset of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for more information. ÷

#### REGISTER 15-1: ICXCON: INPUT CAPTURE 'x' CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0                U-0							
31.24	_	_	_	_	_	-	-	
00:40	U-0                U-0							
23:16	_	_	_	_	_	_	_	_
45.0	R/W-0	U-0	R/W-0	U-0	U-0	U-0	R/W-0	R/W-0
15:8	ON <sup>(1)</sup>	_	SIDL	_	_	_	FEDGE	C32
7.0	R/W-0	R/W-0	R/W-0	R-0	R-0	R/W-0	R/W-0	R/W-0
7:0	ICTMR	ICI<	1:0>	ICOV	ICBNE		ICM<2:0>	

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit

-n = Bit Value at POR: ('0', '1', x = unknown) P = Programmable bit r = Reserved bit

bit 31-16 Unimplemented: Read as '0'

bit 15 **ON:** Input Capture Module Enable bit<sup>(1)</sup>

1 = Module is enabled

0 = Disable and reset module, disable clocks, disable interrupt generation and allow SFR modifications

bit 14 **Unimplemented:** Read as '0'

bit 13 SIDL: Stop in Idle Control bit

1 = Halt in Idle mode

0 = Continue to operate in Idle mode

bit 12-10 Unimplemented: Read as '0'

bit 9 **FEDGE:** First Capture Edge Select bit (only used in mode 6, ICM<2:0> = 110)

1 = Capture rising edge first0 = Capture falling edge first

bit 8 C32: 32-bit Capture Select bit

1 = 32-bit timer resource capture 0 = 16-bit timer resource capture

bit 7 ICTMR: Timer Select bit (Does not affect timer selection when C32 (ICxCON<8>) is '1')

0 = Timer3 is the counter source for capture1 = Timer2 is the counter source for capture

bit 6-5 ICI<1:0>: Interrupt Control bits

11 = Interrupt on every fourth capture event
 10 = Interrupt on every third capture event
 01 = Interrupt on every second capture event

00 = Interrupt on every capture event

bit 4 ICOV: Input Capture Overflow Status Flag bit (read-only)

1 = Input capture overflow has occurred0 = No input capture overflow has occurred

bit 3 ICBNE: Input Capture Buffer Not Empty Status bit (read-only)

1 = Input capture buffer is not empty; at least one more capture value can be read

0 = Input capture buffer is empty

**Note 1:** When using 1:1 PBCLK divisor, the user's software should not read/write the peripheral's SFRs in the SYSCLK cycle immediately following the instruction that clears the module's ON bit.

### REGISTER 15-1: ICXCON: INPUT CAPTURE 'x' CONTROL REGISTER (CONTINUED)

bit 2-0 ICM<2:0>: Input Capture Mode Select bits

- 111 = Interrupt-Only mode (only supported while in Sleep mode or Idle mode)
- 110 = Simple Capture Event mode every edge, specified edge first and every edge thereafter
- 101 = Prescaled Capture Event mode every sixteenth rising edge
- 100 = Prescaled Capture Event mode every fourth rising edge
- 011 = Simple Capture Event mode every rising edge
- 010 = Simple Capture Event mode every falling edge
- 001 = Edge Detect mode every edge (rising and falling)
- 000 = Input Capture module is disabled

**Note 1:** When using 1:1 PBCLK divisor, the user's software should not read/write the peripheral's SFRs in the SYSCLK cycle immediately following the instruction that clears the module's ON bit.

### 16.0 OUTPUT COMPARE

Note:


This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To complement the information in this data sheet, refer to **Section 16. "Output Compare"** (DS60001111), which is available from the *Documentation* > *Reference Manual* section of the Microchip PIC32 web site (www.microchip.com/pic32).

The Output Compare module is used to generate a single pulse or a train of pulses in response to selected time base events. For all modes of operation, the Output Compare module compares the values stored in the OCxR and/or the OCxRS registers to the value in the selected timer. When a match occurs, the Output Compare module generates an event based on the selected mode of operation.

The following are some of the key features:

- · Multiple Output Compare Modules in a device
- Programmable interrupt generation on compare event
- · Single and Dual Compare modes
- · Single and continuous output pulse generation
- · Pulse-Width Modulation (PWM) mode
- Hardware-based PWM Fault detection and automatic output disable
- Can operate from either of two available 16-bit time bases or a single 32-bit time base

#### FIGURE 16-1: OUTPUT COMPARE MODULE BLOCK DIAGRAM



- **Note 1:** Where 'x' is shown, reference is made to the registers associated with the respective output compare channels, 1 through 5.
  - 2: The OCFA pin controls the OC1-OC4 channels. The OCFB pin controls the OC5 channel.

16.1 Output Compare Control Registers

TABLE 16-1: OUTPUT COMPARE 1-OUTPUT COMPARE 5 REGISTER MAP

<u></u>	ן היי	:			-														
SSƏ		(								Bits	ts								9
Virtual Addro (#_0878)	Register Name <sup>(1)</sup>	Bit Range	31/15	30/14	29/13	28/12	27/11	26/10	25/9	24/8	23/7	22/6	21/5	20/4	19/3	18/2	1//1	16/0	eteseЯ IIA
0000		31:16	1	1	1	1	I	1	1	I	1	I	1	1	1	1	I	1	0000
3000	OCICON	15:0	NO	1	SIDL	Ι	1	-	1	-	-	_	OC32	OCFLT	OCTSEL		OCM<2:0>		0000
3010	OC1R	31:16 15:0								OC1R<31:0>	<31:0>							•	XXXXX XXXXX
3020	OC1RS	31:16								OC1RS<31:0>	<31:0>							•	XXX
0000		31:16	I	-	I	I	1	I	1	I	1	I	I	I	I	1	I	1	0000
3200		15:0	NO	I	SIDL	1	1	1	1	1	1	1	OC32	OCFLT	OCTSEL		OCM<2:0>		0000
3210	OC2R	31:16								OC2R<31:0>	<31:0>							•	XXXXX XXXXX
3220	OC2RS	31:16								OC2RS<31:0>	<31:0>								XX XX
00.00		31:16	Ι	Ι	I	I	I	Ι	Ι	I	Ι	I	I	Ι	I	I	I	ı	0000
3400	2020	15:0	NO	I	SIDL	I	Ι	Ι	Ι	I	Ι	I	OC32	OCFLT	OCTSEL		OCM<2:0>		0000
3410	OC3R	31:16								OC3R<31:0>	<31:0>							•	XXXXX
3420	OC3RS	31:16								OC3RS	OC3RS<31:0>							1	XXXX XX
3600	7000	31:16	1	I	1	Ι	1	1	Ι	-	_	Ι	1	1	1	-	I	1	0000
2000		15:0	NO	I	SIDL	1	1	1	1	1	1	I	OC32	OCFLT	OCTSEL		OCM<2:0>		0000
3610	OC4R	31:16 15:0								OC4R<31:0>	<31:0>								XXXX XXXX
3620	OC4RS	31:16								OC4RS<31:0>	<31:0>							1	XXXX X
0000		31:16	I	1	I	I	I	I	I	I	1	I	I	1	I	I	I	I	0000
2000		15:0	NO	-	SIDL	Ι		-	-	1	-	Ι	OC32	OCFLT	OCTSEL	)	OCM<2:0>		0000
3810	OC5R	31:16								OC5R<31:0>	<31:0>							•	XXXXX
3820	OC5RS	31:16								OC5RS<31:0>	<31:0>							•	XXXX
1000	į	- Jak	ac cilor are	1 -+000	- Indianalamian	, poor potac	CO.1000 + CO.00		d di di di do da	o wice bearing									1

All registers in this table have corresponding CLR, SET and INV registers at their virtual addresses, plus offsets of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for more information.  ${\bf x}$  = unknown value on Reset; — = unimplemented, read as '0'. Reset values are shown in hexadecimal.

### REGISTER 16-1: OCXCON: OUTPUT COMPARE 'x' CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0			
24.04	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0			
31:24	-	_	_	_	_	_	-	-			
00.40	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0			
23:16		_	_	_	_	-	_	_			
45.0	R/W-0	U-0	R/W-0	U-0	U-0	U-0	U-0	U-0			
15:8	15:8 ON <sup>(1)</sup>		SIDL	_	_	_	_	_			
7.0	U-0	U-0	R/W-0	R-0	R/W-0	R/W-0	R/W-0	R/W-0			
7:0			OC32	OCFLT <sup>(2)</sup>	OCTSEL	OCM<2:0>					

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

bit 15 **ON:** Output Compare Peripheral On bit<sup>(1)</sup>

1 = Output Compare peripheral is enabled

0 = Output Compare peripheral is disabled

bit 14 Unimplemented: Read as '0'

bit 13 SIDL: Stop in Idle Mode bit

1 = Discontinue module operation when the device enters Idle mode

0 = Continue module operation when the device enters Idle mode

bit 12-6 Unimplemented: Read as '0'

bit 5 OC32: 32-bit Compare Mode bit

1 = OCxR<31:0> and/or OCxRS<31:0> are used for comparisons to the 32-bit timer source

0 = OCxR<15:0> and OCxRS<15:0> are used for comparisons to the 16-bit timer source

bit 4 OCFLT: PWM Fault Condition Status bit(2)

1 = PWM Fault condition has occurred (cleared in hardware only)

0 = No PWM Fault condition has occurred

bit 3 OCTSEL: Output Compare Timer Select bit

1 = Timer3 is the clock source for this Output Compare module

0 = Timer2 is the clock source for this Output Compare module

bit 2-0 OCM<2:0>: Output Compare Mode Select bits

111 = PWM mode on OCx; Fault pin enabled

110 = PWM mode on OCx; Fault pin disabled

101 = Initialize OCx pin low; generate continuous output pulses on OCx pin

100 = Initialize OCx pin low; generate single output pulse on OCx pin

011 = Compare event toggles OCx pin

010 = Initialize OCx pin high; compare event forces OCx pin low

001 = Initialize OCx pin low; compare event forces OCx pin high

000 = Output compare peripheral is disabled but continues to draw current

**Note 1:** When using 1:1 PBCLK divisor, the user's software should not read/write the peripheral's SFRs in the SYSCLK cycle immediately following the instruction that clears the module's ON bit.

2: This bit is only used when OCM<2:0> = '111'. It is read as '0' in all other modes.

NOTES:		

# 17.0 SERIAL PERIPHERAL INTERFACE (SPI)

Note: This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To complement the information in this data sheet, refer to Section 23. "Serial Peripheral Interface (SPI)" (DS60001106), which is available from the Documentation > Reference Manual section of the Microchip PIC32 web site


The SPI module is a synchronous serial interface that is useful for communicating with external peripherals and other microcontrollers. These peripheral devices may be Serial EEPROMs, Shift registers, display drivers, Analog-to-Digital Converters (ADC), etc. The PIC32 SPI module is compatible with Motorola® SPI and SIOP interfaces.

(www.microchip.com/pic32).

Some of the key features of the SPI module are:

- · Master mode and Slave mode support
- Four clock formats
- · Enhanced Framed SPI protocol support
- User-configurable 8-bit, 16-bit and 32-bit data width
- Separate SPI FIFO buffers for receive and transmit
  - FIFO buffers act as 4/8/16-level deep FIFOs based on 32/16/8-bit data width
- Programmable interrupt event on every 8-bit, 16-bit and 32-bit data transfer
- · Operation during Sleep and Idle modes
- Audio Codec Support:
  - I<sup>2</sup>S protocol
  - Left-justified
  - Right-justified
  - PCM

FIGURE 17-1: SPI MODULE BLOCK DIAGRAM



SPI1 AND SPI2 REGISTER MAP **SPI Control Registers** TABLE 17-1:

All registers in this table except SPIxBUF have corresponding CLR, SET and INV registers at their virtual addresses, plus offsets of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for more information. Legend: Note 1:

#### REGISTER 17-1: SPIXCON: SPI CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0		
24.24	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0		
31:24	FRMEN	FRMSYNC	FRMPOL	MSSEN	FRMSYPW	F	RMCNT<2:0	)>		
00.40	R/W-0	U-0	U-0	U-0	U-0	U-0	R/W-0	R/W-0		
23:16	MCLKSEL <sup>(2)</sup>	_	_	_	_	_	SPIFE	ENHBUF <sup>(2)</sup>		
45.0	R/W-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0		
15:8	ON <sup>(1)</sup>	_	SIDL	DISSDO	MODE32	MODE16	SMP	CKE <sup>(3)</sup>		
7.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0		
7:0	SSEN	CKP <sup>(4)</sup>	MSTEN	DISSDI	STXISE	L<1:0>	SRXISEL<1:0>			

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31 FRMEN: Framed SPI Support bit

1 = Framed SPI support is enabled (SSx pin used as FSYNC input/output)

0 = Framed SPI support is disabled

bit 30 FRMSYNC: Frame Sync Pulse Direction Control on SSx pin bit (Framed SPI mode only)

1 = Frame sync pulse input (Slave mode)

0 = Frame sync pulse output (Master mode)

bit 29 FRMPOL: Frame Sync / Slave Select Polarity bit (Framed SPI or Master Transmit modes only)

1 = Frame pulse or SSx pin is active-high

0 = Frame pulse or SSx pin is active-low

bit 28 MSSEN: Master Mode Slave Select Enable bit

1 = Slave select SPI support enabled. The SS pin is automatically driven during transmission in Master mode. Polarity is determined by the FRMPOL bit.

0 = Slave select SPI support is disabled.

bit 27 FRMSYPW: Frame Sync Pulse Width bit

1 = Frame sync pulse is one character wide

0 = Frame sync pulse is one clock wide

bit 26-24 **FRMCNT<2:0>:** Frame Sync Pulse Counter bits. Controls the number of data characters transmitted per pulse. This bit is only valid in FRAMED SYNC mode.

111 = Reserved; do not use

110 = Reserved; do not use

101 = Generate a frame sync pulse on every 32 data characters

100 = Generate a frame sync pulse on every 16 data characters

011 = Generate a frame sync pulse on every 8 data characters

010 = Generate a frame sync pulse on every 4 data characters

001 = Generate a frame sync pulse on every 2 data characters

000 = Generate a frame sync pulse on every data character

bit 23 MCLKSEL: Master Clock Enable bit<sup>(2)</sup>

1 = REFCLK is used by the Baud Rate Generator

0 = PBCLK is used by the Baud Rate Generator

bit 22-18 Unimplemented: Read as '0'

**Note 1:** When using the 1:1 PBCLK divisor, the user's software should not read or write the peripheral's SFRs in the SYSCLK cycle immediately following the instruction that clears the module's ON bit.

2: This bit can only be written when the ON bit = 0.

3: This bit is not used in the Framed SPI mode. The user should program this bit to '0' for the Framed SPI mode (FRMEN = 1).

**4:** When AUDEN = 1, the SPI module functions as if the CKP bit is equal to '1', regardless of the actual value of CKP.

### REGISTER 17-1: SPIXCON: SPI CONTROL REGISTER (CONTINUED)

- bit 17 SPIFE: Frame Sync Pulse Edge Select bit (Framed SPI mode only)
  - 1 = Frame synchronization pulse coincides with the first bit clock
  - 0 = Frame synchronization pulse precedes the first bit clock
- bit 16 **ENHBUF**: Enhanced Buffer Enable bit<sup>(2)</sup>
  - 1 = Enhanced Buffer mode is enabled
  - 0 = Enhanced Buffer mode is disabled
- bit 15 **ON:** SPI Peripheral On bit<sup>(1)</sup>
  - 1 = SPI Peripheral is enabled
  - 0 = SPI Peripheral is disabled
- bit 14 Unimplemented: Read as '0'
- bit 13 SIDL: Stop in Idle Mode bit
  - 1 = Discontinue module operation when the device enters Idle mode
  - 0 = Continue module operation when the device enters Idle mode
- bit 12 DISSDO: Disable SDOx pin bit
  - 1 = SDOx pin is not used by the module. Pin is controlled by associated PORT register
  - 0 = SDOx pin is controlled by the module
- bit 11-10 MODE<32,16>: 32/16-Bit Communication Select bits

### When AUDEN = 1:

MODE32	MODE16	Communication
1	1	24-bit Data, 32-bit FIFO, 32-bit Channel/64-bit Frame
1	0	32-bit Data, 32-bit FIFO, 32-bit Channel/64-bit Frame
0	1	16-bit Data, 16-bit FIFO, 32-bit Channel/64-bit Frame
0	0	16-bit Data, 16-bit FIFO, 16-bit Channel/32-bit Frame

#### When AUDEN = 0:

MODE32	MODE16	Communication
1	x	32-bit
0	1	16-bit
0	0	8-bit

### bit 9 SMP: SPI Data Input Sample Phase bit

### Master mode (MSTEN = 1):

- 1 = Input data sampled at end of data output time
- 0 = Input data sampled at middle of data output time

#### Slave mode (MSTEN = 0):

SMP value is ignored when SPI is used in Slave mode. The module always uses SMP = 0.

To write a '1' to this bit, the MSTEN value = 1 must first be written.

- bit 8 CKE: SPI Clock Edge Select bit<sup>(3)</sup>
  - 1 = Serial output data changes on transition from active clock state to Idle clock state (see the CKP bit)
  - 0 = Serial output data changes on transition from Idle clock state to active clock state (see the CKP bit)
- bit 7 SSEN: Slave Select Enable (Slave mode) bit
  - $1 = \overline{SSx}$  pin used for Slave mode
  - $0 = \overline{SSx}$  pin not used for Slave mode, pin controlled by port function.
- bit 6 **CKP:** Clock Polarity Select bit<sup>(4)</sup>
  - 1 = Idle state for clock is a high level; active state is a low level
  - 0 = Idle state for clock is a low level; active state is a high level
- Note 1: When using the 1:1 PBCLK divisor, the user's software should not read or write the peripheral's SFRs in the SYSCLK cycle immediately following the instruction that clears the module's ON bit.
  - 2: This bit can only be written when the ON bit = 0.
  - 3: This bit is not used in the Framed SPI mode. The user should program this bit to '0' for the Framed SPI mode (FRMEN = 1).
  - **4:** When AUDEN = 1, the SPI module functions as if the CKP bit is equal to '1', regardless of the actual value of CKP.

#### REGISTER 17-1: SPIXCON: SPI CONTROL REGISTER (CONTINUED)

- bit 5 MSTEN: Master Mode Enable bit
  - 1 = Master mode
  - 0 = Slave mode
- bit 4 DISSDI: Disable SDI bit
  - 1 = SDI pin is not used by the SPI module (pin is controlled by PORT function)
  - 0 = SDI pin is controlled by the SPI module
- bit 3-2 STXISEL<1:0>: SPI Transmit Buffer Empty Interrupt Mode bits
  - 11 = Interrupt is generated when the buffer is not full (has one or more empty elements)
  - 10 = Interrupt is generated when the buffer is empty by one-half or more
  - 01 = Interrupt is generated when the buffer is completely empty
  - 00 = Interrupt is generated when the last transfer is shifted out of SPISR and transmit operations are complete
- bit 1-0 SRXISEL<1:0>: SPI Receive Buffer Full Interrupt Mode bits
  - 11 = Interrupt is generated when the buffer is full
  - 10 = Interrupt is generated when the buffer is full by one-half or more
  - 01 = Interrupt is generated when the buffer is not empty
  - 00 = Interrupt is generated when the last word in the receive buffer is read (i.e., buffer is empty)
- **Note 1:** When using the 1:1 PBCLK divisor, the user's software should not read or write the peripheral's SFRs in the SYSCLK cycle immediately following the instruction that clears the module's ON bit.
  - 2: This bit can only be written when the ON bit = 0.
  - 3: This bit is not used in the Framed SPI mode. The user should program this bit to '0' for the Framed SPI mode (FRMEN = 1).
  - **4:** When AUDEN = 1, the SPI module functions as if the CKP bit is equal to '1', regardless of the actual value of CKP.

#### REGISTER 17-2: SPIxCON2: SPI CONTROL REGISTER 2

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31.24	_		_	_		_	_	_
23:16	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23.10	_		_	_	_	_	_	-
15:8	R/W-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
15.6	SPISGNEXT		_	FRMERREN	SPIROVEN	SPITUREN	IGNROV	IGNTUR
7.0	R/W-0	U-0	U-0	U-0	R/W-0	U-0	R/W-0	R/W-0
7:0	AUDEN <sup>(1)</sup>	_	_	_	AUDMONO <sup>(1,2)</sup>	_	AUDMOD	<1:0> <sup>(1,2)</sup>

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

bit 15 SPISGNEXT: Sign Extend Read Data from the RX FIFO bit

1 = Data from RX FIFO is sign extended

0 = Data from RX FIFO is not sign extended

bit 14-13 Unimplemented: Read as '0'

bit 12 FRMERREN: Enable Interrupt Events via FRMERR bit

1 = Frame Error overflow generates error events

0 = Frame Error does not generate error events

bit 11 SPIROVEN: Enable Interrupt Events via SPIROV bit

1 = Receive overflow generates error events

0 = Receive overflow does not generate error events

bit 10 **SPITUREN:** Enable Interrupt Events via SPITUR bit

1 = Transmit underrun generates error events

0 = Transmit underrun does not generate error events

bit 9 IGNROV: Ignore Receive Overflow bit (for Audio Data Transmissions)

1 = A ROV is not a critical error; during ROV data in the FIFO is not overwritten by receive data

0 = A ROV is a critical error that stops SPI operation

bit 8 IGNTUR: Ignore Transmit Underrun bit (for Audio Data Transmissions)

1 = A TUR is not a critical error and zeros are transmitted until the SPIxTXB is not empty

0 = A TUR is a critical error that stops SPI operation

bit 7 AUDEN: Enable Audio CODEC Support bit(1)

1 = Audio protocol enabled

0 = Audio protocol disabled

bit 6-5 Unimplemented: Read as '0'

bit 3 **AUDMONO:** Transmit Audio Data Format bit<sup>(1,2)</sup>

1 = Audio data is mono (Each data word is transmitted on both left and right channels)

0 = Audio data is stereo

bit 2 Unimplemented: Read as '0'

bit 1-0 AUDMOD<1:0>: Audio Protocol Mode bit<sup>(1,2)</sup>

11 = PCM/DSP mode

10 = Right-Justified mode

01 = Left-Justified mode

 $00 = I^2S \text{ mode}$ 

**Note 1:** This bit can only be written when the ON bit = 0.

2: This bit is only valid for AUDEN = 1.

#### **REGISTER 17-3:** SPIXSTAT: SPI STATUS REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0				
24.24	U-0	U-0	U-0	R-0	R-0 R-0 R-0 R-0							
31:24		-	_	RXBUFELM<4:0>								
00.40	U-0 U-0		U-0	R-0	R-0							
23:16		-	_	TXBUFELM<4:0>								
45.0	U-0	U-0	U-0	R/C-0, HS	R-0	U-0	U-0	R-0				
15:8		-	_	FRMERR	SPIBUSY	_	_	SPITUR				
7.0	R-0	R/W-0	R-0	U-0	R-1	U-0	R-0	R-0				
7:0	SRMT	SPIROV	SPIRBE	ı	SPITBE	1	SPITBF	SPIRBF				

Legend:	C = Clearable bit	HS = Set in hardware						
R = Readable bit	W = Writable bit	U = Unimplemented bit, r	ead as '0'					
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown					

bit 31-29 Unimplemented: Read as '0'

bit 28-24 **RXBUFELM<4:0>:** Receive Buffer Element Count bits (valid only when ENHBUF = 1)

bit 23-21 Unimplemented: Read as '0'

bit 20-16 **TXBUFELM<4:0>:** Transmit Buffer Element Count bits (valid only when ENHBUF = 1)

bit 15-13 Unimplemented: Read as '0'

bit 12 FRMERR: SPI Frame Error status bit

1 = Frame error detected

0 = No Frame error detected

This bit is only valid when FRMEN = 1.

bit 11 SPIBUSY: SPI Activity Status bit

1 = SPI peripheral is currently busy with some transactions

0 = SPI peripheral is currently idle

bit 10-9 Unimplemented: Read as '0'

bit 8 SPITUR: Transmit Under Run bit

1 = Transmit buffer has encountered an underrun condition

0 = Transmit buffer has no underrun condition

This bit is only valid in Framed Sync mode; the underrun condition must be cleared by disabling (ON bit = 0) and re-enabling (ON bit = 1) the module, or writing a '0' to SPITUR.

bit 7 **SRMT:** Shift Register Empty bit (valid only when ENHBUF = 1)

1 = When SPI module shift register is empty

0 = When SPI module shift register is not empty

bit 6 SPIROV: Receive Overflow Flag bit

1 = A new data is completely received and discarded. The user software has not read the previous data in the SPIxBUF register.

0 = No overflow has occurred

This bit is set in hardware; can bit only be cleared by disabling (ON bit = 0) and re-enabling (ON bit = 1) the module, or by writing a '0' to SPIROV.

bit 5 **SPIRBE:** RX FIFO Empty bit (valid only when ENHBUF = 1)

1 = RX FIFO is empty (CRPTR = SWPTR)

0 = RX FIFO is not empty (CRPTR ≠ SWPTR)

bit 4 Unimplemented: Read as '0'

#### REGISTER 17-3: SPIXSTAT: SPI STATUS REGISTER

- bit 3 SPITBE: SPI Transmit Buffer Empty Status bit
  - 1 = Transmit buffer, SPIxTXB is empty
  - 0 = Transmit buffer, SPIxTXB is not empty

Automatically set in hardware when SPI transfers data from SPIxTXB to SPIxSR. Automatically cleared in hardware when SPIxBUF is written to, loading SPIxTXB.

- bit 2 Unimplemented: Read as '0'
- bit 1 SPITBF: SPI Transmit Buffer Full Status bit
  - 1 = Transmit not yet started, SPITXB is full
  - 0 = Transmit buffer is not full

#### Standard Buffer Mode:

Automatically set in hardware when the core writes to the SPIBUF location, loading SPITXB. Automatically cleared in hardware when the SPI module transfers data from SPITXB to SPISR.

#### Enhanced Buffer Mode:

Set when CWPTR + 1 = SRPTR; cleared otherwise

- bit 0 SPIRBF: SPI Receive Buffer Full Status bit
  - 1 = Receive buffer, SPIxRXB is full
  - 0 = Receive buffer, SPIxRXB is not full

#### Standard Buffer Mode:

Automatically set in hardware when the SPI module transfers data from SPIxSR to SPIxRXB.

Automatically cleared in hardware when SPIxBUF is read from, reading SPIxRXB.

#### Enhanced Buffer Mode:

Set when SWPTR + 1 = CRPTR; cleared otherwise

# 18.0 INTER-INTEGRATED CIRCUIT (I<sup>2</sup>C)

Note:

This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To complement the information in this data sheet, refer to **Section 24.** "InterIntegrated Circuit (I<sup>2</sup>C)" (DS60001116), which is available from the *Documentation* > *Reference Manual* section of the Microchip PIC32 web site (www.microchip.com/pic32).

The  $I^2C$  module provides complete hardware support for both Slave and Multi-Master modes of the  $I^2C$  serial communication standard. Figure 18-1 illustrates the  $I^2C$  module block diagram.

Each I<sup>2</sup>C module has a 2-pin interface: the SCLx pin is clock and the SDAx pin is data.

Each I<sup>2</sup>C module offers the following key features:

- I<sup>2</sup>C interface supporting both master and slave operation
- I<sup>2</sup>C Slave mode supports 7-bit and 10-bit addressing
- I<sup>2</sup>C Master mode supports 7-bit and 10-bit addressing
- I<sup>2</sup>C port allows bidirectional transfers between master and slaves
- Serial clock synchronization for the I<sup>2</sup>C port can be used as a handshake mechanism to suspend and resume serial transfer (SCLREL control)
- I<sup>2</sup>C supports multi-master operation; detects bus collision and arbitrates accordingly
- · Provides support for address bit masking

I<sup>2</sup>C BLOCK DIAGRAM **FIGURE 18-1:** Internal Data Bus I2CxRCV Read Shift Clock **I2CxRSR** Address Match Match Detect Write I2CxMSK Read Write **I2CxADD** Read Start and Stop bit Detect Write Start and Stop I2CxSTAT bit Generation Control Logic Read Collision Write Detect I2CxCON Acknowledge Read Generation Clock Stretching Write **I2CxTRN** LSB Read Shift Clock Reload Control Write BRG Down Counter I2CxBRG Read **PBCLK** 

TABLE 18-1: 12C1 AND 12C2 REGISTER MAP **I2C Control Registers** 18.1

-	_	teseR IIA	000	100	000	000	000	000	000	000	000	000	000	000	000	000	000	100	000	000	000	000	000	000	000	000	000	000	000	000
		16/0	I	SEN	I	TBF	_		Ι		_		-		_		I	SEN	I	TBF	1		1		-		-		1	
		17/1	1	RSEN	_	RBF	_		-		I		1		_		I	RSEN	I	RBF	_		_		_		Ι		1	
		18/2	1	PEN	1	M_N	I		1		I		I		1		I	PEN	I	$R_{M}$	1		1		I		I		1	
		19/3	1	RCEN	_	S	I		-		I		I	Transmit Register	-	Register	1	RCEN	I	S	-		-		I		ı	Register	1	Receive Register
		20/4	1	ACKEN	-	Ь	_	Address Register	-	Address Mask Register	_	ster	_	Transmit	1	Receive Register	I	ACKEN	Ι	Ь	1	Address Register	1	Address Mask Register	_	ster	Ι	Transmit Register	Ι	Receive
		21/5	1	ACKDT	-	D_A	_	Address	-	Address Ma	_	erator Regi	_		_		I	ACKDT	Ι	$P^{-}Q$	Ι	Address	Ι	Address Ma	_	ıerator Regi	-		I	
		22/6	1	STREN	-	ISCOV	_		-		_	Baud Rate Generator Register	_		_		I	STREN	Ι	IZCOV	Ι		Ι	'	_	Baud Rate Generator Register	-		I	
1	DILS	23/7	I	GCEN	Ι	IWCOL	Ι		I		Ι	Ban	I		I		I	GCEN	I	IWCOL	1		1		I	Ban	I		Ι	
C	0	24/8	I	SMEN	Ι	ADD10	_		Ι		_		_	_	_	I	I	SMEN	I	ADD10	-		-		_		I	Ι	Ι	I
		25/9	I	DISSLW	Ι	GCSTAT	_		Ι		_		_	_	_	Ι	I	DISSLW	I	GCSTAT	-		-		_		Ι	Ι	Ι	I
		26/10	I	A10M	Ι	BCL	_	I	Ι	I	_		_	_	_	Ι	I	A10M	I	BCL	-	-	-	_	_		Ι	Ι	Ι	I
		27/11	I	STRICT	Ι	Ι	Ι	Ι	Ι	Ι	Ι		Ι	Ι	1	I	Ι	STRICT	I	1	1	1	1	1	Ι		I	I	Ι	I
		28/12	1	SCLREL	1	Ι	Ι	Ι	1	Ι	Ι	I	I	I	1	I	1	SCLREL	I	1	1	1	1	1	I	1	I	I	Ι	Ι
		29/13	1	SIDL	1	Ι	I	Ι	1	Ι	I	Ι	Ι	Ι	١	I	1	SIDL	I	1	1	1	1	١	Ι	1	I	I	Ι	Ι
		30/14	1	1	-	TRSTAT	Ι	Ι	-	Ι	Ι	Ι	Ι	Ι	1	Ι	1	1	I	TRSTAT	1	1	1	1	Ι	1	Ι	Ι	Ι	Ι
		31/15	1	NO	I	ACKSTAT	I	I	I	I	I	I	I	I	1	I	1	NO	I	ACKSTAT	1	1	1	1	I	1	I	I	1	1
	ŧ	Bit Range	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0
		Register <sup>(†)</sup> อmsN		NOOLOZI	TATOLOGI	IZC ISTAL	007700	IZCIADD	710000	IZC IMION	Jaarjoi	פאפו או	Matroci	N	/\JakJ6	202		IZCZCON	TATOCOCI	ואוסאסאו	חחענטנו	מטאבטבו	ASMCOCI	IZCZINISIN	Jacobi	פרמצטצו	Natood	ואואואוא		IZCZRCV
s		Virtual Addr (#_0878)	000	0006	010	0100	0003	2020	0003	0506	6040	2040	6050	nene	6060	0000	7	0016	7	0.10	6120	3120	5130	0010	6140	0 140	6450	0010	7.460	091.6

All registers in this table except I2CxRCV have corresponding CLR, SET and INV registers at their virtual addresses, plus offsets of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for more information. x = unknown value on Reset; --= unimplemented, read as '0'. Reset values are shown in hexadecimal. Legend:

### REGISTER 18-1: I2CxCON: I<sup>2</sup>C CONTROL REGISTER

<b>1201011</b>	-11 10 11 12	OXOGITI I	00.11.1102	1120101211	•			
Bit Bit Range 31/23/15/7		Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
04:04	U-0                U-0							
31:24	_	_	_	_	_	_	_	_
00.40	U-0                U-0							
23:16	_	_	_	_	_	_	_	_
45.0	R/W-0	U-0	R/W-0	R/W-1, HC	R/W-0	R/W-0	R/W-0	R/W-0
15:8	ON <sup>(1)</sup>	_	SIDL	SCLREL	STRICT	A10M	DISSLW	SMEN
7.0	R/W-0	R/W-0	R/W-0	R/W-0, HC	R/W-0, HC	R/W-0, HC	R/W-0, HC	R/W-0, HC
7:0	GCEN	STREN	ACKDT	ACKEN	RCEN	PEN	RSEN	SEN

**Legend:** HC = Cleared in Hardware

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### bit 31-16 Unimplemented: Read as '0'

bit 15 **ON:** I<sup>2</sup>C Enable bit<sup>(1)</sup>

1 = Enables the I<sup>2</sup>C module and configures the SDA and SCL pins as serial port pins

 $0 = \text{Disables the } 1^2\text{C module}$ ; all  $1^2\text{C pins}$  are controlled by PORT functions

bit 14 Unimplemented: Read as '0'

bit 13 SIDL: Stop in Idle Mode bit

1 = Discontinue module operation when the device enters Idle mode

0 = Continue module operation when the device enters Idle mode

bit 12 **SCLREL:** SCLx Release Control bit (when operating as I<sup>2</sup>C slave)

1 = Release SCLx clock

0 = Hold SCLx clock low (clock stretch)

### If STREN = 1:

Bit is R/W (i.e., software can write '0' to initiate stretch and write '1' to release clock). Hardware clear at beginning of slave transmission. Hardware clear at end of slave reception.

#### If STREN = 0

Bit is R/S (i.e., software can only write '1' to release clock). Hardware clear at beginning of slave transmission

### bit 11 STRICT: Strict I<sup>2</sup>C Reserved Address Rule Enable bit

- 1 = Strict reserved addressing is enforced. Device does not respond to reserved address space or generate addresses in reserved address space.
- 0 = Strict I<sup>2</sup>C Reserved Address Rule not enabled
- bit 10 A10M: 10-bit Slave Address bit

1 = I2CxADD is a 10-bit slave address

0 = I2CxADD is a 7-bit slave address

bit 9 DISSLW: Disable Slew Rate Control bit

1 = Slew rate control disabled

0 = Slew rate control enabled

bit 8 SMEN: SMBus Input Levels bit

1 = Enable I/O pin thresholds compliant with SMBus specification

0 = Disable SMBus input thresholds

**Note 1:** When using 1:1 PBCLK divisor, the user's software should not read/write the peripheral's SFRs in the SYSCLK cycle immediately following the instruction that clears the module's ON bit.

### REGISTER 18-1: I2CxCON: I<sup>2</sup>C CONTROL REGISTER (CONTINUED)

- bit 7 GCEN: General Call Enable bit (when operating as I<sup>2</sup>C slave)
  - 1 = Enable interrupt when a general call address is received in the I2CxRSR (module is enabled for reception)
  - 0 = General call address is disabled
- bit 6 STREN: SCLx Clock Stretch Enable bit (when operating as I<sup>2</sup>C slave)

Used in conjunction with SCLREL bit.

- 1 = Enable software or receive clock stretching
- 0 = Disable software or receive clock stretching
- bit 5 **ACKDT:** Acknowledge Data bit (when operating as I<sup>2</sup>C master, applicable during master receive)

Value that is transmitted when the software initiates an Acknowledge sequence.

- 1 = Send a NACK during an Acknowledge sequence
- 0 = Send an ACK during an Acknowledge sequence
- bit 4 **ACKEN:** Acknowledge Sequence Enable bit (when operating as I<sup>2</sup>C master, applicable during master receive)
  - 1 = Initiate Acknowledge sequence on SDAx and SCLx pins and transmit ACKDT data bit. Hardware clear at end of master Acknowledge sequence.
  - 0 = Acknowledge sequence not in progress
- bit 3 **RCEN**: Receive Enable bit (when operating as I<sup>2</sup>C master)
  - 1 = Enables Receive mode for I<sup>2</sup>C. Hardware clear at end of eighth bit of master receive data byte.
  - 0 = Receive sequence not in progress
- bit 2 **PEN:** Stop Condition Enable bit (when operating as I<sup>2</sup>C master)
  - 1 = Initiate Stop condition on SDAx and SCLx pins. Hardware clear at end of master Stop sequence.
  - 0 = Stop condition not in progress
- bit 1 **RSEN:** Repeated Start Condition Enable bit (when operating as I<sup>2</sup>C master)
  - 1 = Initiate Repeated Start condition on SDAx and SCLx pins. Hardware clear at end of master Repeated Start sequence.
  - 0 = Repeated Start condition not in progress
- bit 0 **SEN:** Start Condition Enable bit (when operating as I<sup>2</sup>C master)
  - 1 = Initiate Start condition on SDAx and SCLx pins. Hardware clear at end of master Start sequence.
  - 0 = Start condition not in progress
- **Note 1:** When using 1:1 PBCLK divisor, the user's software should not read/write the peripheral's SFRs in the SYSCLK cycle immediately following the instruction that clears the module's ON bit.

#### REGISTER 18-2: I2CXSTAT: I<sup>2</sup>C STATUS REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0                U-0							
31:24	_	_	_	_	-	_	_	_
00.40	U-0                U-0							
23:16	_	_	_	_	_	_	_	_
45.0	R-0, HSC	R-0, HSC	U-0	U-0	U-0	R/C-0, HS	R-0, HSC	R-0, HSC
15:8	ACKSTAT	TRSTAT	_	_	_	BCL	GCSTAT	ADD10
7.0	R/C-0, HS	R/C-0, HS	R-0, HSC	R/C-0, HSC	R/C-0, HSC	R-0, HSC	R-0, HSC	R-0, HSC
7:0	IWCOL	I2COV	D_A	Р	S	R_W	RBF	TBF

Legend:HS = Set in hardwareHSC = Hardware set/clearedR = Readable bitW = Writable bitU = Unimplemented bit, read as '0'-n = Value at POR'1' = Bit is set'0' = Bit is clearedC = Clearable bit

bit 31-16 Unimplemented: Read as '0'

bit 15 **ACKSTAT:** Acknowledge Status bit (when operating as I<sup>2</sup>C master, applicable to master transmit operation)

- 1 = Acknowledge was not received from slave
- 0 = Acknowledge was received from slave

Hardware set or clear at end of slave Acknowledge.

bit 14 **TRSTAT:** Transmit Status bit (when operating as I<sup>2</sup>C master, applicable to master transmit operation)

- 1 = Master transmit is in progress (8 bits + ACK)
- 0 = Master transmit is not in progress

Hardware set at beginning of master transmission. Hardware clear at end of slave Acknowledge.

- bit 13-11 Unimplemented: Read as '0'
- bit 10 BCL: Master Bus Collision Detect bit
  - 1 = A bus collision has been detected during a master operation
  - 0 = No collision

Hardware set at detection of bus collision. This condition can only be cleared by disabling (ON bit = 0) and re-enabling (ON bit = 1) the module.

- bit 9 GCSTAT: General Call Status bit
  - 1 = General call address was received
  - 0 = General call address was not received

Hardware set when address matches general call address. Hardware clear at Stop detection.

- bit 8 ADD10: 10-bit Address Status bit
  - 1 = 10-bit address was matched
  - 0 = 10-bit address was not matched

Hardware set at match of 2nd byte of matched 10-bit address. Hardware clear at Stop detection.

- bit 7 IWCOL: Write Collision Detect bit
  - 1 = An attempt to write the I2CxTRN register failed because the I<sup>2</sup>C module is busy
  - 0 = No collision

Hardware set at occurrence of write to I2CxTRN while busy (cleared by software).

- bit 6 I2COV: Receive Overflow Flag bit
  - 1 = A byte was received while the I2CxRCV register is still holding the previous byte
  - 0 = No overflow

Hardware set at attempt to transfer I2CxRSR to I2CxRCV (cleared by software).

- bit 5 **D\_A:** Data/Address bit (when operating as I<sup>2</sup>C slave)
  - 1 = Indicates that the last byte received was data
  - 0 = Indicates that the last byte received was device address

Hardware clear at device address match. Hardware set by reception of slave byte.

#### REGISTER 18-2: I2CxSTAT: I<sup>2</sup>C STATUS REGISTER (CONTINUED)

- bit 4 P: Stop bit
  - 1 = Indicates that a Stop bit has been detected last
  - 0 = Stop bit was not detected last

Hardware set or clear when Start, Repeated Start or Stop detected.

- bit 3 S: Start bit
  - 1 = Indicates that a Start (or Repeated Start) bit has been detected last
  - 0 = Start bit was not detected last

Hardware set or clear when Start, Repeated Start or Stop detected.

- bit 2 **R\_W**: Read/Write Information bit (when operating as I<sup>2</sup>C slave)
  - 1 = Read indicates data transfer is output from slave
  - 0 = Write indicates data transfer is input to slave

Hardware set or clear after reception of I<sup>2</sup>C device address byte.

- bit 1 RBF: Receive Buffer Full Status bit
  - 1 = Receive complete, I2CxRCV is full
  - 0 = Receive not complete, I2CxRCV is empty

Hardware set when I2CxRCV is written with received byte. Hardware clear when software reads I2CxRCV.

- bit 0 TBF: Transmit Buffer Full Status bit
  - 1 = Transmit in progress, I2CxTRN is full
  - 0 = Transmit complete, I2CxTRN is empty

Hardware set when software writes I2CxTRN. Hardware clear at completion of data transmission.

NOTES:		

# 19.0 UNIVERSAL ASYNCHRONOUS RECEIVER TRANSMITTER (UART)

Note:

This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To complement the information in this data sheet, refer to **Section 21. "Universal Asynchronous Receiver Transmitter (UART)"** (DS60001107), which is available from the *Documentation > Reference Manual* section of the Microchip PIC32 web site (www.microchip.com/pic32).


The UART module is one of the serial I/O modules available in PIC32MX1XX/2XX 28/36/44-pin Family devices. The UART is a full-duplex, asynchronous communication channel that communicates with peripheral devices and personal computers through protocols, such as RS-232, RS-485, LIN, and IrDA®. The UART module also supports the hardware flow control option, with UxCTS and UxRTS pins, and also includes an IrDA encoder and decoder.

Key features of the UART module include:

- · Full-duplex, 8-bit or 9-bit data transmission
- Even, Odd or No Parity options (for 8-bit data)
- · One or two Stop bits
- · Hardware auto-baud feature
- · Hardware flow control option
- Fully integrated Baud Rate Generator (BRG) with 16-bit prescaler
- Baud rates ranging from 38 bps to 12.5 Mbps at 50 MHz
- 8-level deep First In First Out (FIFO) transmit data buffer
- · 8-level deep FIFO receive data buffer
- · Parity, framing and buffer overrun error detection
- Support for interrupt-only on address detect (9th bit = 1)
- · Separate transmit and receive interrupts
- · Loopback mode for diagnostic support
- · LIN protocol support
- IrDA encoder and decoder with 16x baud clock output for external IrDA encoder/decoder support

Figure 19-1 illustrates a simplified block diagram of the UART module.

FIGURE 19-1: UART SIMPLIFIED BLOCK DIAGRAM



19.1 UART Control Registers
TABLE 19-1: UART1 AND UART2 REGISTER MAP

s	Jesef IIA	0000	0000	0000	0110	0000	0000	0000	0000	0000	0000	0000	0000	0000	0110	0000	0000	0000	0000	0000	0000
	16/0	I	STSEL		NRXDA	_		_		_		_	STSEL		NRXDA	_		_		1	
	17/1	I	-<1:0>		OERR	-		_		_		_	PDSEL<1:0>		OERR	_		Ι		_	
	18/2	I	PDSEL<1:0>		FERR	Ι		1		-		1	PDSEI		FERR	_		I		_	İ
	19/3	I	BRGH	ADDR<7:0>	PERR	_	ster	_	ster	_		_	HSAB	ADDR<7:0>	PERR	1	ster	-	ster	I	
	20/4	Ι	RXINV	ADDR	RIDLE	_	Transmit Register	_	Receive Register	_		_	RXINV	ADDR	RIDLE	-	Transmit Register	_	Receive Register	1	
	21/5	1	ABAUD		ADDEN	-	Tra	_	Re			_	ABAUD		ADDEN	-	Tra	1	Re	1	
	22/6	I	LPBACK		URXISEL<1:0>	Ι		-		-	caler	-	LPBACK		URXISEL<1:0>	1		I		1	caler
Bits	23/7	I	WAKE		BIXXIO	_		_		_	Baud Rate Generator Prescaler	_	WAKE		BIXXIO	_		_		1	Baud Rate Generator Prescaler
Bi	24/8	I	<1:0>	ADM_EN	TRMT	-		_		_	d Rate Gen	_	UEN<1:0>	ADM_EN	TRMT	_		Ι		_	d Rate Gen
	25/9	Ι	UEN<1:0>	_	UTXBF	_	_	_	_	_	Bau	_	NEN	_	UTXBF	-	-	_	-	1	Bau
	26/10	-	I	_	NEXEN	_	_	_	_	_		_	_	_	NEXEN	-	-	_	-	1	İ
	27/11	I	RTSMD	_	UTXBRK	_	_	_	_	_		_	RTSMD	_	UTXBRK	I	I	_	I	1	İ
	28/12	I	IREN	_	NEXEN	_	Ι	_	_	_		_	IREN	Ι	NEXEN	Ι	Ι	_	Ι	1	İ
	29/13	I	SIDL	Ι	VNIXTU	I	I	Ι	I	Ι		Ι	SIDL	I	VNIXTU	1	1	I	1	1	
	30/14	I	1	I	UTXISEL<1:0>	I	I	I	I	Ι		I	I	I	UTXISEL<1:0>	1	1	I	1	1	
	31/15	Ι	NO	_	UTXIS	Ι	_	_	Ι	_		_	NO	_	UTXIS	1	1	Ι	1	1	
•	Bit Range	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0
	Register 9msM	31:16	UIMODE	111CTA(1)	. XISIO	CHANCE	פוערוס	CHOVER	פואאוס	(1)	. פאם וס	31:16	OZINODE	(1)OCTA(1)	UZSIA	DIOTYPEC	טבואאבוש		UZIVANEG	(1) Dag(1)	OZDNO
	Virtual Addr (#_0878)	0	0000	010	000	0000	0700	0000		0,00	0400	0000	0070	0770	07 70	0000	0220	0000	05.30	6240	0470

This register has corresponding CLR, SET and INV registers at its virtual address, plus an offset of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for more information.

#### REGISTER 19-1: UxMODE: UARTX MODE REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0                U-0							
31:24		_	_	-	-	_	_	_
00:40	U-0                U-0							
23:16	_	_	_	_	_	_	_	_
45.0	R/W-0	U-0	R/W-0	R/W-0	R/W-0	U-0	R/W-0	R/W-0
15:8	ON <sup>(1)</sup>	_	SIDL	IREN	RTSMD	_	UEN:	<1:0>
7.0	R/W-0              R/W-0							
7:0	WAKE	LPBACK	ABAUD	RXINV	BRGH	PDSEL	<1:0>	STSEL

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### bit 31-16 Unimplemented: Read as '0'

bit 15 **ON:** UARTx Enable bit<sup>(1)</sup>

- 1 = UARTx is enabled. UARTx pins are controlled by UARTx as defined by the UEN<1:0> and UTXEN control bits
- 0 = UARTx is disabled. All UARTx pins are controlled by corresponding bits in the PORTx, TRISx and LATx registers; UARTx power consumption is minimal.
- bit 14 Unimplemented: Read as '0'
- bit 13 SIDL: Stop in Idle Mode bit
  - 1 = Discontinue module operation when the device enters Idle mode
  - 0 = Continue module operation when the device enters Idle mode
- bit 12 IREN: IrDA Encoder and Decoder Enable bit
  - 1 = IrDA is enabled
  - 0 = IrDA is disabled
- bit 11 RTSMD: Mode Selection for UxRTS Pin bit
  - $1 = \overline{\text{UxRTS}}$  pin is in Simplex mode
  - $0 = \overline{\text{UxRTS}}$  pin is in Flow Control mode
- bit 10 Unimplemented: Read as '0'
- bit 9-8 **UEN<1:0>:** UARTx Enable bits
  - 11 = UxTX, UxRX and UxBCLK pins are enabled and used; UxCTS pin is controlled by corresponding bits in the PORTx register
  - 10 = UxTX, UxRX,  $\overline{\text{UxCTS}}$  and  $\overline{\text{UxRTS}}$  pins are enabled and used
  - 01 = UxTX, UxRX and  $\overline{UxRTS}$  pins are enabled and used;  $\overline{UxCTS}$  pin is controlled by corresponding bits in the PORTx register
  - 00 = UxTX and UxRX pins are enabled and used; UxCTS and UxRTS/UxBCLK pins are controlled by corresponding bits in the PORTx register
- bit 7 WAKE: Enable Wake-up on Start bit Detect During Sleep Mode bit
  - 1 = Wake-up enabled
  - 0 = Wake-up disabled
- bit 6 LPBACK: UARTx Loopback Mode Select bit
  - 1 = Loopback mode is enabled
  - 0 = Loopback mode is disabled
- **Note 1:** When using 1:1 PBCLK divisor, the user software should not read/write the peripheral SFRs in the SYSCLK cycle immediately following the instruction that clears the module's ON bit.

#### REGISTER 19-1: UxMODE: UARTX MODE REGISTER (CONTINUED)

- bit 5 ABAUD: Auto-Baud Enable bit
  - 1 = Enable baud rate measurement on the next character requires reception of Sync character (0x55); cleared by hardware upon completion
  - 0 = Baud rate measurement disabled or completed
- bit 4 RXINV: Receive Polarity Inversion bit
  - 1 = UxRX Idle state is '0'
  - 0 = UxRX Idle state is '1'
- bit 3 BRGH: High Baud Rate Enable bit
  - 1 = High-Speed mode 4x baud clock enabled
  - 0 = Standard Speed mode 16x baud clock enabled
- bit 2-1 PDSEL<1:0>: Parity and Data Selection bits
  - 11 = 9-bit data, no parity
  - 10 = 8-bit data, odd parity
  - 01 = 8-bit data, even parity
  - 00 = 8-bit data, no parity
- bit 0 STSEL: Stop Selection bit
  - 1 = 2 Stop bits
  - 0 = 1 Stop bit
- **Note 1:** When using 1:1 PBCLK divisor, the user software should not read/write the peripheral SFRs in the SYSCLK cycle immediately following the instruction that clears the module's ON bit.

#### REGISTER 19-2: UxSTA: UARTX STATUS AND CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0                R/W-0							
31:24	_	_	_	-	_	_	_	ADM_EN
00:40	R/W-0              R/W-0							
23:16				ADDR<	<7:0>			
45.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R-0	R-1
15:8	UTXISE	L<1:0>	UTXINV	URXEN	UTXBRK	UTXEN	UTXBF	TRMT
7.0	R/W-0	R/W-0	R/W-0	R-1	R-0	R-0	R/W-0	R-0
7:0	URXISE	L<1:0>	ADDEN	RIDLE	PERR	FERR	OERR	URXDA

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### bit 31-25 Unimplemented: Read as '0'

bit 24 ADM EN: Automatic Address Detect Mode Enable bit

1 = Automatic Address Detect mode is enabled

0 = Automatic Address Detect mode is disabled

bit 23-16 ADDR<7:0>: Automatic Address Mask bits

When the ADM\_EN bit is '1', this value defines the address character to use for automatic address detection.

#### bit 15-14 UTXISEL<1:0>: TX Interrupt Mode Selection bits

- 11 = Reserved, do not use
- 10 = Interrupt is generated and asserted while the transmit buffer is empty
- 01 = Interrupt is generated and asserted when all characters have been transmitted
- 00 = Interrupt is generated and asserted while the transmit buffer contains at least one empty space

#### bit 13 **UTXINV:** Transmit Polarity Inversion bit

#### If IrDA mode is disabled (i.e., IREN (UxMODE<12>) is '0'):

- 1 = UxTX Idle state is '0'
- 0 = UxTX Idle state is '1'

#### If IrDA mode is enabled (i.e., IREN (UxMODE<12>) is '1'):

- 1 = IrDA encoded UxTX Idle state is '1'
- 0 = IrDA encoded UxTX Idle state is '0'
- bit 12 URXEN: Receiver Enable bit
  - 1 = UARTx receiver is enabled. UxRX pin is controlled by UARTx (if ON = 1)
  - 0 = UARTx receiver is disabled. UxRX pin is ignored by the UARTx module. UxRX pin is controlled by port.
- bit 11 UTXBRK: Transmit Break bit
  - 1 = Send Break on next transmission. Start bit followed by twelve '0' bits, followed by Stop bit; cleared by hardware upon completion
  - 0 = Break transmission is disabled or completed
- bit 10 UTXEN: Transmit Enable bit
  - 1 = UARTx transmitter is enabled. UxTX pin is controlled by UARTx (if ON = 1).
  - 0 = UARTx transmitter is disabled. Any pending transmission is aborted and buffer is reset. UxTX pin is controlled by port.
- bit 9 **UTXBF:** Transmit Buffer Full Status bit (read-only)
  - 1 = Transmit buffer is full
  - 0 = Transmit buffer is not full, at least one more character can be written
- bit 8 **TRMT:** Transmit Shift Register is Empty bit (read-only)
  - 1 = Transmit shift register is empty and transmit buffer is empty (the last transmission has completed)
  - 0 = Transmit shift register is not empty, a transmission is in progress or queued in the transmit buffer

#### REGISTER 19-2: UxSTA: UARTx STATUS AND CONTROL REGISTER (CONTINUED)

- bit 7-6 URXISEL<1:0>: Receive Interrupt Mode Selection bit
  - 11 = Reserved; do not use
  - 10 = Interrupt flag bit is asserted while receive buffer is 3/4 or more full (i.e., has 6 or more data characters)
  - 01 = Interrupt flag bit is asserted while receive buffer is 1/2 or more full (i.e., has 4 or more data characters)
  - 00 = Interrupt flag bit is asserted while receive buffer is not empty (i.e., has at least 1 data character)
- bit 5 ADDEN: Address Character Detect bit (bit 8 of received data = 1)
  - 1 = Address Detect mode is enabled. If 9-bit mode is not selected, this control bit has no effect.
  - 0 = Address Detect mode is disabled
- bit 4 RIDLE: Receiver Idle bit (read-only)
  - 1 = Receiver is Idle
  - 0 = Data is being received
- bit 3 **PERR:** Parity Error Status bit (read-only)
  - 1 = Parity error has been detected for the current character
  - 0 = Parity error has not been detected
- bit 2 **FERR:** Framing Error Status bit (read-only)
  - 1 = Framing error has been detected for the current character
  - 0 = Framing error has not been detected
- bit 1 **OERR:** Receive Buffer Overrun Error Status bit.

This bit is set in hardware and can only be cleared (= 0) in software. Clearing a previously set OERR bit resets the receiver buffer and the RSR to an empty state.

- 1 = Receive buffer has overflowed
- 0 = Receive buffer has not overflowed
- bit 0 **URXDA:** Receive Buffer Data Available bit (read-only)
  - 1 = Receive buffer has data, at least one more character can be read
  - 0 = Receive buffer is empty

Figure 19-2 and Figure 19-3 illustrate typical receive and transmit timing for the UART module.

FIGURE 19-2: UART RECEPTION





FIGURE 19-3: TRANSMISSION (8-BIT OR 9-BIT DATA)



NOTES:			

## 20.0 PARALLEL MASTER PORT (PMP)

Note:

This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To complement the information in this data sheet, refer to **Section 13. "Parallel Master Port (PMP)"** (DS60001128), which is available from the *Documentation* > *Reference Manual* section of the Microchip PIC32 web site (www.microchip.com/pic32).


The PMP is a parallel 8-bit input/output module specifically designed to communicate with a wide variety of parallel devices, such as communications peripherals, LCDs, external memory devices and microcontrollers. Because the interface to parallel peripherals varies significantly, the PMP module is highly configurable.

Key features of the PMP module include:

- · Fully multiplexed address/data mode
- Demultiplexed or partially multiplexed address/ data mode
  - up to 11 address lines with single Chip Select
  - up to 12 address lines without Chip Select
- · One Chip Select line
- · Programmable strobe options
  - Individual read and write strobes or;
  - Read/write strobe with enable strobe
- · Address auto-increment/auto-decrement
- · Programmable address/data multiplexing
- · Programmable polarity on control signals
- · Legacy parallel slave port support
- Enhanced parallel slave support
  - Address support
  - 4-byte deep auto-incrementing buffer
- Programmable Wait states
- · Selectable input voltage levels

Figure 20-1 illustrates the PMP module block diagram.

FIGURE 20-1: PMP MODULE PINOUT AND CONNECTIONS TO EXTERNAL DEVICES



20.1 PMP Control Registers
TABLE 20-1: PARALLEL MASTER PORT REGISTER MAP

s	stəsəЯ IIA	0000	0000	0000	0000	0000	0 00 0	0000	0000	0000	0000	0000	008F
	16/0	1	RDSP	I	:<1:0>	I				1		1	OB0E
	17/1	1	WRSP	I	WAITE<1:0>	I				I		I	OB1E
	18/2	I	I	I		I				I		I	OB2E
	19/3	1	CS1P	I	1<3:0>	I				I		I	OB3E
	20/4	I	1	I	WAITM<3:0>	I	_			1		1	1
	21/5	I	ALP	I		I	ADDR<10:0>			I	PTEN<10:0>	I	1
	22/6	1	CSF<1:0>	I	WAITB<1:0>	I	•			I		I	OBUF
Bits	23/7	1	CSF	I	WAITE	I		DATAOUT<31:0>	DATAIN<31:0>	I		I	OBE
B	24/8	1	PTRDEN	I	MODE<1:0>	I		DATAOU	DATAIN	I		I	IB0F
	25/9	I	PTWREN	I	MODE	I				I		I	IB1F
	26/10	I	PMPTTL	I	I	I				ı		I	IB2F
	27/11	I	JX<1:0>	I	<1:0>	I	ı			I	1	1	IB3F
	28/12	I	ADRMU	I	INCM	I	I			I	Ι	I	1
	29/13	1	SIDL	I	IRQM<1:0>	I	I			I	I	I	1
	30/14	ı	Ι	I	IRQM	I	CS1 ADDR14			I	PTEN14	I	IBOV
	31/15	I	NO	Ι	BUSY	Ι	1			I	I	I	IBF
•	Bit Range	31:16	15:0	31:16	15:0	31:16	15:0	31:16 15:0	31:16 15:0	31:16	15:0	31:16	15:0
	Register Name <sup>(1)</sup>			T C C 4 4 4 4 C	VOID PINIMODE		PMADDR	PMDOUT	NIQWA		PMAEN	TATOMAG	FMSIAI
	Virtual Addr (#_0878)	1000	0007	7070	01.07		7020	7030	7040	1	0907		0007

All registers in this table have corresponding CLR, SET and INV registers at their virtual addresses, plus offsets of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for more information.  ${\bf x}$  = unknown value on Reset; — = unimplemented, read as '0'. Reset values are shown in hexadecimal. Legend:

#### REGISTER 20-1: PMCON: PARALLEL PORT CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31.24	_	_	-	-	_	-	_	_
00.40	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23:16	_	_	-	-	_	-	_	_
45.0	R/W-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
15:8	ON <sup>(1)</sup>	_	SIDL	ADRMU	JX<1:0>	PMPTTL	PTWREN	PTRDEN
7.0	R/W-0	R/W-0	R/W-0	U-0	R/W-0	U-0	R/W-0	R/W-0
7:0	CSF<	1:0> <sup>(2)</sup>	ALP <sup>(2)</sup>		CS1P <sup>(2)</sup>		WRSP	RDSP

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

bit 15 **ON:** Parallel Master Port Enable bit<sup>(1)</sup>

1 = PMP enabled

0 = PMP disabled, no off-chip access performed

bit 14 **Unimplemented:** Read as '0'

bit 13 SIDL: Stop in Idle Mode bit

1 = Discontinue module operation when the device enters Idle mode

0 = Continue module operation when the device enters Idle mode

bit 12-11 ADRMUX<1:0>: Address/Data Multiplexing Selection bits

11 = Lower 8 bits of address are multiplexed on PMD<7:0> pins; upper 8 bits are not used

10 = All 16 bits of address are multiplexed on PMD<7:0> pins

01 = Lower 8 bits of address are multiplexed on PMD<7:0> pins, upper bits are on PMA<10:8> and PMA<14>

00 = Address and data appear on separate pins

bit 10 PMPTTL: PMP Module TTL Input Buffer Select bit

1 = PMP module uses TTL input buffers

0 = PMP module uses Schmitt Trigger input buffer

bit 9 PTWREN: Write Enable Strobe Port Enable bit

1 = PMWR/PMENB port enabled

0 = PMWR/PMENB port disabled

bit 8 PTRDEN: Read/Write Strobe Port Enable bit

1 = PMRD/PMWR port enabled

0 = PMRD/PMWR port disabled

bit 7-6 CSF<1:0>: Chip Select Function bits<sup>(2)</sup>

11 = Reserved

10 = PMCS1 functions as Chip Select

01 = PMCS1 functions as PMA<14>

00 = PMCS1 functions as PMA<14>

bit 5 ALP: Address Latch Polarity bit<sup>(2)</sup>

1 = Active-high (PMALL and PMALH)

0 = Active-low (PMALL and PMALH)

**Note 1:** When using 1:1 PBCLK divisor, the user's software should not read/write the peripheral's SFRs in the SYSCLK cycle immediately following the instruction that clears the module's ON control bit.

2: These bits have no effect when their corresponding pins are used as address lines.

#### REGISTER 20-1: PMCON: PARALLEL PORT CONTROL REGISTER (CONTINUED)

- bit 4 **Unimplemented:** Read as '0'
- bit 3 **CS1P:** Chip Select 0 Polarity bit<sup>(2)</sup>
  - 1 = Active-high (PMCS1)
  - 0 = Active-low (PMCS1)
- bit 2 Unimplemented: Read as '0'
- bit 1 WRSP: Write Strobe Polarity bit

For Slave Modes and Master mode 2 (MODE<1:0> = 00,01,10):

- 1 = Write strobe active-high (PMWR)
- $0 = Write strobe active-low (\overline{PMWR})$

For Master mode 1 (MODE<1:0> = 11):

- 1 = Enable strobe active-high (PMENB)
- 0 = Enable strobe active-low (PMENB)
- bit 0 RDSP: Read Strobe Polarity bit

For Slave modes and Master mode 2 (MODE<1:0> = 00,01,10):

- 1 = Read Strobe active-high (PMRD)
- 0 = Read Strobe active-low (PMRD)

For Master mode 1 (MODE<1:0> = 11):

- 1 = Read/write strobe active-high (PMRD/PMWR)
- 0 = Read/write strobe active-low (PMRD/PMWR)

**Note 1:** When using 1:1 PBCLK divisor, the user's software should not read/write the peripheral's SFRs in the SYSCLK cycle immediately following the instruction that clears the module's ON control bit.

2: These bits have no effect when their corresponding pins are used as address lines.

#### REGISTER 20-2: PMMODE: PARALLEL PORT MODE REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31.24	_	_	_	_	_	_	_	_
00:40	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23:16	_	_	_	_	_	_	_	_
45.0	R-0	R/W-0	R/W-0	R/W-0	R/W-0	U-0	R/W-0	R/W-0
15:8	BUSY	IRQM	<1:0>	INCM	<1:0>	_	MODE	E<1:0>
7.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
7:0	WAITB	<1:0> <sup>(1)</sup>		WAITM	<3:0> <sup>(1)</sup>		WAITE	<1:0> <sup>(1)</sup>

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

bit 15 BUSY: Busy bit (Master mode only)

1 = Port is busy

0 = Port is not busy

bit 14-13 IRQM<1:0>: Interrupt Request Mode bits (3)

- 11 = Reserved, do not use
- 10 = Interrupt generated when Read Buffer 3 is read or Write Buffer 3 is written (Buffered PSP mode) or on a read or write operation when PMA<1:0> =11 (Addressable Slave mode only)
- 01 = Interrupt generated at the end of the read/write cycle
- 00 = No Interrupt generated
- bit 12-11 INCM<1:0>: Increment Mode bits
  - 11 = Slave mode read and write buffers auto-increment (MODE<1:0> = 00 only)
  - 10 = Decrement ADDR<10:2> and ADDR<14> by 1 every read/write cycle<sup>(2)</sup>
  - 01 = Increment ADDR<10:2> and ADDR<14> by 1 every read/write cycle<sup>(2)</sup>
  - 00 = No increment or decrement of address
- bit 10 Unimplemented: Read as '0'
- bit 9-8 MODE<1:0>: Parallel Port Mode Select bits
  - 11 = Master mode 1 (PMCS1, PMRD/PMWR, PMENB, PMA<x:0>, and PMD<7:0>)
  - 10 = Master mode 2 (PMCS1, PMRD, PMWR, PMA<x:0>, and PMD<7:0>)
  - 01 = Enhanced Slave mode, control signals (PMRD, PMWR, PMCS1, PMD<7:0>, and PMA<1:0>)
  - 00 = Legacy Parallel Slave Port, control signals (PMRD, PMWR, PMCS1, and PMD<7:0>)
- bit 7-6 WAITB<1:0>: Data Setup to Read/Write Strobe Wait States bits<sup>(1)</sup>
  - 11 = Data wait of 4 TPB; multiplexed address phase of 4 TPB
  - 10 = Data wait of 3 TPB; multiplexed address phase of 3 TPB
  - 01 = Data wait of 2 TPB; multiplexed address phase of 2 TPB
  - 00 = Data wait of 1 TPB; multiplexed address phase of 1 TPB (default)
  - Note 1: Whenever WAITM<3:0> = 0000, WAITB and WAITE bits are ignored and forced to 1 ΤΡΒCLΚ cycle for a write operation; WAITB = 1 ΤΡΒCLΚ cycle, WAITE = 0 ΤΡΒCLΚ cycles for a read operation.
    - 2: Address bit A14 is not subject to auto-increment/decrement if configured as Chip Select CS1.
    - **3:** These bits only control generating the Parallel Master Port (PMP) interrupt. The Parallel Master Port Error (PMPE) is always generated.

#### REGISTER 20-2: PMMODE: PARALLEL PORT MODE REGISTER (CONTINUED)

```
WAITM<3:0>: Data Read/Write Strobe Wait States bits(1)
bit 5-2
          1111 = Wait of 16 TPB
          0001 = Wait of 2 TPB
          0000 = Wait of 1 TPB (default)
          WAITE<1:0>: Data Hold After Read/Write Strobe Wait States bits(1)
bit 1-0
          11 = Wait of 4 TPB
          10 = Wait of 3 TPB
          01 = Wait of 2 TPB
          00 = Wait of 1 TPB (default)
          For Read operations:
          11 = Wait of 3 TPB
          10 = Wait of 2 TPB
          01 = Wait of 1 TPB
          00 = Wait of 0 TpB (default)
```

- Note 1: Whenever WAITM<3:0> = 0000, WAITB and WAITE bits are ignored and forced to 1 ΤΡΒCLΚ cycle for a write operation; WAITB = 1 ΤΡΒCLΚ cycle, WAITE = 0 ΤΡΒCLΚ cycles for a read operation.
  - 2: Address bit A14 is not subject to auto-increment/decrement if configured as Chip Select CS1.
  - **3:** These bits only control generating the Parallel Master Port (PMP) interrupt. The Parallel Master Port Error (PMPE) is always generated.

#### REGISTER 20-3: PMADDR: PARALLEL PORT ADDRESS REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31:24	_	_	_	_	_	_	_	_
00:40	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23:16	_	_		_		_		
	U-0	R/W-0	U-0	U-0	U-0	R/W-0	R/W-0	R/W-0
15:8		CS1 <sup>(1)</sup>					ADDD 440.05	
	_	ADDR14 <sup>(2)</sup>	_	_	_		ADDR<10:8>	
7:0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
				ADDR:	<7:0>			

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-15 Unimplemented: Read as '0'

bit 14 CS1: Chip Select 1 bit<sup>(1)</sup>

1 = Chip Select 1 is active0 = Chip Select 1 is inactive

bit 14 ADDR<14>: Destination Address bit 14<sup>(2)</sup>

bit 13-11 Unimplemented: Read as '0'

bit 10-0 ADDR<10:0>: Destination Address bits

Note 1: When the CSF<1:0> bits (PMCON<7:6>) = 10.

**2:** When the CSF<1:0> bits (PMCON<7:6>) = 00 or 01.

#### REGISTER 20-4: PMAEN: PARALLEL PORT PIN ENABLE REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0                U-0							
31:24	_	-	-	-	-	1	-	_
00:40	U-0                U-0							
23:16	_	_	_	_	_	_	_	_
45.0	U-0	R/W-0	U-0	U-0	U-0	R/W-0	R/W-0	R/W-0
15:8	_	PTEN14	_	_	_		PTEN<10:8>	
7.0	R/W-0              R/W-0							
7:0				PTEN	<7:0>			

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-15 Unimplemented: Read as '0'

bit 15-14 PTEN14: PMCS1 Address Port Enable bits

1 = PMA14 functions as either PMA14 or PMCS1<sup>(1)</sup>

0 = PMA14 functions as port I/O

bit 13-11 Unimplemented: Read as '0'

bit 10-2 PTEN<10:2>: PMP Address Port Enable bits

1 = PMA<10:2> function as PMP address lines

0 = PMA<10:2> function as port I/O

bit 1-0 PTEN<1:0>: PMALH/PMALL Address Port Enable bits

1 = PMA1 and PMA0 function as either PMA<1:0> or PMALH and PMALL(2)

0 = PMA1 and PMA0 pads functions as port I/O

Note 1: The use of this pin as PMA14 or CS1 is selected by the CSF<1:0> bits in the PMCON register.

2: The use of these pins as PMA1/PMA0 or PMALH/PMALL depends on the Address/Data Multiplex mode selected by bits ADRMUX<1:0> in the PMCON register.

#### REGISTER 20-5: PMSTAT: PARALLEL PORT STATUS REGISTER (SLAVE MODES ONLY)

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0                U-0							
31:24	_		_	_	_	_		_
00:40	U-0                U-0							
23:16	_	_	_	_	_	_	_	_
45.0	R-0	R/W-0, HS, SC	U-0	U-0	R-0	R-0	R-0	R-0
15:8	IBF	IBOV	_	_	IB3F	IB2F	IB1F	IB0F
7.0	R-1	R/W-0, HS, SC	U-0	U-0	R-1	R-1	R-1	R-1
7:0	OBE	OBUF	_	_	OB3E	OB2E	OB1E	OB0E

Legend:HS = Hardware SetSC = Cleared by SoftwareR = Readable bitW = Writable bitU = Unimplemented bit, read as '0'-n = Value at POR'1' = Bit is set'0' = Bit is clearedx = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

bit 15 IBF: Input Buffer Full Status bit

1 = All writable input buffer registers are full

0 = Some or all of the writable input buffer registers are empty

bit 14 **IBOV:** Input Buffer Overflow Status bit (1)

1 = A write attempt to a full input byte buffer occurred (must be cleared in software)

0 = No overflow occurred

bit 13-12 Unimplemented: Read as '0'

bit 11-8 IBxF: Input Buffer 'x' Status Full bits

1 = Input Buffer contains data that has not been read (reading buffer will clear this bit)

0 = Input Buffer does not contain any unread data

bit 7 OBE: Output Buffer Empty Status bit

1 = All readable output buffer registers are empty

0 = Some or all of the readable output buffer registers are full

bit 6 **OBUF:** Output Buffer Underflow Status bit <sup>(1)</sup>

1 = A read occurred from an empty output byte buffer (must be cleared in software)

0 = No underflow occurred

bit 5-4 Unimplemented: Read as '0'

bit 3-0 **OBxE:** Output Buffer 'x' Status Empty bits

1 = Output buffer is empty (writing data to the buffer will clear this bit)

0 = Output buffer contains data that has not been transmitted

Note 1: This will generate a PMPE - Parallel Master Port Error interrupt.

	20/30	// <del></del> -	1 AWII	
NOTES:				

## 21.0 REAL-TIME CLOCK AND CALENDAR (RTCC)

Note:


This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To complement the information in this data sheet, refer to Section 29. "Real-Time Clock and Calendar (RTCC)" (DS60001125), which is available from the Documentation > Reference Manual section of the Microchip PIC32 web site (www.microchip.com/pic32).

The PIC32 RTCC module is intended for applications in which accurate time must be maintained for extended periods of time with minimal or no CPU intervention. Low-power optimization provides extended battery lifetime while keeping track of time.

Following are some of the key features of this module:

- · Time: hours, minutes and seconds
- 24-hour format (military time)
- · Visibility of one-half second period
- · Provides calendar: day, date, month and year
- Alarm intervals are configurable for half of a second, one second, 10 seconds, one minute, 10 minutes, one hour, one day, one week, one month and one year
- · Alarm repeat with decrementing counter
- · Alarm with indefinite repeat: Chime
- Year range: 2000 to 2099
- · Leap year correction
- · BCD format for smaller firmware overhead
- · Optimized for long-term battery operation
- · Fractional second synchronization
- User calibration of the clock crystal frequency with auto-adjust
- Calibration range: ±0.66 seconds error per month
- · Calibrates up to 260 ppm of crystal error
- Requirements: External 32.768 kHz clock crystal
- Alarm pulse or seconds clock output on RTCC pin

#### FIGURE 21-1: RTCC BLOCK DIAGRAM



21.1 RTCC Control Registers
TABLE 21-1: RTCC REGISTER MAP

S	steseЯ IIA	0000	0000	0000	0000	XXXX	00xx	XXXX	00xx	XXXX	00xx	00xx	x0xx	r more
	16/0		RTCOE	I			Ι		V		I		<u>^</u>	gisters" fo
	1//1		<b>1ALFSEC</b>	I		3:0>	I	1<3:0>	WDAY01<2:0>	3:0>	I	1<3:0>	WDAY01<2:0>	nd INV Reg
	18/2		RTCSYNC	I		MIN01<3:0>	I	MONTH01<3:0>	JW	MIN01<3:0>	I	MONTH01<3:0>	W	CLR, SET a
	19/3		RTCWREN RTCSYNC HALFSEC	I	<7:0>		I		1		1		ı	ection 11.2 "
	20/4	CAL<9:0>	I	I	ARPT<7:0>		I	MONTH10	I		I	MONTH10	I	ively. See Se
	21/5	CAL	I	I		MIN10<2:0>	Ι	Ι	I	MIN10<2:0>	I	I	1	C, respecti
	22/6		RTCCLKON	I		Σ	I	Ι	I	M	I	I	I	, 0x8 and 0x
Bits	23/7		RTSECSEL RTCCLKON	I		ı	I	Ι	I	I	I	I	I	'0'. Reset values are shown in hexadecimal. INV registers at its virtual address, plus an offset of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for more
	24/8		I	I								I		nexadecima ss, plus an
	25/9		ı	I	<3:0>	3:0>	<3:0>	1<3:0>	<3:0>	:3:0>	<3:0>	ı	<3:0>	shown in h tual addres
	26/10	1	I	I	AMASK<3:0>	HR01<3:0>	SEC01<3:0>	YEAR01<3:0>	DAY01<3:0>	HR01<3:0>	SEC01<3:0>	I	DAY01<3:0>	values are ers at its vir
	27/11	1	I	I								I	•	
	28/12	1	I	I	ALRMSYNC	HR10<1:0>	Δ		DAY10<1:0>	HR10<1:0>	Δ	I		x = unknown value on Reset; — = unimplemented, read as '0'. Reset values are shown in hexadecimal All registers in this table have corresponding CLR, SET and INV registers at its virtual address, plus an o
	29/13	1	SIDL	I	/ NI	HR10	SEC10<2:0>	YEAR10<3:0>	DAY1	HR10	SEC10<2:0>	I	DAY10<3:0>	unimpleme sponding C
	30/14	I	I	I	CHIME	I		YEAR	I	Ι	,	I	DAY1	Reset; — = have corre
	31/15	I	NO	I	ALRMEN	I	I		I	I	I	I		value on F n this table
•	Bit Range	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	x = unknown All registers i
	Register Name <sup>(1)</sup>	I COL		LAG IVOTO	N CALRIM			DTODATE		TAMETINAL IN		TTV C140	שבאוווטאו ב	
ssə	Virtual Addr (#_0878)		00200		07 10		0220	0220		0,00	0240	0360	0000	Legend: Note 1

DS60001168L-page 204

#### REGISTER 21-1: RTCCON: RTC CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0	U-0	U-0	U-0	U-0	U-0	R/W-0	R/W-0
31:24	_	_	_	_	_	_	CAL<9	):8>
00.40	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
23:16				CAL<	7:0>			
45.0	R/W-0	U-0	R/W-0	U-0	U-0	U-0	U-0	U-0
15:8	ON <sup>(1,2)</sup>	_	SIDL	_	_	_	_	_
7.0	R/W-0	R-0	U-0	U-0	R/W-0	R-0	R-0	R/W-0
7:0	RTSECSEL <sup>(3)</sup>	RTCCLKON	_	_	RTCWREN <sup>(4)</sup>	RTCSYNC	HALFSEC <sup>(5)</sup>	RTCOE

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-26 Unimplemented: Read as '0'

bit 25-16 CAL<9:0>: RTC Drift Calibration bits, which contain a signed 10-bit integer value

0111111111 = Maximum positive adjustment, adds 511 RTC clock pulses every one minute

•

.

000000001 = Minimum positive adjustment, adds 1 RTC clock pulse every one minute

0000000000 = No adjustment

111111111 = Minimum negative adjustment, subtracts 1 RTC clock pulse every one minute

•

100000000 = Maximum negative adjustment, subtracts 512 clock pulses every one minute

bit 15 **ON:** RTCC On bit<sup>(1,2)</sup>

1 = RTCC module is enabled

0 = RTCC module is disabled

bit 14 Unimplemented: Read as '0'

bit 13 SIDL: Stop in Idle Mode bit

1 = Disables the PBCLK to the RTCC when the device enters Idle mode

0 = Continue normal operation when the device enters Idle mode

bit 12-8 Unimplemented: Read as '0'

bit 7 RTSECSEL: RTCC Seconds Clock Output Select bit (3)

1 = RTCC Seconds Clock is selected for the RTCC pin

0 = RTCC Alarm Pulse is selected for the RTCC pin

bit 6 RTCCLKON: RTCC Clock Enable Status bit

1 = RTCC Clock is actively running

0 = RTCC Clock is not running

**Note 1:** The ON bit is only writable when RTCWREN = 1.

- 2: When using the 1:1 PBCLK divisor, the user's software should not read/write the peripheral's SFRs in the SYSCLK cycle immediately following the instruction that clears the module's ON bit.
- 3: Requires RTCOE = 1 (RTCCON<0>) for the output to be active.
- 4: The RTCWREN bit can be set only when the write sequence is enabled.
- 5: This bit is read-only. It is cleared to '0' on a write to the seconds bit fields (RTCTIME<14:8>).

#### REGISTER 21-1: RTCCON: RTC CONTROL REGISTER (CONTINUED)

- bit 5-4 Unimplemented: Read as '0'
- bit 3 RTCWREN: RTC Value Registers Write Enable bit (4)
  - 1 = RTC Value registers can be written to by the user
  - 0 = RTC Value registers are locked out from being written to by the user
- bit 2 RTCSYNC: RTCC Value Registers Read Synchronization bit
  - 1 = RTC Value registers can change while reading, due to a rollover ripple that results in an invalid data read If the register is read twice and results in the same data, the data can be assumed to be valid
  - 0 = RTC Value registers can be read without concern about a rollover ripple
- bit 1 HALFSEC: Half-Second Status bit (5)
  - 1 = Second half period of a second
  - 0 = First half period of a second
- bit 0 RTCOE: RTCC Output Enable bit
  - 1 = RTCC clock output enabled clock presented onto an I/O
  - 0 = RTCC clock output disabled
- **Note 1:** The ON bit is only writable when RTCWREN = 1.
  - 2: When using the 1:1 PBCLK divisor, the user's software should not read/write the peripheral's SFRs in the SYSCLK cycle immediately following the instruction that clears the module's ON bit.
  - 3: Requires RTCOE = 1 (RTCCON<0>) for the output to be active.
  - **4:** The RTCWREN bit can be set only when the write sequence is enabled.
  - 5: This bit is read-only. It is cleared to '0' on a write to the seconds bit fields (RTCTIME<14:8>).

#### REGISTER 21-2: RTCALRM: RTC ALARM CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31.24	_	_	_		1		_	-
00.40	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23:16	_	_	_	_		_	_	_
45.0	R/W-0	R/W-0	R/W-0	R-0	R/W-0	R/W-0	R/W-0	R/W-0
15:8	ALRMEN <sup>(1,2)</sup>	CHIME <sup>(2)</sup>	PIV <sup>(2)</sup>	ALRMSYNC <sup>(3)</sup>		AMASK	<3:0> <sup>(2)</sup>	
7.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
7:0				ARPT<7:0	>(2)			

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 **Unimplemented:** Read as '0'

bit 15 **ALRMEN:** Alarm Enable bit<sup>(1,2)</sup>

1 = Alarm is enabled

0 = Alarm is disabled

bit 14 **CHIME**: Chime Enable bit<sup>(2)</sup>

1 = Chime is enabled – ARPT<7:0> is allowed to rollover from 0x00 to 0xFF

0 = Chime is disabled – ARPT<7:0> stops once it reaches 0x00

bit 13 PIV: Alarm Pulse Initial Value bit<sup>(2)</sup>

When ALRMEN = 0, PIV is writable and determines the initial value of the Alarm Pulse.

When ALRMEN = 1, PIV is read-only and returns the state of the Alarm Pulse.

- bit 12 **ALRMSYNC:** Alarm Sync bit<sup>(3)</sup>
  - 1 = ARPT<7:0> and ALRMEN may change as a result of a half second rollover during a read.

    The ARPT must be read repeatedly until the same value is read twice. This must be done since multiple bits may be changing, which are then synchronized to the PB clock domain
  - 0 = ARPT<7:0> and ALRMEN can be read without concerns of rollover because the prescaler is > 32 RTC clocks away from a half-second rollover
- bit 11-8 AMASK<3:0>: Alarm Mask Configuration bits(2)

0000 = Every half-second

0001 = Every second

0010 = Every 10 seconds

0011 = Every minute

0100 = Every 10 minutes

0101 = Every hour

0110 = Once a day

0111 = Once a week

1000 = Once a month

1001 = Once a year (except when configured for February 29, once every four years)

1010 = Reserved; do not use

1011 = Reserved; do not use

11xx = Reserved; do not use

- **Note 1:** Hardware clears the ALRMEN bit anytime the alarm event occurs, when ARPT<7:0> = 00 and CHIME = 0.
  - 2: This field should not be written when the RTCC ON bit = '1' (RTCCON<15>) and ALRMSYNC = 1.
  - 3: This assumes a CPU read will execute in less than 32 PBCLKs.

#### REGISTER 21-2: RTCALRM: RTC ALARM CONTROL REGISTER (CONTINUED)

bit 7-0 ARPT<7:0>: Alarm Repeat Counter Value bits<sup>(2)</sup>

11111111 = Alarm will trigger 256 times

•

00000000 = Alarm will trigger one time

The counter decrements on any alarm event. The counter only rolls over from 0x00 to 0xFF if CHIME = 1.

- Note 1: Hardware clears the ALRMEN bit anytime the alarm event occurs, when ARPT<7:0> = 00 and CHIME = 0.
  - 2: This field should not be written when the RTCC ON bit = '1' (RTCCON<15>) and ALRMSYNC = 1.
  - 3: This assumes a CPU read will execute in less than 32 PBCLKs.

#### REGISTER 21-3: RTCTIME: RTC TIME VALUE REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0	U-0	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
31:24	_	_	HR10	<1:0>		HR01	<3:0>	
22.46	U-0	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
23:16			MIN10<2:0>			MIN01	<3:0>	
45.0	U-0	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
15:8	_		SEC10<2:0>			SEC01	<3:0>	
7.0	U-0                U-0							
7:0	_	_	_	_	_		_	_

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-30 Unimplemented: Read as '0'

bit 29-28 HR10<1:0>: Binary-Coded Decimal Value of Hours bits, 10s place digit; contains a value from 0 to 2

bit 27-24 **HR01<3:0>:** Binary-Coded Decimal Value of Hours bits, 1s place digit; contains a value from 0 to 9

bit 23 Unimplemented: Read as '0'

bit 22-20 MIN10<2:0>: Binary-Coded Decimal Value of Minutes bits, 10s place digit; contains a value from 0 to 5

bit 19-16 MIN01<3:0>: Binary-Coded Decimal Value of Minutes bits, 1s place digit; contains a value from 0 to 9

bit 15 Unimplemented: Read as '0'

bit 14-12 SEC10<2:0>: Binary-Coded Decimal Value of Seconds bits, 10s place digit; contains a value from 0 to 5

bit 11-8 SEC01<3:0>: Binary-Coded Decimal Value of Seconds bits, 1s place digit; contains a value from 0 to 9

bit 7-0 Unimplemented: Read as '0'

**Note:** This register is only writable when RTCWREN = 1 (RTCCON<3>).

#### REGISTER 21-4: RTCDATE: RTC DATE VALUE REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	R/W-x              R/W-x							
31:24		YEAR1	0<3:0>			YEAR0	1<3:0>	
00.40	U-0	U-0	U-0	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
23:16		_	_	MONTH10		MONTH	01<3:0>	
45.0	U-0	U-0	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
15:8	_	_	DAY10	)<1:0>		DAY01	<3:0>	
7.0	U-0	U-0	U-0	U-0	U-0	R/W-x	R/W-x	R/W-x
7:0	_	_	_	_	_	V	VDAY01<2:0	>

#### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-28 YEAR10<3:0>: Binary-Coded Decimal Value of Years bits, 10s place digit; contains a value from 0 to 9

bit 27-24 YEAR01<3:0>: Binary-Coded Decimal Value of Years bits, 1s place digit; contains a value from 0 to 9

bit 23-21 Unimplemented: Read as '0'

bit 20 MONTH10: Binary-Coded Decimal Value of Months bits, 10s place digit; contains a value of 0 or 1

bit 19-16 MONTH01<3:0>: Binary-Coded Decimal Value of Months bits, 1s place digit; contains a value from 0 to 9

bit 15-14 Unimplemented: Read as '0'

bit 13-12 DAY10<1:0>: Binary-Coded Decimal Value of Days bits, 10s place digit; contains a value of 0 to 3

bit 11-8 DAY01<3:0>: Binary-Coded Decimal Value of Days bits, 1s place digit; contains a value from 0 to 9

bit 7-3 Unimplemented: Read as '0'

bit 2-0 WDAY01<2:0>: Binary-Coded Decimal Value of Weekdays bits; contains a value from 0 to 6

**Note:** This register is only writable when RTCWREN = 1 (RTCCON<3>).

#### REGISTER 21-5: ALRMTIME: ALARM TIME VALUE REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0	U-0	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
31:24	_	_	HR10	<1:0>		HR01	<3:0>	
00:40	U-0	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
23:16			MIN10<2:0>			MIN01	<3:0>	
45.0	U-0	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
15:8	_		SEC10<2:0>			SEC01	<3:0>	
7.0	U-0                U-0							
7:0		_	_	_	_	_	_	_

Lea	eı	าd:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-30 Unimplemented: Read as '0'

bit 29-28 HR10<1:0>: Binary Coded Decimal value of hours bits, 10s place digit; contains a value from 0 to 2

bit 27-24 HR01<3:0>: Binary Coded Decimal value of hours bits, 1s place digit; contains a value from 0 to 9

bit 23 Unimplemented: Read as '0'

bit 22-20 MIN10<2:0>: Binary Coded Decimal value of minutes bits, 10s place digit; contains a value from 0 to 5

bit 19-16 MIN01<3:0>: Binary Coded Decimal value of minutes bits, 1s place digit; contains a value from 0 to 9

bit 15 Unimplemented: Read as '0'

bit 14-12 SEC10<2:0>: Binary Coded Decimal value of seconds bits, 10s place digit; contains a value from 0 to 5

bit 11-8 SEC01<3:0>: Binary Coded Decimal value of seconds bits, 1s place digit; contains a value from 0 to 9

bit 7-0 **Unimplemented:** Read as '0'

#### REGISTER 21-6: ALRMDATE: ALARM DATE VALUE REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.04	U-0                U-0							
31:24	_	_	_	_	_	_	_	_
00.40	U-0	U-0	U-0	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
23:16	_		-	MONTH10		MONTH	01<3:0>	
45.0	U-0	U-0	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
15:8	_	_	DAY1	0<1:0>		DAY01	<3:0>	
7.0	U-0	U-0	U-0	U-0	U-0	R/W-x	R/W-x	R/W-x
7:0	_	_	_	_	_	V	VDAY01<2:0	>

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-21 Unimplemented: Read as '0'

bit 20 MONTH10: Binary Coded Decimal value of months bits, 10s place digit; contains a value of 0 or 1

bit 19-16 MONTH01<3:0>: Binary Coded Decimal value of months bits, 1s place digit; contains a value from 0 to 9

bit 15-14 Unimplemented: Read as '0'

bit 13-12 DAY10<1:0>: Binary Coded Decimal value of days bits, 10s place digit; contains a value from 0 to 3

bit 11-8 DAY01<3:0>: Binary Coded Decimal value of days bits, 1s place digit; contains a value from 0 to 9

bit 7-3 Unimplemented: Read as '0'

bit 2-0 WDAY01<2:0>: Binary Coded Decimal value of weekdays bits; contains a value from 0 to 6

## 22.0 10-BIT ANALOG-TO-DIGITAL CONVERTER (ADC)

Note: This of t

This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To complement the information in this data sheet, refer to Section 17. "10-bit Analog-to-Digital Converter (ADC)" (DS60001104), which is available from the Documentation > Reference Manual section of the Microchip PIC32 web site (www.microchip.com/pic32).


The 10-bit Analog-to-Digital Converter (ADC) includes the following features:

- Successive Approximation Register (SAR) conversion
- · Up to 1 Msps conversion speed

- · Up to 13 analog input pins
- · External voltage reference input pins
- One unipolar, differential Sample and Hold Amplifier (SHA)
- · Automatic Channel Scan mode
- · Selectable conversion trigger source
- · 16-word conversion result buffer
- Selectable buffer fill modes
- · Eight conversion result format options
- · Operation during Sleep and Idle modes

A block diagram of the 10-bit ADC is illustrated in Figure 22-1. Figure 22-2 illustrates a block diagram of the ADC conversion clock period. The 10-bit ADC has up to 13 analog input pins, designated AN0-AN12. In addition, there are two analog input pins for external voltage reference connections. These voltage reference inputs may be shared with other analog input pins and may be common to other analog module references.

#### FIGURE 22-1: ADC1 MODULE BLOCK DIAGRAM



- Note 1: VREF+ and VREF- inputs can be multiplexed with other analog inputs.
  - 2: The AN8 pin is only available on 44-pin devices. The AN6 and AN7pins are not available on 28-pin devices. The AN12 pin is available on all General Purpose Devices as well as 36 and 44 pin USB Devices.
  - 3: Connected to the CTMU module. See Section 25.0 "Charge Time Measurement Unit (CTMU)" for more information.
  - 4: Internal precision voltage reference (1.2V).

#### FIGURE 22-2: ADC CONVERSION CLOCK PERIOD BLOCK DIAGRAM




TABLE 22-1: ADC REGISTER MAP **ADC Control Registers** 

(#	_									200	0								
Virtual Add #_0878)	Register Name	Bit Range	31/15	30/14	29/13	28/12	27/11	26/10	25/9	24/8	23/7	22/6	21/5	20/4	19/3	18/2	1//1	16/0	steseЯ IIA
0000	(1) FINOUT (1)	31:16	I	I	I	I	Ι	Ι	I	I	I	I	I	Ι	I	Ι	I	I	0000
0000	, CONTO	15:0	NO	1	SIDL	Ι	-	F	FORM<2:0>			SSRC<2:0>		CLRASAM	-	ASAM	SAMP	DONE	0000
010	9010 AD1CON2(1) 31:16	31:16	Ι	1	1	1	Ι	Ι	1	Ι	I	I	1	Ι	Ι	Ι	I	1	0000
2	20010	15:0	/	VCFG<2:0>		OFFCAL	Ι	CSCNA	1	Ι	BUFS	I		SMPI<3:0>	<3:0>		BUFM	ALTS	0000
0000	(1)ENOD10		1	1	_	1	1	1	1	1	I	1	1	1	1	1	I	1	0000
2070		15:0	ADRC	I	1		0)	SAMC<4:0>						ADCS<7:0>	<7:0>				0000
9040	AD1CHS <sup>(1)</sup>	` '	CHONB	I	ı	I		CH0SB<3:0>	<3:0>		CHONA	I	Ι	I		CH0SA<3:0>	<3:0>		0000
		15:0	ı	I	ı	I	I	I	I	I	I	I	1	I	I	I	I	1	0000
9050 A	AD1CSSL <sup>(1)</sup> 31:16 15:0	31:16 15:0	CSSL15	CSSL14	CSSL13	CSSL12	CSSL11	CSSL10	CSSL9	CSSL8	CSSL7	CSSL6	CSSL5	CSSL4	CSSL3	CSSL2	CSSL1	CSSL0	0000
9070	ADC1BUF0	31:16						1	ADC Resu	ult Word 0 (	ADC Result Word 0 (ADC1BUF0<31:0>)	)<31:0>)							0000
9080	ADC1BUF1	31:16							ADC Resu	ult Word 1 (	ADC Result Word 1 (ADC1BUF1<31:0>)	1<31:0>)							0000
d 0606	ADC1BUF2	31:16							ADC Resu	ult Word 2 (	ADC Result Word 2 (ADC1BUF2<31:0>)	2<31:0>)							0000
90A0	ADC1BUF3	31:16 15:0							ADC Resu	ult Word 3 (	ADC Result Word 3 (ADC1BUF3<31:0>)	3<31:0>)							0000
9080 4	ADC1BUF4	31:16 15:0							ADC Resu	ult Word 4 (	ADC Result Word 4 (ADC1BUF4<31:0>)	4<31:0>)							0000
90C0	ADC1BUF5	31:16							ADC Resu	ult Word 5 (	ADC Result Word 5 (ADC1BUF5<31:0>)	5<31:0>)							0000
⊌ 0006	ADC1BUF6	31:16 15:0							ADC Resu	ult Word 6 (	ADC Result Word 6 (ADC1BUF6<31:0>)	3<31:0>)							0000
90E0 A	ADC1BUF7	31:16 15:0							ADC Resu	ult Word 7 (	ADC Result Word 7 (ADC1BUF7<31:0>)	7<31:0>)							0000
90F0 A	ADC1BUF8	31:16 15:0							ADC Resu	ult Word 8 (	ADC Result Word 8 (ADC1BUF8<31:0>)	3<31:0>)							0000
9100	ADC1BUF9								ADC Resu	ult Word 9 (	ADC Result Word 9 (ADC1BUF9<31:0>)	9<31:0>)							0000
9110	ADC1BUFA	31:16							ADC Resu	ult Word A (.	ADC Result Word A (ADC1BUFA<31:0>)	4<31:0>)							0000

© 2011-2019 Microchip Technology Inc.

TAE	<b>TABLE 22-1</b> :		C REG	STER 1	ADC REGISTER MAP (CONTIN	ONITNO	UED)												
ssə		€								Bits	s,								s
Virtual Addr (#_0878)	Register Name	Bit Range	31/15	30/14	29/13	28/12	27/11	26/10	25/9	24/8	23/7	22/6	21/5	20/4	19/3	18/2	17/1	16/0	Peset
5		31:16							700	/ G P20/VV #1	10C 401 IEE	(20.00)							0000
9 20	9120 ADCIBULE	15:0							ADC Resi	ADC Result Word B (ADC IBOFB 31:03)	ADCIBUL	(<0.15>6							0000
04.30	9130 ADC1BLIEC	31:16							ADC Bost	ADC Besult Word C (ADC18) IEC/31:07)	ADC1811EC	/34.0~)						0	0000
5		15:0							אביו הקע	) piow iii	חסו אפר	(10:10/1						O	0000
5	04.40 APC4BLIED	31:16							700	(10.12.70.1) (10.12.01.1) (10.12.01.1)	70010	170.167						0	0000
9 - -	ADCIBOTO	15:0							ADC Resi	) II wold D	ADCIBUL	(>0.16>0						O	0000
04.50	0150 ADC181155	31:16							ייים טטע	(10.15.23.16.70.4) Inches 15.00.4	אם ופרטטע	/24.07.)						0	0000
9		15:0							700	all word F		( ) ( ) ( )						U	0000
2	0460	31:16								/ L P P 7 / V 1 1 .	10,000	70.70						0	0000
00	T DGI DGE	15:0							ADC NES	ADC Result Wold F (ADC IBOTT 131.07)		(20.15)						O	0000
	1	- Inches			L - 1		1		all arrange has	In contract to a contract								=	

This register has corresponding CLR, SET and INV registers at its virtual address, plus offsets of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for details.  ${\bf x}$  = unknown value on Reset; — = unimplemented, read as '0'. Reset values are shown in hexadecimal.

#### REGISTER 22-1: AD1CON1: ADC CONTROL REGISTER 1

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.04	U-0	U-0						
31:24		_	_	_	_		_	_
22.46	U-0	U-0						
23:16		_	_	_	_		_	_
45.0	R/W-0	U-0	R/W-0	U-0	U-0	R/W-0	R/W-0	R/W-0
15:8	ON <sup>(1)</sup>	_	SIDL	_	_	F	FORM<2:0>	
7.0	R/W-0	R/W-0	R/W-0	R/W-0	U-0	R/W-0	R/W-0, HSC	R/C-0, HSC
7:0		SSRC<2:0>		CLRASAM	_	ASAM	SAMP <sup>(2)</sup>	DONE <sup>(3)</sup>

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

bit 15 **ON:** ADC Operating Mode bit<sup>(1)</sup>

1 = ADC module is operating

0 = ADC module is not operating

bit 14 Unimplemented: Read as '0'

bit 13 SIDL: Stop in Idle Mode bit

1 = Discontinue module operation when device enters Idle mode

0 = Continue module operation when the device enters Idle mode

bit 12-11 Unimplemented: Read as '0'

bit 10-8 FORM<2:0>: Data Output Format bits

111 = Signed Fractional 32-bit (DOUT = sddd dddd dd00 0000 0000 0000 0000)

101 = Signed Integer 32-bit (DOUT = ssss ssss ssss ssss ssss ssss dddd dddd)

100 = Integer 32-bit (DOUT = 0000 0000 0000 0000 0000 00dd dddd dddd)

011 = Signed Fractional 16-bit (DOUT = 0000 0000 0000 0000 sddd dddd dd00 0000)

010 = Fractional 16-bit (DOUT = 0000 0000 0000 0000 dddd dddd dd00 0000)

000 =Integer 16-bit (DOUT = 0000 0000 0000 0000 0000 00dd dddd dddd)

bit 7-5 SSRC<2:0>: Conversion Trigger Source Select bits

111 = Internal counter ends sampling and starts conversion (auto convert)

110 = Reserved

101 = Reserved

100 = Reserved

011 = CTMU ends sampling and starts conversion

010 = Timer 3 period match ends sampling and starts conversion

001 = Active transition on INT0 pin ends sampling and starts conversion

000 = Clearing SAMP bit ends sampling and starts conversion

**Note 1:** When using 1:1 PBCLK divisor, the user's software should not read/write the peripheral's SFRs in the SYSCLK cycle immediately following the instruction that clears the module's ON bit.

- 2: If ASAM = 0, software can write a '1' to start sampling. This bit is automatically set by hardware if ASAM = 1. If SSRC = 0, software can write a '0' to end sampling and start conversion. If SSRC ≠ '0', this bit is automatically cleared by hardware to end sampling and start conversion.
- 3: This bit is automatically set by hardware when analog-to-digital conversion is complete. Software can write a '0' to clear this bit (a write of '1' is not allowed). Clearing this bit does not affect any operation already in progress. This bit is automatically cleared by hardware at the start of a new conversion.

#### REGISTER 22-1: AD1CON1: ADC CONTROL REGISTER 1 (CONTINUED)

- bit 4 **CLRASAM:** Stop Conversion Sequence bit (when the first ADC interrupt is generated)
  - 1 = Stop conversions when the first ADC interrupt is generated. Hardware clears the ASAM bit when the ADC interrupt is generated.
  - 0 = Normal operation, buffer contents will be overwritten by the next conversion sequence
- bit 3 Unimplemented: Read as '0'
- bit 2 ASAM: ADC Sample Auto-Start bit
  - 1 = Sampling begins immediately after last conversion completes; SAMP bit is automatically set.
  - 0 = Sampling begins when SAMP bit is set
- bit 1 SAMP: ADC Sample Enable bit<sup>(2)</sup>
  - 1 = The ADC sample and hold amplifier is sampling
  - 0 = The ADC sample/hold amplifier is holding

When ASAM = 0, writing '1' to this bit starts sampling.

When SSRC = 000, writing '0' to this bit will end sampling and start conversion.

- bit 0 **DONE**: Analog-to-Digital Conversion Status bit<sup>(3)</sup>
  - 1 = Analog-to-digital conversion is done
  - 0 = Analog-to-digital conversion is not done or has not started

Clearing this bit will not affect any operation in progress.

- **Note 1:** When using 1:1 PBCLK divisor, the user's software should not read/write the peripheral's SFRs in the SYSCLK cycle immediately following the instruction that clears the module's ON bit.
  - **2:** If ASAM = 0, software can write a '1' to start sampling. This bit is automatically set by hardware if ASAM = 1. If SSRC = 0, software can write a '0' to end sampling and start conversion. If SSRC ≠ '0', this bit is automatically cleared by hardware to end sampling and start conversion.
  - **3:** This bit is automatically set by hardware when analog-to-digital conversion is complete. Software can write a '0' to clear this bit (a write of '1' is not allowed). Clearing this bit does not affect any operation already in progress. This bit is automatically cleared by hardware at the start of a new conversion.

#### REGISTER 22-2: AD1CON2: ADC CONTROL REGISTER 2

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0                U-0							
31.24	_	_	_	_	_	_	_	_
23:16	U-0                U-0							
23.10	_	_	_	_	_	_	_	_
15:8	R/W-0	R/W-0	R/W-0	R/W-0	U-0	R/W-0	U-0	U-0
15.6	VCFG<2:0>			OFFCAL	_	CSCNA	_	_
7:0	R-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
1.0	BUFS	_		SMP	I<3:0>		BUFM	ALTS

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

bit 15-13 VCFG<2:0>: Voltage Reference Configuration bits

	VREFH	VREFL
000	AVDD	AVss
001	External VREF+ pin	AVss
010	AVDD	External VREF- pin
011	External VREF+ pin	External VREF- pin
1xx	AVDD	AVss

- bit 12 **OFFCAL:** Input Offset Calibration Mode Select bit
  - 1 = Enable Offset Calibration mode

Positive and negative inputs of the sample and hold amplifier are connected to VREFL

0 = Disable Offset Calibration mode

The inputs to the sample and hold amplifier are controlled by AD1CHS or AD1CSSL

- bit 11 Unimplemented: Read as '0'
- bit 10 CSCNA: Input Scan Select bit
  - 1 = Scan inputs
  - 0 = Do not scan inputs
- bit 9-8 Unimplemented: Read as '0'
- bit 7 BUFS: Buffer Fill Status bit
  - Only valid when BUFM = 1.
  - 1 = ADC is currently filling buffer 0x8-0xF, user should access data in 0x0-0x7
  - 0 = ADC is currently filling buffer 0x0-0x7, user should access data in 0x8-0xF
- bit 6 Unimplemented: Read as '0'
- bit 5-2 SMPI<3:0>: Sample/Convert Sequences Per Interrupt Selection bits

1111 = Interrupts at the completion of conversion for each 16<sup>th</sup> sample/convert sequence

1110 = Interrupts at the completion of conversion for each 15<sup>th</sup> sample/convert sequence

0001 = Interrupts at the completion of conversion for each 2<sup>nd</sup> sample/convert sequence 0000 = Interrupts at the completion of conversion for each sample/convert sequence

- bit 1 BUFM: ADC Result Buffer Mode Select bit
  - 1 = Buffer configured as two 8-word buffers, ADC1BUF7-ADC1BUF0, ADC1BUFF-ADCBUF8
  - 0 = Buffer configured as one 16-word buffer ADC1BUFF-ADC1BUF0
- bit 0 ALTS: Alternate Input Sample Mode Select bit
  - 1 = Uses Sample A input multiplexer settings for first sample, then alternates between Sample B and Sample A input multiplexer settings for all subsequent samples
  - 0 = Always use Sample A input multiplexer settings

#### REGISTER 22-3: AD1CON3: ADC CONTROL REGISTER 3

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0		
24.04	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0		
31:24	_	_	_	-	_		_	_		
00.46	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0		
23:16	_	_	_	_	_	_	_	_		
45.0	R/W-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0		
15:8	ADRC	_	_	SAMC<4:0> <sup>(1)</sup>						
7.0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W	R/W-0		
7:0				ADCS<	7:0> <sup>(2)</sup>					

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

bit 15 ADRC: ADC Conversion Clock Source bit

1 = Clock derived from FRC

0 = Clock derived from Peripheral Bus Clock (PBCLK)

bit 14-13 Unimplemented: Read as '0'

bit 12-8 **SAMC<4:0>:** Auto-Sample Time bits<sup>(1)</sup>

11111 = **31** TAD

•

Ť

00001 = 1 TAD

00000 = 0 TAD (Not allowed)

bit 7-0 ADCS<7:0>: ADC Conversion Clock Select bits<sup>(2)</sup>

11111111 = TPB • 2 • (ADCS<7:0> + 1) = 512 • TPB = TAD

•

•

•

00000001 =TPB • 2 • (ADCS<7:0> + 1) = 4 • TPB = TAD 00000000 =TPB • 2 • (ADCS<7:0> + 1) = 2 • TPB = TAD

**Note 1:** This bit is only used if the SSRC<2:0> bits (AD1CON1<7:5>) = 111.

2: This bit is not used if the ADRC (AD1CON3<15>) bit = 1.

U = Unimplemented bit, read as '0'

x = Bit is unknown

#### REGISTER 22-4: AD1CHS: ADC INPUT SELECT REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0		
04.04	R/W-0	U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0		
31:24	CH0NB	_	_	-	CH0SB<3:0>					
00.40	R/W-0	U-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0		
23:16	CH0NA	_	_	_	CH0SA<3:0>					
45.0	U-0                U-0									
15:8	_	_	_	_	_	_	_	_		
7.0	U-0                U-0									
7:0	_	_	_	_		_	_	_		

-n = Value at POR '1' = Bit is set '0' = Bit is cleared

CH0NB: Negative Input Select bit for Sample B

1 = Channel 0 negative input is AN10 = Channel 0 negative input is VREFL

bit 30-28 Unimplemented: Read as '0'

bit 27-24 CH0SB<3:0>: Positive Input Select bits for Sample B

1111 = Channel 0 positive input is Open<sup>(1)</sup>

1110 = Channel 0 positive input is IVREF<sup>(2)</sup>

1101 = Channel 0 positive input is CTMU temperature sensor (CTMUT)<sup>(3)</sup>

W = Writable bit

1100 = Channel 0 positive input is AN12<sup>(4)</sup>

•

Legend:

bit 31

R = Readable bit

.

0001 = Channel 0 positive input is AN1

0000 = Channel 0 positive input is AN0

bit 23 **CHONA:** Negative Input Select bit for Sample A Multiplexer Setting<sup>(2)</sup>

1 = Channel 0 negative input is AN1

0 = Channel 0 negative input is VREFL

bit 22-20 Unimplemented: Read as '0'

bit 19-16 CH0SA<3:0>: Positive Input Select bits for Sample A Multiplexer Setting

1111 = Channel 0 positive input is Open(1)

1110 = Channel 0 positive input is IVREF(2)

1101 = Channel 0 positive input is CTMU temperature (CTMUT)(3)

1100 = Channel 0 positive input is AN12<sup>(4)</sup>

•

0001 = Channel 0 positive input is AN1

0000 = Channel 0 positive input is AN0

bit 15-0 Unimplemented: Read as '0'

Note 1: This selection is only used with CTMU capacitive and time measurement.

2: See Section 24.0 "Comparator Voltage Reference (CVREF)" for more information.

3: See Section 25.0 "Charge Time Measurement Unit (CTMU)" for more information.

**4:** The AN8 pin is only available on the 44-pin devices. The AN6 and AN7 pins are not available on the 28-pin devices. The AN12 pin is available on all General Purpose Devices as well as 36 and 44 pin USB Devices.

#### REGISTER 22-5: AD1CSSL: ADC INPUT SCAN SELECT REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.04	U-0                U-0							
31:24		_	_	-			_	_
22.46	U-0                U-0							
23:16	_	_	_	_	_	_	_	_
45.0	R/W-0              R/W-0							
15:8	CSSL15	CSSL14	CSSL13	CSSL12	CSSL11	CSSL10	CSSL9	CSSL8
7.0	R/W-0              R/W-0							
7:0	CSSL7	CSSL6	CSSL5	CSSL4	CSSL3	CSSL2	CSSL1	CSSL0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

bit 15-0 CSSL<15:0>: ADC Input Pin Scan Selection bits(1,2)

1 = Select ANx for input scan0 = Skip ANx for input scan

**Note 1:** CSSL = ANx, where 'x' = 0-12; CSSL13 selects CTMU input for scan; CSSL14 selects IVREF for scan; CSSL15 selects VSS for scan.

2: On devices with less than 13 analog inputs, all CSSLx bits can be selected; however, inputs selected for scan without a corresponding input on the device will convert to VREFL.

#### 23.0 COMPARATOR

Note: This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To complement the information in this data Section refer to "Comparator" (DS60001110), which is available from the Documentation > Reference Manual section the PIC32 Microchip web (www.microchip.com/pic32).


The Analog Comparator module contains three comparators that can be configured in a variety of ways.

Following are some of the key features of this module:

- · Selectable inputs available include:
  - Analog inputs multiplexed with I/O pins
  - On-chip internal absolute voltage reference (IVREF)
  - Comparator voltage reference (CVREF)
- · Outputs can be Inverted
- · Selectable interrupt generation

A block diagram of the comparator module is provided in Figure 23-1.

FIGURE 23-1: COMPARATOR BLOCK DIAGRAM



23.1 Comparator Control Registers
TABLE 23-1: COMPARATOR REGISTER MAP

S	steseR IIA	0000	0003	0000	0003	0000	0003	0000	0000	
	16/0	I	CCH<1:0>	_	CCH<1:0>	_	CCH<1:0>	_	C10UT	
	17/1	I	CCH	_	CCH	_	CCH	_	C2OUT	
	18/2	I	I	_	_	_	_	_	C3ONT	
	19/3	I	Ι	Ι	I	Ι	Ι	Ι	1	
	20/4	I	CREF	-	CREF	-	CREF	-	-	
	21/5	I	I	_	Ι	_	_	_	_	
	22/6	I	EVPOL<1:0>	_	EVPOL<1:0>	_	EVPOL<1:0>	_	-	
Bits	23/7	I	EVPO	-	EVPO	-	EVPO	-	-	
B	24/8	I	COUT	-	COUT	-	LOOD	-	-	
	25/9	I	I	_	-	_	_	_	_	I all according
	26/10	Ι	I	_	—	_	_	_	_	4
	27/11	I	Ι	Ι	I	Ι	Ι	Ι	1	
	28/12	I	I	-	Ι	-	-	-	-	
	29/13	I	CPOL	Ι	CPOL	Ι	CPOL	Ι	SIDL	
	30/14	I	COE	Ι	COE	Ι	COE	Ι	I	
	31/15	31:16 —	NO	1	NO	1	NO	1	1	
€	Bit Range		15:0	31:16	15:0	31:16	15:0	31:16	15:0	1
Register Name <sup>(1)</sup>				NOCKYO	COMMO	IACOCKAO			2000	
	Virtual Addr (#_0878)	000	4000	0.40	2	000	AUZO	0904	900	

All registers in this table have corresponding CLR, SET and INV registers at their virtual addresses, plus offsets of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for more information.

Note

#### REGISTER 23-1: CMXCON: COMPARATOR CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.04	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31:24	_	_	_	_	-	-	_	_
22.46	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23:16	_	_	_	_	-		_	_
45.0	R/W-0	R/W-0	R/W-0	U-0	U-0	U-0	U-0	R-0
15:8	ON <sup>(1)</sup>	COE	CPOL <sup>(2)</sup>	_	-	-	_	COUT
7.0	R/W-1	R/W-1	U-0	R/W-0	U-0	U-0	R/W-1	R/W-1
7:0	EVPOL	_<1:0>		CREF	_		CCH	<1:0>

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### bit 31-16 Unimplemented: Read as '0'

- bit 15 ON: Comparator ON bit<sup>(1)</sup>
  - 1 = Module is enabled. Setting this bit does not affect the other bits in this register
  - 0 = Module is disabled and does not consume current. Clearing this bit does not affect the other bits in this register
- bit 14 COE: Comparator Output Enable bit
  - 1 = Comparator output is driven on the output CxOUT pin
  - 0 = Comparator output is not driven on the output CxOUT pin
- bit 13 **CPOL:** Comparator Output Inversion bit<sup>(2)</sup>
  - 1 = Output is inverted
  - 0 = Output is not inverted
- bit 12-9 Unimplemented: Read as '0'
- bit 8 **COUT:** Comparator Output bit
  - 1 = Output of the Comparator is a '1'
  - 0 = Output of the Comparator is a '0'
- bit 7-6 **EVPOL<1:0>:** Interrupt Event Polarity Select bits
  - 11 = Comparator interrupt is generated on a low-to-high or high-to-low transition of the comparator output
  - 10 = Comparator interrupt is generated on a high-to-low transition of the comparator output
  - 01 = Comparator interrupt is generated on a low-to-high transition of the comparator output
  - 00 = Comparator interrupt generation is disabled
- bit 5 **Unimplemented:** Read as '0'
- bit 4 CREF: Comparator Positive Input Configure bit
  - 1 = Comparator non-inverting input is connected to the internal CVREF
  - 0 = Comparator non-inverting input is connected to the CxINA pin
- bit 3-2 **Unimplemented:** Read as '0'
- bit 1-0 CCH<1:0>: Comparator Negative Input Select bits for Comparator
  - 11 = Comparator inverting input is connected to the IVREF
  - 10 = Comparator inverting input is connected to the CxIND pin
  - 01 = Comparator inverting input is connected to the CxINC pin
  - 00 = Comparator inverting input is connected to the CxINB pin
- **Note 1:** When using the 1:1 PBCLK divisor, the user's software should not read/write the peripheral's SFRs in the SYSCLK cycle immediately following the instruction that clears the module's ON bit.
  - 2: Setting this bit will invert the signal to the comparator interrupt generator as well. This will result in an interrupt being generated on the opposite edge from the one selected by EVPOL<1:0>.

#### REGISTER 23-2: CMSTAT: COMPARATOR STATUS REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	U-0                U-0							
31.24	-	_	_	_			-	_
22.46	U-0                U-0							
23:16	_	_	_	_		_	_	_
15:8	U-0	U-0	R/W-0	U-0	U-0	U-0	U-0	U-0
15.6	_	_	SIDL	_		_	_	
7.0	U-0	U-0	U-0	U-0	U-0	R-0	R-0	R-0
7:0	_	_	_	_	_	C3OUT	C2OUT	C10UT

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-14 Unimplemented: Read as '0'

bit 13 SIDL: Stop in Idle Control bit

1 = All Comparator modules are disabled when the device enters Idle mode

0 = All Comparator modules continue to operate when the device enters Idle mode

bit 12-3 **Unimplemented:** Read as '0'

bit 2 C3OUT: Comparator Output bit

1 = Output of Comparator 3 is a '1'

0 = Output of Comparator 3 is a '0'

bit 1 C2OUT: Comparator Output bit

1 = Output of Comparator 2 is a '1'

0 = Output of Comparator 2 is a '0'

bit 0 C10UT: Comparator Output bit

1 = Output of Comparator 1 is a '1'

0 = Output of Comparator 1 is a '0'

# 24.0 COMPARATOR VOLTAGE REFERENCE (CVREF)

Note: This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To complement the information in this data sheet, refer to Section 20. "Comparator Voltage Reference (CVREF)" (DS60001109), which is available from the Documentation > Reference Manual

section of the Microchip PIC32 web site

The CVREF module is a 16-tap, resistor ladder network that provides a selectable reference voltage. Although its primary purpose is to provide a reference for the analog comparators, it also may be used independently of them.

(www.microchip.com/pic32).


The resistor ladder is segmented to provide two ranges of voltage reference values and has a power-down function to conserve power when the reference is not being used. The module's supply reference can be provided from either device VDD/Vss or an external voltage reference. The CVREF output is available for the comparators and typically available for pin output.

The comparator voltage reference has the following features:

- · High and low range selection
- · Sixteen output levels available for each range
- Internally connected to comparators to conserve device pins
- · Output can be connected to a pin

A block diagram of the module is shown in Figure 24-1.





# 24.1 Comparator Voltage Reference Control Register

**COMPARATOR VOLTAGE REFERENCE REGISTER MAP** 

9	Pll Resets	0000	0000	
	16/0	1		
	17/1	1	3:0>	
	18/2	1	CVR<3:0>	
	19/3	1		
	20/4	1	CVRSS	
	21/5	1	CVROE   CVRS	
	22/6	1	CVROE	
	23/7	1	_	
Bits	24/8		_	
	25/9	1	1	
	26/10	1	1	
	27/11	1	1	
	28/12	ı	I	
	29/13		_	
	30/14		_	
	31/15	1	NO	
€	Bit Range	31:16	15:0	
	Register Name <sup>(1)</sup>	14000	NONE NO	
SSƏ	Virtual Addr (#_0878)	9800 CV		

All registers in this table have corresponding CLR, SET and INV registers at their virtual addresses, plus offsets of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for more information.  ${
m x}$  = unknown value on Reset; — = unimplemented, read as '0'. Reset values are shown in hexadecimal. Legend:

DS60001168L-page 228

**TABLE 24-1**:

#### REGISTER 24-1: CVRCON: COMPARATOR VOLTAGE REFERENCE CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0                U-0							
31:24		_	_	_	_	_	_	_
00.40	U-0                U-0							
23:16		_	_	_	_	_	_	_
45.0	R/W-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
15:8	ON <sup>(1)</sup>	_	_	_	_	_	_	_
7.0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
7:0		CVROE	CVRR	CVRSS		CVR<	<3:0>	

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-16 Unimplemented: Read as '0'

bit 15 **ON:** Comparator Voltage Reference On bit<sup>(1)</sup>

1 = Module is enabled

Setting this bit does not affect other bits in the register.

0 = Module is disabled and does not consume current.

Clearing this bit does not affect the other bits in the register.

bit 14-7 Unimplemented: Read as '0'

bit 6 CVROE: CVREFOUT Enable bit

1 = Voltage level is output on CVREFOUT pin

0 = Voltage level is disconnected from CVREFOUT pin

bit 5 CVRR: CVREF Range Selection bit

1 = 0 to 0.67 CVRSRC, with CVRSRC/24 step size

0 = 0.25 CVRSRC to 0.75 CVRSRC, with CVRSRC/32 step size

bit 4 CVRSS: CVREF Source Selection bit

1 = Comparator voltage reference source, CVRSRC = (VREF+) - (VREF-)

0 = Comparator voltage reference source, CVRSRC = AVDD - AVSS

bit 3-0 **CVR<3:0>:** CVREF Value Selection  $0 \le CVR<3:0> \le 15$  bits

When CVRR = 1:

CVREF = (CVR<3:0>/24) • (CVRSRC)

When CVRR = 0:

CVREF = 1/4 • (CVRSRC) + (CVR<3:0>/32) • (CVRSRC)

**Note 1:** When using 1:1 PBCLK divisor, the user's software should not read/write the peripheral's SFRs in the SYSCLK cycle immediately following the instruction that clears the module's ON bit.

NOTES:			

# 25.0 CHARGE TIME MEASUREMENT UNIT (CTMU)

Note:

This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To complement the information in this data sheet, refer to **Section 37. "Charge Time Measurement Unit (CTMU)"** (DS60001167), which is available from the *Documentation > Reference Manual* section of the Microchip PIC32 web site (www.microchip.com/pic32).


The Charge Time Measurement Unit (CTMU) is a flexible analog module that has a configurable current source with a digital configuration circuit built around it. The CTMU can be used for differential time measurement between pulse sources and can be used for generating an asynchronous pulse. By working with other on-chip analog modules, the CTMU can be used for high resolution time measurement, measure capacitance, measure relative changes in capacitance or generate output pulses with a specific time delay. The CTMU is ideal for interfacing with capacitive-based sensors.

The CTMU module includes the following key features:

- Up to 13 channels available for capacitive or time measurement input
- · On-chip precision current source
- · 16-edge input trigger sources
- · Selection of edge or level-sensitive inputs
- · Polarity control for each edge source
- · Control of edge sequence
- · Control of response to edges
- · High precision time measurement
- Time delay of external or internal signal asynchronous to system clock
- · Integrated temperature sensing diode
- · Control of current source during auto-sampling
- · Four current source ranges
- · Time measurement resolution of one nanosecond

A block diagram of the CTMU is shown in Figure 25-1.





# **CTMU Control Registers** 25.1

9	steseR IIA	0000	0000	for
	16/0	1	IRNG<1:0>	egisters'
	17/1	1	IRNG	and INV R
	18/2			CLR, SET a
	19/3	EDG2SEL<3:0>		tion 11.2 '
	20/4	EDG28	:5:0>	/. See Sec
	21/5		ITRIM<5:0>	espectivel
	22/6	EDG2POL		3 and 0xC, r
	23/7	EDG2STAT EDG1STAT EDG2MOD EDG2POL		et of 0x4, 0x
Bits	24/8	EDG1STAT	CTTRIG	decimal. plus an offse
	25/9	<b>EDG2STAT</b>	IDISSEN	own in hexa al address,
	26/10		EDGEN EDGSEQEN IDISSEN	x = unknown value on Reset; — = unimplemented, read as '0'. Reset values are shown in hexadecimal.  All registers in this table have corresponding CLR, SET and INV registers at its virtual address, plus an offset of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for more information.
	27/11	1SEL<3:0>	EDGEN	s '0'. Reset d INV regis
	28/12	EDG18	TGEN	ted, read as LR, SET an
	29/13		CTMUSIDL	unimplemen esponding Cl
	30/14	EDG1POL	I	Reset; — =
	31/15	31:16 EDG1MOD EDG1POI	NO	n value on l in this tabl∉ ation.
•	Bit Range	31:16	15:0	<ul><li>= unknown valu</li><li>All registers in thi</li><li>nore information.</li></ul>
	Register Name <sup>(1)</sup>	N COLUMN		
	Virtual Addr (BF80_#)	000	AZOO	Legend: Note 1:

TABLE 25-1: CTMU REGISTER MAP

#### REGISTER 25-1: CTMUCON: CTMU CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
31.24	EDG1MOD	EDG1POL		EDG1S	EDG2STAT	EDG1STAT		
23:16	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	U-0	U-0
23.10	EDG2MOD	EDG2POL		EDG2S	EL<3:0>		_	_
15:8	R/W-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
15.6	ON	_	CTMUSIDL	TGEN <sup>(1)</sup>	EDGEN	EDGSEQEN	IDISSEN <sup>(2)</sup>	CTTRIG
7:0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
7.0				IRNG	<1:0>			

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31 EDG1MOD: Edge1 Edge Sampling Select bit

1 = Input is edge-sensitive

0 = Input is level-sensitive

bit 30 EDG1POL: Edge 1 Polarity Select bit

1 = Edge1 programmed for a positive edge response

0 = Edge1 programmed for a negative edge response

bit 29-26 EDG1SEL<3:0>: Edge 1 Source Select bits

1111 = C3OUT pin is selected

1110 = C2OUT pin is selected

1101 = C1OUT pin is selected

1100 = IC3 Capture Event is selected

1011 = IC2 Capture Event is selected

1010 = IC1 Capture Event is selected

1001 = CTED8 pin is selected

1000 = CTED7 pin is selected

0111 = CTED6 pin is selected

0110 = CTED5 pin is selected

0101 = CTED4 pin is selected

0100 = CTED3 pin is selected

0011 = CTED1 pin is selected

0010 = CTED2 pin is selected

0001 = OC1 Compare Event is selected

0000 = Timer1 Event is selected

bit 25 EDG2STAT: Edge2 Status bit

Indicates the status of Edge2 and can be written to control edge source

1 = Edge2 has occurred

0 = Edge2 has not occurred

- Note 1: When this bit is set for Pulse Delay Generation, the EDG2SEL<3:0> bits must be set to '1110' to select C2OUT.
  - 2: The ADC module Sample and Hold capacitor is not automatically discharged between sample/conversion cycles. Software using the ADC as part of a capacitive measurement, must discharge the ADC capacitor before conducting the measurement. The IDISSEN bit, when set to '1', performs this function. The ADC module must be sampling while the IDISSEN bit is active to connect the discharge sink to the capacitor array.
  - 3: Refer to the CTMU Current Source Specifications (Table 30-41) in Section 30.0 "Electrical Characteristics" for current values.
  - 4: This bit setting is not available for the CTMU temperature diode.

#### REGISTER 25-1: CTMUCON: CTMU CONTROL REGISTER (CONTINUED) EDG1STAT: Edge1 Status bit bit 24 Indicates the status of Edge1 and can be written to control edge source 1 = Edge1 has occurred 0 = Edge1 has not occurred bit 23 EDG2MOD: Edge2 Edge Sampling Select bit 1 = Input is edge-sensitive 0 = Input is level-sensitive bit 22 **EDG2POL:** Edge 2 Polarity Select bit 1 = Edge2 programmed for a positive edge response 0 = Edge2 programmed for a negative edge response bit 21-18 EDG2SEL<3:0>: Edge 2 Source Select bits 1111 = C3OUT pin is selected 1110 = C2OUT pin is selected 1101 = C1OUT pin is selected 1100 = PBCLK clock is selected 1011 = IC3 Capture Event is selected 1010 = IC2 Capture Event is selected 1001 = IC1 Capture Event is selected 1000 = CTED13 pin is selected 0111 = CTED12 pin is selected 0110 = CTED11 pin is selected 0101 = CTED10 pin is selected 0100 = CTED9 pin is selected 0011 = CTED1 pin is selected 0010 = CTED2 pin is selected 0001 = OC1 Compare Event is selected 0000 = Timer1 Event is selected bit 17-16 Unimplemented: Read as '0' bit 15 ON: ON Enable bit 1 = Module is enabled 0 = Module is disabled bit 14 Unimplemented: Read as '0' bit 13 CTMUSIDL: Stop in Idle Mode bit 1 = Discontinue module operation when the device enters Idle mode 0 = Continue module operation when the device enters Idle mode TGEN: Time Generation Enable bit(1) bit 12 1 = Enables edge delay generation 0 = Disables edge delay generation bit 11 **EDGEN:** Edge Enable bit 1 = Edges are not blocked 0 = Edges are blocked

- **Note 1:** When this bit is set for Pulse Delay Generation, the EDG2SEL<3:0> bits must be set to '1110' to select C2OUT.
  - 2: The ADC module Sample and Hold capacitor is not automatically discharged between sample/conversion cycles. Software using the ADC as part of a capacitive measurement, must discharge the ADC capacitor before conducting the measurement. The IDISSEN bit, when set to '1', performs this function. The ADC module must be sampling while the IDISSEN bit is active to connect the discharge sink to the capacitor array.
  - 3: Refer to the CTMU Current Source Specifications (Table 30-41) in Section 30.0 "Electrical Characteristics" for current values.
  - 4: This bit setting is not available for the CTMU temperature diode.

#### REGISTER 25-1: CTMUCON: CTMU CONTROL REGISTER (CONTINUED) EDGSEQEN: Edge Sequence Enable bit 1 = Edge1 must occur before Edge2 can occur 0 = No edge sequence is needed bit 9 IDISSEN: Analog Current Source Control bit(2) 1 = Analog current source output is grounded 0 = Analog current source output is not grounded bit 8 CTTRIG: Trigger Control bit 1 = Trigger output is enabled 0 = Trigger output is disabled bit 7-2 ITRIM<5:0>: Current Source Trim bits 011111 = Maximum positive change from nominal current 011110 000001 = Minimum positive change from nominal current 000000 = Nominal current output specified by IRNG<1:0> 111111 = Minimum negative change from nominal current 100010 100001 = Maximum negative change from nominal current IRNG<1:0>: Current Range Select bits<sup>(3)</sup> bit 1-0 11 = 100 times base current 10 = 10 times base current 01 = Base current level 00 = 1000 times base current<sup>(4)</sup>

- **Note 1:** When this bit is set for Pulse Delay Generation, the EDG2SEL<3:0> bits must be set to '1110' to select C2OUT.
  - 2: The ADC module Sample and Hold capacitor is not automatically discharged between sample/conversion cycles. Software using the ADC as part of a capacitive measurement, must discharge the ADC capacitor before conducting the measurement. The IDISSEN bit, when set to '1', performs this function. The ADC module must be sampling while the IDISSEN bit is active to connect the discharge sink to the capacitor array.
  - 3: Refer to the CTMU Current Source Specifications (Table 30-41) in Section 30.0 "Electrical Characteristics" for current values.
  - 4: This bit setting is not available for the CTMU temperature diode.

NOTES:			

#### 26.0 POWER-SAVING FEATURES

Note:

This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. It is not intended to be a comprehensive reference source. To complement the information in this data sheet, refer to Section 10. "Power-Saving Features" (DS60001130), which is available from the Documentation > Reference Manual section of the PIC32 Microchip web site (www.microchip.com/pic32).

This section describes power-saving features for the PIC32MX1XX/2XX 28/36/44-pin Family. The PIC32 devices offer a total of nine methods and modes, organized into two categories, that allow the user to balance power consumption with device performance. In all of the methods and modes described in this section, power-saving is controlled by software.

#### 26.1 Power Saving with CPU Running

When the CPU is running, power consumption can be controlled by reducing the CPU clock frequency, lowering the PBCLK and by individually disabling modules. These methods are grouped into the following categories:

- FRC Run mode: the CPU is clocked from the FRC clock source with or without postscalers
- LPRC Run mode: the CPU is clocked from the LPRC clock source
- Sosc Run mode: the CPU is clocked from the Sosc clock source

In addition, the Peripheral Bus Scaling mode is available where peripherals are clocked at the programmable fraction of the CPU clock (SYSCLK).

#### 26.2 CPU Halted Methods

The device supports two power-saving modes, Sleep and Idle, both of which Halt the clock to the CPU. These modes operate with all clock sources, as follows:

- Posc Idle mode: the system clock is derived from the Posc. The system clock source continues to operate. Peripherals continue to operate, but can optionally be individually disabled.
- FRC Idle mode: the system clock is derived from the FRC with or without postscalers. Peripherals continue to operate, but can optionally be individually disabled.
- Sosc Idle mode: the system clock is derived from the Sosc. Peripherals continue to operate, but can optionally be individually disabled.

- LPRC Idle mode: the system clock is derived from the LPRC. Peripherals continue to operate, but can optionally be individually disabled. This is the lowest power mode for the device with a clock running.
- Sleep mode: the CPU, the system clock source and any peripherals that operate from the system clock source are Halted. Some peripherals can operate in Sleep using specific clock sources. This is the lowest power mode for the device.

#### 26.3 Power-Saving Operation

Peripherals and the CPU can be Halted or disabled to further reduce power consumption.

#### 26.3.1 SLEEP MODE

Sleep mode has the lowest power consumption of the device power-saving operating modes. The CPU and most peripherals are Halted. Select peripherals can continue to operate in Sleep mode and can be used to wake the device from Sleep. See the individual peripheral module sections for descriptions of behavior in Sleep.

Sleep mode includes the following characteristics:

- · The CPU is halted
- The system clock source is typically shutdown.
   See Section 26.3.3 "Peripheral Bus Scaling Method" for specific information.
- There can be a wake-up delay based on the oscillator selection
- The Fail-Safe Clock Monitor (FSCM) does not operate during Sleep mode
- The BOR circuit remains operative during Sleep mode
- The WDT, if enabled, is not automatically cleared prior to entering Sleep mode
- Some peripherals can continue to operate at limited functionality in Sleep mode. These peripherals include I/O pins that detect a change in the input signal, WDT, ADC, UART and peripherals that use an external clock input or the internal LPRC oscillator (e.g., RTCC, Timer1 and Input Capture).
- I/O pins continue to sink or source current in the same manner as they do when the device is not in Sleep
- The USB module can override the disabling of the Posc or FRC. Refer to the USB section for specific details.
- Modules can be individually disabled by software prior to entering Sleep in order to further reduce consumption

The processor will exit, or 'wake-up', from Sleep on one of the following events:

- On any interrupt from an enabled source that is operating in Sleep. The interrupt priority must be greater than the current CPU priority.
- · On any form of device Reset
- · On a WDT time-out

If the interrupt priority is lower than or equal to the current priority, the CPU will remain Halted, but the PBCLK will start running and the device will enter into Idle mode.

#### 26.3.2 IDLE MODE

In Idle mode, the CPU is Halted but the System Clock (SYSCLK) source is still enabled. This allows peripherals to continue operation when the CPU is Halted. Peripherals can be individually configured to Halt when entering Idle by setting their respective SIDL bit. Latency, when exiting Idle mode, is very low due to the CPU oscillator source remaining active.

- Note 1: Changing the PBCLK divider ratio requires recalculation of peripheral timing. For example, assume the UART is configured for 9600 baud with a PB clock ratio of 1:1 and a Posc of 8 MHz. When the PB clock divisor of 1:2 is used, the input frequency to the baud clock is cut in half; therefore, the baud rate is reduced to 1/2 its former value. Due to numeric truncation in calculations (such as the baud rate divisor), the actual baud rate may be a tiny percentage different than expected. For this reason, any timing calculation required for a peripheral should be performed with the new PB clock frequency instead of scaling the previous value based on a change in the PB divisor ratio.
  - 2: Oscillator start-up and PLL lock delays are applied when switching to a clock source that was disabled and that uses a crystal and/or the PLL. For example, assume the clock source is switched from Posc to LPRC just prior to entering Sleep in order to save power. No oscillator start-up delay would be applied when exiting Idle. However, when switching back to Posc, the appropriate PLL and/or oscillator start-up/lock delays would be applied.

The device enters Idle mode when the SLPEN (OSCCON<4>) bit is clear and a WAIT instruction is executed.

The processor will wake or exit from Idle mode on the following events:

- On any interrupt event for which the interrupt source is enabled. The priority of the interrupt event must be greater than the current priority of the CPU. If the priority of the interrupt event is lower than or equal to current priority of the CPU, the CPU will remain Halted and the device will remain in Idle mode.
- · On any form of device Reset
- · On a WDT time-out interrupt

# 26.3.3 PERIPHERAL BUS SCALING METHOD

Most of the peripherals on the device are clocked using the PBCLK. The Peripheral Bus can be scaled relative to the SYSCLK to minimize the dynamic power consumed by the peripherals. The PBCLK divisor is controlled by PBDIV<1:0> (OSCCON<20:19>), allowing SYSCLK to PBCLK ratios of 1:1, 1:2, 1:4 and 1:8. All peripherals using PBCLK are affected when the divisor is changed. Peripherals such as the USB, Interrupt Controller, DMA, and the bus matrix are clocked directly from SYSCLK. As a result, they are not affected by PBCLK divisor changes.

Changing the PBCLK divisor affects:

- The CPU to peripheral access latency. The CPU has to wait for next PBCLK edge for a read to complete. In 1:8 mode, this results in a latency of one to seven SYSCLKs.
- The power consumption of the peripherals. Power consumption is directly proportional to the frequency at which the peripherals are clocked. The greater the divisor, the lower the power consumed by the peripherals.

To minimize dynamic power, the PB divisor should be chosen to run the peripherals at the lowest frequency that provides acceptable system performance. When selecting a PBCLK divider, peripheral clock requirements, such as baud rate accuracy, should be taken into account. For example, the UART peripheral may not be able to achieve all baud rate values at some PBCLK divider depending on the SYSCLK value.

#### 26.4 Peripheral Module Disable

The Peripheral Module Disable (PMD) registers provide a method to disable a peripheral module by stopping all clock sources supplied to that module. When a peripheral is disabled using the appropriate PMD control bit, the peripheral is in a minimum power consumption state. The control and status registers associated with the peripheral are also disabled, so writes to those registers do not have effect and read values are invalid.

To disable a peripheral, the associated PMDx bit must be set to '1'. To enable a peripheral, the associated PMDx bit must be cleared (default). See Table 26-1 for more information.

Note:

Disabling a peripheral module while it's ON bit is set, may result in undefined behavior. The ON bit for the associated peripheral module must be cleared prior to disable a module via the PMDx bits.

TABLE 26-1: PERIPHERAL MODULE DISABLE BITS AND LOCATIONS

Peripheral <sup>(1)</sup>	PMDx bit Name <sup>(1)</sup>	Register Name and Bit Location
ADC1	AD1MD	PMD1<0>
СТМИ	CTMUMD	PMD1<8>
Comparator Voltage Reference	CVRMD	PMD1<12>
Comparator 1	CMP1MD	PMD2<0>
Comparator 2	CMP2MD	PMD2<1>
Comparator 3	CMP3MD	PMD2<2>
Input Capture 1	IC1MD	PMD3<0>
Input Capture 2	IC2MD	PMD3<1>
Input Capture 3	IC3MD	PMD3<2>
Input Capture 4	IC4MD	PMD3<3>
Input Capture 5	IC5MD	PMD3<4>
Output Compare 1	OC1MD	PMD3<16>
Output Compare 2	OC2MD	PMD3<17>
Output Compare 3	OC3MD	PMD3<18>
Output Compare 4	OC4MD	PMD3<19>
Output Compare 5	OC5MD	PMD3<20>
Timer1	T1MD	PMD4<0>
Timer2	T2MD	PMD4<1>
Timer3	T3MD	PMD4<2>
Timer4	T4MD	PMD4<3>
Timer5	T5MD	PMD4<4>
UART1	U1MD	PMD5<0>
UART2	U2MD	PMD5<1>
SPI1	SPI1MD	PMD5<8>
SPI2	SPI2MD	PMD5<9>
I2C1	I2C1MD	PMD5<16>
I2C2	I2C2MD	PMD5<17>
USB <sup>(2)</sup>	USBMD	PMD5<24>
RTCC	RTCCMD	PMD6<0>
Reference Clock Output	REFOMD	PMD6<1>
PMP	PMPMD	PMD6<16>

Note 1: Not all modules and associated PMDx bits are available on all devices. See TABLE 1: "PIC32MX1XX 28/36/44-Pin General Purpose Family Features" and TABLE 2: "PIC32MX2XX 28/36/44-pin USB Family Features" for the lists of available peripherals.

<sup>2:</sup> The module must not be busy after clearing the associated ON bit and prior to setting the USBMD bit.

# 26.4.1 CONTROLLING CONFIGURATION CHANGES

Because peripherals can be disabled during run time, some restrictions on disabling peripherals are needed to prevent accidental configuration changes. PIC32 devices include two features to prevent alterations to enabled or disabled peripherals:

- · Control register lock sequence
- · Configuration bit select lock

#### 26.4.1.1 Control Register Lock

Under normal operation, writes to the PMDx registers are not allowed. Attempted writes appear to execute normally, but the contents of the registers remain unchanged. To change these registers, they must be unlocked in hardware. The register lock is controlled by the Configuration bit, PMDLOCK (CFGCON<12>). Setting PMDLOCK prevents writes to the control registers; clearing PMDLOCK allows writes.

To set or clear PMDLOCK, an unlock sequence must be executed. Refer to **Section 6. "Oscillator"** (DS60001112) in the "PIC32 Family Reference Manual" for details.

#### 26.4.1.2 Configuration Bit Select Lock

As an additional level of safety, the device can be configured to prevent more than one write session to the PMDx registers. The Configuration bit, PMDL1WAY (DEVCFG3<28>), blocks the PMDLOCK bit from being cleared after it has been set once. If PMDLOCK remains set, the register unlock procedure does not execute, and the peripheral pin select control registers cannot be written to. The only way to clear the bit and re-enable PMD functionality is to perform a device Reset.

TABLE 26-2: PERIPHERAL MODULE DISABLE REGISTER MAP

9	steseЯ IIA	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	
	16/0	I	AD1MD	I	CMP1MD	OC1MD	IC1MD	I	T1MD	I2C1MD	U1MD	PMPMD	RTCCMD	
	1/11	I	I	I	CMP2MD	OC2MD	IC2MD	I	T2MD	I2C1MD	UZMD	I	REFOMD	
	18/2	I	1	I	CMP3MD	OC3MD	IC3MD	Ι	T3MD	I	1	I	Ι	
	19/3	I	1	1	1	OC4MD	IC4MD	1	T4MD	1	1	1	Ι	
	20/4	I	I	I	I	OC5MD	ICSMD	-	<b>TSMD</b>	I	I	I	-	
	21/5	I	I	I	I	I	I	Ι	I	I	I	I	I	
	22/6	I	I	I	I	I	I	_	-	I	I	I	_	
Bits	23/7	I	I	I	I	I	I	_	_	I	I	I	_	cimal.
	24/8	I	CTMUMD	1	1	1	1	_	-	USB1MD	SPI1MD	1	_	as '0'. Reset values are shown in hexadecimal
	25/9	I	I	I	I	I	I	_	-	I	SPI2MD	I	-	s are show
	26/10	I	1	1	1	1	1	Ι	I	1	1	1	I	eset values
	27/11	I	I	I	I	I	I	Ι	I	I	I	I	Ι	
	28/12	I	CVRMD	Ι	1	Ι	Ι	I	I	Ι	1	Ι	I	mented, re-
	29/13	I	I	I	I	I	Ι	Ι	I	I	I	I	Ι	x = unknown value on Reset; = unimplemented, read
	30/14	I	1	1	1	1	1	I	I	1	1	1	I	n Reset; –
31/15		31:16 —	1	Ι	1	Ι	1	-	Ι	Ι	1	Ι	Ι	n value or
	Bit Range		15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0	unknow
	Register Name <sup>(1)</sup>		7 5 -		Z N N		Z Z		7 5 4		S C C C C C C C C C C C C C C C C C C C			
	Virtual Address (#_0878)		F240	100	F250	000	F260	107	F2/U	000	F280	000	F290	Legend:

All registers in this table have corresponding CLR, SET and INV registers at their virtual addresses, plus offsets of 0x4, 0x8 and 0xC, respectively. See Section 11.2 "CLR, SET and INV Registers" for more information.

NOTES:			

#### 27.0 SPECIAL FEATURES

Note:

This data sheet summarizes the features of the PIC32MX1XX/2XX 28/36/44-pin Family of devices. However, it is not intended to be a comprehensive reference source. To complement the information in this data sheet, refer to 32. "Configuration" Section (DS60001124) and Section "Programming and Diagnostics" (DS60001129), which are available from the Documentation > Reference Manual section of the Microchip PIC32 web site (www.microchip.com/pic32).

PIC32MX1XX/2XX 28/36/44-pin Family devices include the following features intended to maximize application flexibility, reliability and minimize cost through elimination of external components.

- · Flexible device configuration
- Joint Test Action Group (JTAG) interface
- In-Circuit Serial Programming™ (ICSP™)

#### 27.1 Configuration Bits

The Configuration bits can be programmed using the following registers to select various device configurations.

- DEVCFG0: Device Configuration Word 0
- DEVCFG1: Device Configuration Word 1
- DEVCFG2: Device Configuration Word 2
- DEVCFG3: Device Configuration Word 3
- · CFGCON: Configuration Control Register

In addition, the DEVID register (Register 27-6) provides device and revision information.

**Configuration Registers** 27.2

TABLE 27-1: DEVCFG: DEVICE CONFIGURATION WORD SUMMARY

s	PII Reseta	XXXX	XXXX	XXXX	XXXX	XXXX	XXXX	XXXX	XXXX
	16/0	-		<0:	<0:		<u>^</u>	(2)	IG<1:0>
	17/1	I		FPLLODIV<2:0>	FPLLIDIV<2:0>	<b>^</b> 0	FNOSC<2:0>	PWP<8:6>(2)	DEBUG<1:0>
	18/2	I		Ĭ.	4	WDTPS<4:0>			ICESEL<1:0> JTAGEN
	19/3	1		Ι	Ι		Ι	Ι	:L<1:0>
	20/4	I		I	<0:			I	ICESE
	21/5	I		-	FPLLMUL<2:0>	-	FSOSCEN	-	1
	22/6	I		Ι	Ē	MINDIS	Ι	Ι	I
	23/7	I	15:0>	Ι	Ι	FWDTEN	IESO	Ι	1
Bits	24/8	1	USERID<15:0>	Ι	>(1)	FWDTWINSZ<1:0> FWDTEN	OD<1:0>	BWP	1
	25/9			Ι	UPLLIDIV<2:0>(1)		POSCM	Ι	I
	26/10	I		I	UPI	I	OSCIOFNC POSCMOD<1:0>	I	
	27/11	Ι		Ι	Ι	Ι	Ι	Ι	
	28/12	PMDL1WAY		-	-	-	FPBDIV<1:0>	SP	<2:0>
	29/13	IOL1WAY		-	-	-	1844	-	PWP<5:0>
	30/14	FUSBIDIO		Ι	I	Ι	<1:0>	Ι	
	31/15			1	UPLLEN <sup>(1)</sup>	1	FCKSM<1:0>	1	
6	Bit Range	31:16	15:0	31:16	15:0	31:16	15:0	31:16	15:0
	Register Aame	OBEO DEVCECS 31:16 FVBUSONIO FUSBIDIO IOL1WAY PMDL1WA	20,00	31:16	25 CO VEI G	, , , , , , , , , ,	D \ \	, 0010/110	00 00 00
ssə	Virtual Addr (#_0D78)	OBEO		7000	400	0000	000	000	ם ס
	1								

— = unimplemented, read as '0'. Reset values are shown in hexadecimal.

x= unknown value on Reset; — = unimplemented, read as '0'. This bit is only available on PIC32MX2XX devices. PWP<8:7> are only available on devices with 256 KB of Flash.

DEVICE ID, REVISION, AND CONFIGURATION SUMMARY **TABLE 27-2:** 

	(L)	stəsəЯ IIA	xxxx(1)	XXXX(1)	0000	000B	0000	0000
		16/0			-	TDOEN		
		1/11			Ι	Ι		
		18/2			1	1		
		19/3			I	JTAGEN		
		20/4			I	Ι		
		21/5	DEVID<27:16>		I	Ι		
		22/6	DEVID		I	Ι		
	Bits	23/7		DEVID<15:0>	I	Ι	70.10	70.16
	ā	24/8		DEVID	I	-	F230 SYSKEY(3) 31:16 SYSKEY<31:0>	O ONE
		25/9			I	-		
		26/10			1	Ι		
		27/11			Ι	1		
		28/12			I	IOLOCK PMDLOCK		
,		29/13	VER<3:0>		1	IOLOCK		
,		30/14	VER		Ι	-		
		31/15			-	_		
	(	Bit Range	31:16	15:0	31:16	15:0	31:16	15:0
		Register Mame	( )	ט ט	NOUGH	NO0910	SVS//EV(3)	O LONE L
	ssə	Virtual Addr (#_0878)		L 220		P.200	000	F230

x= unknown value on Reset; — = unimplemented, read as '0'. Reset values are shown in hexadecimal Reset values are dependent on the device variant.

#### REGISTER 27-1: DEVCFG0: DEVICE CONFIGURATION WORD 0

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	r-0	r-1	r-1	R/P	r-1	r-1	r-1	R/P
31.24	_	_	_	CP	_	_	_	BWP
22,16	r-1	r-1	r-1	r-1	r-1	R/P	R/P	R/P
23:16	_	_	_	_	_	I	PWP<8:6> <sup>(3)</sup>	
15:8	R/P	R/P	R/P	R/P	R/P	R/P	r-1	r-1
15.6			PWP<	:5:0>			_	_
7:0	r-1	r-1	r-1	R/P	R/P	R/P	R/P	R/P
7.0	_	_	_	ICESEL	<1:0> <sup>(2)</sup>	JTAGEN <sup>(1)</sup>	DEBU	G<1:0>

Legend:r = Reserved bitP = Programmable bitR = Readable bitW = Writable bitU = Unimplemented bit, read as '0'-n = Value at POR'1' = Bit is set'0' = Bit is clearedx = Bit is unknown

bit 31 Reserved: Write '0' bit 30-29 Reserved: Write '1' bit 28 CP: Code-Protect bit

Prevents boot and program Flash memory from being read or modified by an external programming device.

1 = Protection is disabled0 = Protection is enabled

bit 27-25 Reserved: Write '1'

bit 24 **BWP:** Boot Flash Write-Protect bit

Prevents boot Flash memory from being modified during code execution.

1 = Boot Flash is writable0 = Boot Flash is not writable

bit 23-19 Reserved: Write '1'

Note 1: This bit sets the value for the JTAGEN bit in the CFGCON register.

- 2: The PGEC4/PGED4 pin pair is not available on all devices. Refer to the "Pin Diagrams" section for availability.
- 3: The PWP<8:7> bits are only available on devices with 256 KB Flash.

#### REGISTER 27-1: DEVCFG0: DEVICE CONFIGURATION WORD 0 (CONTINUED)

```
bit 18-10 PWP<8:0>: Program Flash Write-Protect bits<sup>(3)</sup>
         Prevents selected program Flash memory pages from being modified during code execution.
         111111111 = Disabled
         111111110 = Memory below 0x0400 address is write-protected
         111111101 = Memory below 0x0800 address is write-protected
         111111100 = Memory below 0x0C00 address is write-protected
         111111011 = Memory below 0x1000 (4K) address is write-protected
         111111010 = Memory below 0x1400 address is write-protected
         111111001 = Memory below 0x1800 address is write-protected
         111111000 = Memory below 0x1C00 address is write-protected
         111110111 = Memory below 0x2000 (8K) address is write-protected
         111110110 = Memory below 0x2400 address is write-protected
         111110101 = Memory below 0x2800 address is write-protected
         111110100 = Memory below 0x2C00 address is write-protected
         111110011 = Memory below 0x3000 address is write-protected
         111110010 = Memory below 0x3400 address is write-protected
         111110001 = Memory below 0x3800 address is write-protected
         111110000 = Memory below 0x3C00 address is write-protected
         111101111 = Memory below 0x4000 (16K) address is write-protected
         110111111 = Memory below 0x10000 (64K) address is write-protected
```

101111111 = Memory below 0x20000 (128K) address is write-protected 011111111 = Memory below 0x40000 (256K) address is write-protected

000000000 = All possible memory is write-protected

- bit 9-5 Reserved: Write '1'
- ICESEL<1:0>: In-Circuit Emulator/Debugger Communication Channel Select bits<sup>(2)</sup> bit 4-3
  - 11 = PGEC1/PGED1 pair is used
  - 10 = PGEC2/PGED2 pair is used
  - 01 = PGEC3/PGED3 pair is used
  - 00 = PGEC4/PGED4 pair is used<sup>(2)</sup>
- bit 2 JTAGEN: JTAG Enable bit(1)
  - 1 = JTAG is enabled
  - 0 = JTAG is disabled
- DEBUG<1:0>: Background Debugger Enable bits (forced to '11' if code-protect is enabled) bit 1-0
  - 11 = Debugger is disabled
  - 0x = Debugger is enabled
- Note 1: This bit sets the value for the JTAGEN bit in the CFGCON register.
  - 2: The PGEC4/PGED4 pin pair is not available on all devices. Refer to the "Pin Diagrams" section for availability.
  - 3: The PWP<8:7> bits are only available on devices with 256 KB Flash.

#### REGISTER 27-2: DEVCFG1: DEVICE CONFIGURATION WORD 1

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	r-1	r-1	r-1	r-1	r-1	r-1	R/P	R/P
31:24	_	_	_	FWDTWINSZ<				
00:40	R/P	R/P	r-1	R/P	R/P	R/P	R/P	R/P
23:16	FWDTEN	WINDIS	_			WDTPS<4:0>		
45.0	R/P	R/P	R/P	R/P	r-1	R/P	R/P	R/P
15:8	FCKSM	<b>1&lt;1:0&gt;</b>	FPBDI	DIV<1:0> — OSCIOFNC POSCMOD				OD<1:0>
7.0	R/P	r-1	R/P	r-1	r-1	R/P	R/P	R/P
7:0	IESO	_	FSOSCEN		_	F	NOSC<2:0>	•

Legend:r = Reserved bitP = Programmable bitR = Readable bitW = Writable bitU = Unimplemented bit, read as '0'-n = Value at POR'1' = Bit is set'0' = Bit is clearedx = Bit is unknown

bit 31-26 Reserved: Write '1'

bit 25-24 FWDTWINSZ<1:0>: Watchdog Timer Window Size bits

11 = Window size is 25%

10 = Window size is 37.5%

01 = Window size is 50%

00 = Window size is 75%

bit 23 FWDTEN: Watchdog Timer Enable bit

1 = Watchdog Timer is enabled and cannot be disabled by software

0 = Watchdog Timer is not enabled; it can be enabled in software

bit 22 WINDIS: Watchdog Timer Window Enable bit

1 = Watchdog Timer is in non-Window mode

0 = Watchdog Timer is in Window mode

bit 21 Reserved: Write '1'

bit 20-16 WDTPS<4:0>: Watchdog Timer Postscale Select bits

10100 = 1:1048576

10011 = 1:524288

10010 = 1:262144

10001 = 1:131072

10000 = 1:65536

01111 = 1:32768

01110 = 1:16384

01101 = 1:8192

01100 = 1:4096

01011 = 1:2048

01010 = 1:1024

01001 = 1:512

01000 = 1:25600111 = 1:128

00110 = 1:64

00101 = 1:32

00100 = 1:16

00011 = 1:8

00010 = 1:4

00001 = 1:2

00000 = 1:1

All other combinations not shown result in operation = 10100

**Note 1:** Do not disable the Posc (POSCMOD = 11) when using this oscillator source.

#### REGISTER 27-2: DEVCFG1: DEVICE CONFIGURATION WORD 1 (CONTINUED)

- bit 15-14 FCKSM<1:0>: Clock Switching and Monitor Selection Configuration bits 1x = Clock switching is disabled, Fail-Safe Clock Monitor is disabled 01 = Clock switching is enabled, Fail-Safe Clock Monitor is disabled 00 = Clock switching is enabled, Fail-Safe Clock Monitor is enabled bit 13-12 FPBDIV<1:0>: Peripheral Bus Clock Divisor Default Value bits 11 = PBCLK is SYSCLK divided by 8 10 = PBCLK is SYSCLK divided by 4 01 = PBCLK is SYSCLK divided by 2 00 = PBCLK is SYSCLK divided by 1 bit 11 Reserved: Write '1' bit 10 OSCIOFNC: CLKO Enable Configuration bit 1 = CLKO output disabled 0 = CLKO output signal active on the OSCO pin; Primary Oscillator must be disabled or configured for the External Clock mode (EC) for the CLKO to be active (POSCMOD<1:0> = 11 or 00) POSCMOD<1:0>: Primary Oscillator Configuration bits bit 9-8 11 = Primary Oscillator is disabled 10 = HS Oscillator mode is selected 01 = XT Oscillator mode is selected 00 = External Clock mode is selected bit 7 IESO: Internal External Switchover bit 1 = Internal External Switchover mode is enabled (Two-Speed Start-up is enabled) 0 = Internal External Switchover mode is disabled (Two-Speed Start-up is disabled) bit 6 Reserved: Write '1' bit 5 FSOSCEN: Secondary Oscillator Enable bit 1 = Enable Secondary Oscillator 0 = Disable Secondary Oscillator bit 4-3 Reserved: Write '1' bit 2-0 FNOSC<2:0>: Oscillator Selection bits 111 = Fast RC Oscillator with divide-by-N (FRCDIV) 110 = FRCDIV16 Fast RC Oscillator with fixed divide-by-16 postscaler 101 = Low-Power RC Oscillator (LPRC) 100 = Secondary Oscillator (Sosc) 011 = Primary Oscillator (Posc) with PLL module (XT+PLL, HS+PLL, EC+PLL) 010 = Primary Oscillator (XT, HS, EC)(1) 001 = Fast RC Oscillator with divide-by-N with PLL module (FRCDIV+PLL) 000 = Fast RC Oscillator (FRC)
- **Note 1:** Do not disable the Posc (POSCMOD = 11) when using this oscillator source.

#### REGISTER 27-3: DEVCFG2: DEVICE CONFIGURATION WORD 2

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
31:24	r-1	r-1	r-1	r-1	r-1	r-1	r-1	r-1
31.24	_	_	_	_	_	_	_	_
00.40	r-1	r-1	r-1	r-1	r-1	R/P	R/P	R/P
23:16	_	_	_	_	_	FI	PLLODIV<2:0	)>
45.0	R/P	r-1	r-1	r-1	r-1	R/P	R/P	R/P
15:8	UPLLEN <sup>(1)</sup>	_	_	_	— UPLLIDIV<2:			,(1)
7.0	r-1	R/P-1	R/P	R/P-1	r-1	R/P	R/P	R/P
7:0		F	PLLMUL<2:0>	•	_	F	PLLIDIV<2:0	>

Legend:r = Reserved bitP = Programmable bitR = Readable bitW = Writable bitU = Unimplemented bit, read as '0'-n = Value at POR'1' = Bit is set'0' = Bit is clearedx = Bit is unknown

bit 31-19 Reserved: Write '1'

bit 18-16 FPLLODIV<2:0>: Default PLL Output Divisor bits

111 = PLL output divided by 256

110 = PLL output divided by 64

101 = PLL output divided by 32

100 = PLL output divided by 16

011 = PLL output divided by 8

010 = PLL output divided by 4

001 = PLL output divided by 2

000 = PLL output divided by 1

bit 15 **UPLLEN:** USB PLL Enable bit<sup>(1)</sup>

1 = Disable and bypass USB PLL

0 = Enable USB PLL

bit 14-11 Reserved: Write '1'

bit 10-8 **UPLLIDIV<2:0>:** USB PLL Input Divider bits<sup>(1)</sup>

111 = 12x divider

110 = 10x divider

101 = 6x divider

100 = 5x divider

011 = 4x divider

010 = 3x divider

010 = 3x divider

001 = 2x divider

000 = 1x divider

bit 7 Reserved: Write '1'

bit 6-4 FPLLMUL<2:0>: PLL Multiplier bits

111 = 24x multiplier

110 = 21x multiplier

101 = 20x multiplier

100 = 19x multiplier

011 = 18x multiplier

010 = 17x multiplier

001 = 16x multiplier

000 = 15x multiplier

bit 3 Reserved: Write '1'

Note 1: This bit is only available on PIC32MX2XX devices.

#### REGISTER 27-3: DEVCFG2: DEVICE CONFIGURATION WORD 2 (CONTINUED)

bit 2-0 **FPLLIDIV<2:0>:** PLL Input Divider bits

111 = 12x divider

110 = **10**x divider

101 = 6x divider

100 = 5x divider 011 = 4x divider

011 = 4x divider 010 = 3x divider

001 = 2x divider

000 = 1x divider

Note 1: This bit is only available on PIC32MX2XX devices.

#### REGISTER 27-4: DEVCFG3: DEVICE CONFIGURATION WORD 3

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0	
24.24	R/P	R/P	R/P	R/P	r-1	r-1	r-1	r-1	
31:24	FVBUSONIO	FUSBIDIO	IOL1WAY	PMDL1WAY	_	_	_	_	
22,46	r-1                r-1								
23:16	_	_	_	_	_	_	_	_	
15:8	R/P                R/P								
13.6		USERID<15:8>							
7:0	R/P                R/P								
7.0			•	USERID<	7:0>			•	

Legend:r = Reserved bitP = Programmable bitR = Readable bitW = Writable bitU = Unimplemented bit, read as '0'-n = Value at POR'1' = Bit is set'0' = Bit is clearedx = Bit is unknown

bit 31 FVBUSONIO: USB VBUSON Selection bit

1 = VBUSON pin is controlled by the USB module 0 = VBUSON pin is controlled by the port function

bit 30 FUSBIDIO: USB USBID Selection bit

1 = USBID pin is controlled by the USB module 0 = USBID pin is controlled by the port function

IOL1WAY: Peripheral Pin Select Configuration bit

1 = Allow only one reconfiguration0 = Allow multiple reconfigurations

bit 28 PMDI1WAY: Peripheral Module Disable Configuration bit

1 = Allow only one reconfiguration0 = Allow multiple reconfigurations

bit 27-16 Reserved: Write '1'

bit 29

bit 15-0 USERID<15:0>: User ID bits

This is a 16-bit value that is user-defined and is readable via ICSP™ and JTAG.

#### REGISTER 27-5: CFGCON: CONFIGURATION CONTROL REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0
24.24	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
31:24	_	1	-		-	_	_	_
00:40	U-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0
23:16	_	-	_	_	_	_	_	_
45.0	U-0	U-0	R/W-0	R/W-0	U-0	U-0	U-0	U-0
15:8	_	-	IOLOCK <sup>(1)</sup>	PMDLOCK <sup>(1)</sup>	_	_	_	_
7.0	U-0	U-0	U-0	U-0	R/W-1	U-0	U-1	R/W-1
7:0	_		_	_	JTAGEN	_	_	TDOEN

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 31-14 Unimplemented: Read as '0'

bit 13 **IOLOCK:** Peripheral Pin Select Lock bit<sup>(1)</sup>

1 = Peripheral Pin Select is locked. Writes to PPS registers is not allowed.

0 = Peripheral Pin Select is not locked. Writes to PPS registers is allowed.

bit 12 **PMDLOCK:** Peripheral Module Disable bit<sup>(1)</sup>

1 = Peripheral module is locked. Writes to PMD registers is not allowed.

0 = Peripheral module is not locked. Writes to PMD registers is allowed.

bit 11-4 Unimplemented: Read as '0'

bit 3 JTAGEN: JTAG Port Enable bit

1 = Enable the JTAG port

0 = Disable the JTAG port

bit 2-1 **Unimplemented:** Read as '1'

bit 0 TDOEN: TDO Enable for 2-Wire JTAG bit

1 = 2-wire JTAG protocol uses TDO

0 = 2-wire JTAG protocol does not use TDO

Note 1: To change this bit, the unlock sequence must be performed. Refer to **Section 6. "Oscillator"** (DS60001112) in the "PIC32 Family Reference Manual" for details.

#### REGISTER 27-6: DEVID: DEVICE AND REVISION ID REGISTER

Bit Range	Bit 31/23/15/7	Bit 30/22/14/6	Bit 29/21/13/5	Bit 28/20/12/4	Bit 27/19/11/3	Bit 26/18/10/2	Bit 25/17/9/1	Bit 24/16/8/0	
24.24	R	R	R	R	R	R	R	R	
31:24	VER<3:0> <sup>(1)</sup>				DEVID<27:24>(1)				
00:40	R	R	R	R	R	R	R	R	
23:16	DEVID<23:16> <sup>(1)</sup>								
45.0	R	R	R	R	R	R	R	R	
15:8	DEVID<15:8> <sup>(1)</sup>								
7.0	R	R	R	R	R	R	R	R	
7:0	DEVID<7:0> <sup>(1)</sup>								

Legend:				
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'		
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown	

bit 31-28 **VER<3:0>:** Revision Identifier bits<sup>(1)</sup> bit 27-0 **DEVID<27:0>:** Device ID bits<sup>(1)</sup>

Note 1: See the "PIC32 Flash Programming Specification" (DS60001145) for a list of Revision and Device ID values.

### 27.3 On-Chip Voltage Regulator

All PIC32MX1XX/2XX 28/36/44-pin Family devices' core and digital logic are designed to operate at a nominal 1.8V. To simplify system designs, most devices in the PIC32MX1XX/2XX 28/36/44-pin Family family incorporate an on-chip regulator providing the required core logic voltage from VDD.

A low-ESR capacitor (such as tantalum) must be connected to the VCAP pin (see Figure 27-1). This helps to maintain the stability of the regulator. The recommended value for the filter capacitor is provided in Section 30.1 "DC Characteristics".

**Note:** It is important that the low-ESR capacitor is placed as close as possible to the VCAP pin.


#### 27.3.1 ON-CHIP REGULATOR AND POR

It takes a fixed delay for the on-chip regulator to generate an output. During this time, designated as TPU, code execution is disabled. TPU is applied every time the device resumes operation after any power-down, including Sleep mode.

#### 27.3.2 ON-CHIP REGULATOR AND BOR

PIC32MX1XX/2XX 28/36/44-pin Family devices also have a simple brown-out capability. If the voltage supplied to the regulator is inadequate to maintain a regulated level, the regulator Reset circuitry will generate a Brown-out Reset. This event is captured by the BOR flag bit (RCON<1>). The brown-out voltage levels are specific in Section 30.1 "DC Characteristics".

## FIGURE 27-1: CONNECTIONS FOR THE ON-CHIP REGULATOR



- Note 1: These are typical operating voltages. Refer to Section 30.1 "DC Characteristics" for the full operating ranges of VDD.
  - 2: It is important that the low-ESR capacitor is placed as close as possible to the VCAP pin.
  - **3:** The typical voltage on the VCAP pin is 1.8V.

### 27.4 Programming and Diagnostics


PIC32MX1XX/2XX 28/36/44-pin Family devices provide a complete range of programming and diagnostic features that can increase the flexibility of any application using them. These features allow system designers to include:

- Simplified field programmability using two-wire In-Circuit Serial Programming™ (ICSP™) interfaces
- · Debugging using ICSP
- Programming and debugging capabilities using the EJTAG extension of JTAG
- JTAG boundary scan testing for device and board diagnostics

PIC32 devices incorporate two programming and diagnostic modules, and a trace controller, that provide a range of functions to the application developer.

Figure 27-2 illustrates a block diagram of the programming, debugging, and trace ports.

FIGURE 27-2: BLOCK DIAGRAM OF PROGRAMMING, DEBUGGING AND TRACE PORTS



### 28.0 INSTRUCTION SET

The PIC32MX1XX/2XX family instruction set complies with the MIPS32 $^{\circledR}$  Release 2 instruction set architecture. The PIC32 device family does not support the following features:

- · Core extend instructions
- · Coprocessor 1 instructions
- · Coprocessor 2 instructions

Note: Refer to "MIPS32<sup>®</sup> Architecture for Programmers Volume II: The MIPS32<sup>®</sup> Instruction Set" at www.imgtec.com for more information.

NOTES:			

#### 29.0 DEVELOPMENT SUPPORT

The PIC<sup>®</sup> microcontrollers (MCU) and dsPIC<sup>®</sup> digital signal controllers (DSC) are supported with a full range of software and hardware development tools:

- · Integrated Development Environment
  - MPLAB® X IDE Software
- · Compilers/Assemblers/Linkers
  - MPLAB XC Compiler
  - MPASM™ Assembler
  - MPLINK™ Object Linker/ MPLIB™ Object Librarian
  - MPLAB Assembler/Linker/Librarian for Various Device Families
- Simulators
  - MPLAB X SIM Software Simulator
- Fmulators
  - MPLAB REAL ICE™ In-Circuit Emulator
- · In-Circuit Debuggers/Programmers
  - MPLAB ICD 3
  - PICkit™ 3
- · Device Programmers
  - MPLAB PM3 Device Programmer
- Low-Cost Demonstration/Development Boards, Evaluation Kits and Starter Kits
- · Third-party development tools

## 29.1 MPLAB X Integrated Development Environment Software

The MPLAB X IDE is a single, unified graphical user interface for Microchip and third-party software, and hardware development tool that runs on Windows<sup>®</sup>, Linux and Mac OS<sup>®</sup> X. Based on the NetBeans IDE, MPLAB X IDE is an entirely new IDE with a host of free software components and plug-ins for high-performance application development and debugging. Moving between tools and upgrading from software simulators to hardware debugging and programming tools is simple with the seamless user interface.

With complete project management, visual call graphs, a configurable watch window and a feature-rich editor that includes code completion and context menus, MPLAB X IDE is flexible and friendly enough for new users. With the ability to support multiple tools on multiple projects with simultaneous debugging, MPLAB X IDE is also suitable for the needs of experienced users.

#### Feature-Rich Editor:

- Color syntax highlighting
- Smart code completion makes suggestions and provides hints as you type
- Automatic code formatting based on user-defined rules
- · Live parsing

User-Friendly, Customizable Interface:

- Fully customizable interface: toolbars, toolbar buttons, windows, window placement, etc.
- · Call graph window

Project-Based Workspaces:

- · Multiple projects
- Multiple tools
- · Multiple configurations
- · Simultaneous debugging sessions

File History and Bug Tracking:

- · Local file history feature
- · Built-in support for Bugzilla issue tracker

### 29.2 MPLAB XC Compilers

The MPLAB XC Compilers are complete ANSI C compilers for all of Microchip's 8, 16, and 32-bit MCU and DSC devices. These compilers provide powerful integration capabilities, superior code optimization and ease of use. MPLAB XC Compilers run on Windows, Linux or MAC OS X.

For easy source level debugging, the compilers provide debug information that is optimized to the MPLAB X IDF.

The free MPLAB XC Compiler editions support all devices and commands, with no time or memory restrictions, and offer sufficient code optimization for most applications.

MPLAB XC Compilers include an assembler, linker and utilities. The assembler generates relocatable object files that can then be archived or linked with other relocatable object files and archives to create an executable file. MPLAB XC Compiler uses the assembler to produce its object file. Notable features of the assembler include:

- · Support for the entire device instruction set
- · Support for fixed-point and floating-point data
- · Command-line interface
- · Rich directive set
- · Flexible macro language
- · MPLAB X IDE compatibility

#### 29.3 MPASM Assembler

The MPASM Assembler is a full-featured, universal macro assembler for PIC10/12/16/18 MCUs.

The MPASM Assembler generates relocatable object files for the MPLINK Object Linker, Intel® standard HEX files, MAP files to detail memory usage and symbol reference, absolute LST files that contain source lines and generated machine code, and COFF files for debugging.

The MPASM Assembler features include:

- · Integration into MPLAB X IDE projects
- User-defined macros to streamline assembly code
- Conditional assembly for multipurpose source files
- Directives that allow complete control over the assembly process

### 29.4 MPLINK Object Linker/ MPLIB Object Librarian

The MPLINK Object Linker combines relocatable objects created by the MPASM Assembler. It can link relocatable objects from precompiled libraries, using directives from a linker script.

The MPLIB Object Librarian manages the creation and modification of library files of precompiled code. When a routine from a library is called from a source file, only the modules that contain that routine will be linked in with the application. This allows large libraries to be used efficiently in many different applications.

The object linker/library features include:

- Efficient linking of single libraries instead of many smaller files
- Enhanced code maintainability by grouping related modules together
- Flexible creation of libraries with easy module listing, replacement, deletion and extraction

# 29.5 MPLAB Assembler, Linker and Librarian for Various Device Families

MPLAB Assembler produces relocatable machine code from symbolic assembly language for PIC24, PIC32 and dsPIC DSC devices. MPLAB XC Compiler uses the assembler to produce its object file. The assembler generates relocatable object files that can then be archived or linked with other relocatable object files and archives to create an executable file. Notable features of the assembler include:

- · Support for the entire device instruction set
- · Support for fixed-point and floating-point data
- · Command-line interface
- · Rich directive set
- · Flexible macro language
- · MPLAB X IDE compatibility

#### 29.6 MPLAB X SIM Software Simulator

The MPLAB X SIM Software Simulator allows code development in a PC-hosted environment by simulating the PIC MCUs and dsPIC DSCs on an instruction level. On any given instruction, the data areas can be examined or modified and stimuli can be applied from a comprehensive stimulus controller. Registers can be logged to files for further run-time analysis. The trace buffer and logic analyzer display extend the power of the simulator to record and track program execution, actions on I/O, most peripherals and internal registers.

The MPLAB X SIM Software Simulator fully supports symbolic debugging using the MPLAB XC Compilers, and the MPASM and MPLAB Assemblers. The software simulator offers the flexibility to develop and debug code outside of the hardware laboratory environment, making it an excellent, economical software development tool.

# 29.7 MPLAB REAL ICE In-Circuit Emulator System

The MPLAB REAL ICE In-Circuit Emulator System is Microchip's next generation high-speed emulator for Microchip Flash DSC and MCU devices. It debugs and programs all 8, 16 and 32-bit MCU, and DSC devices with the easy-to-use, powerful graphical user interface of the MPLAB X IDE.

The emulator is connected to the design engineer's PC using a high-speed USB 2.0 interface and is connected to the target with either a connector compatible with in-circuit debugger systems (RJ-11) or with the new high-speed, noise tolerant, Low-Voltage Differential Signal (LVDS) interconnection (CAT5).

The emulator is field upgradable through future firmware downloads in MPLAB X IDE. MPLAB REAL ICE offers significant advantages over competitive emulators including full-speed emulation, run-time variable watches, trace analysis, complex breakpoints, logic probes, a ruggedized probe interface and long (up to three meters) interconnection cables.

### 29.8 MPLAB ICD 3 In-Circuit Debugger System

The MPLAB ICD 3 In-Circuit Debugger System is Microchip's most cost-effective, high-speed hardware debugger/programmer for Microchip Flash DSC and MCU devices. It debugs and programs PIC Flash microcontrollers and dsPIC DSCs with the powerful, yet easy-to-use graphical user interface of the MPLAB IDF.

The MPLAB ICD 3 In-Circuit Debugger probe is connected to the design engineer's PC using a high-speed USB 2.0 interface and is connected to the target with a connector compatible with the MPLAB ICD 2 or MPLAB REAL ICE systems (RJ-11). MPLAB ICD 3 supports all MPLAB ICD 2 headers.

### 29.9 PICkit 3 In-Circuit Debugger/ Programmer

The MPLAB PICkit 3 allows debugging and programming of PIC and dsPIC Flash microcontrollers at a most affordable price point using the powerful graphical user interface of the MPLAB IDE. The MPLAB PICkit 3 is connected to the design engineer's PC using a full-speed USB interface and can be connected to the target via a Microchip debug (RJ-11) connector (compatible with MPLAB ICD 3 and MPLAB REAL ICE). The connector uses two device I/O pins and the Reset line to implement in-circuit debugging and In-Circuit Serial Programming™ (ICSP™).

#### 29.10 MPLAB PM3 Device Programmer

The MPLAB PM3 Device Programmer is a universal, CE compliant device programmer with programmable voltage verification at VDDMIN and VDDMAX for maximum reliability. It features a large LCD display (128 x 64) for menus and error messages, and a modular, detachable socket assembly to support various package types. The ICSP cable assembly is included as a standard item. In Stand-Alone mode, the MPLAB PM3 Device Programmer can read, verify and program PIC devices without a PC connection. It can also set code protection in this mode. The MPLAB PM3 connects to the host PC via an RS-232 or USB cable. The MPLAB PM3 has high-speed communications and optimized algorithms for quick programming of large memory devices, and incorporates an MMC card for file storage and data applications.

# 29.11 Demonstration/Development Boards, Evaluation Kits, and Starter Kits

A wide variety of demonstration, development and evaluation boards for various PIC MCUs and dsPIC DSCs allows quick application development on fully functional systems. Most boards include prototyping areas for adding custom circuitry and provide application firmware and source code for examination and modification.

The boards support a variety of features, including LEDs, temperature sensors, switches, speakers, RS-232 interfaces, LCD displays, potentiometers and additional EEPROM memory.

The demonstration and development boards can be used in teaching environments, for prototyping custom circuits and for learning about various microcontroller applications.

In addition to the PICDEM™ and dsPICDEM™ demonstration/development board series of circuits, Microchip has a line of evaluation kits and demonstration software for analog filter design, KEELoQ® security ICs, CAN, IrDA®, PowerSmart battery management, SEEVAL® evaluation system, Sigma-Delta ADC, flow rate sensing, plus many more.

Also available are starter kits that contain everything needed to experience the specified device. This usually includes a single application and debug capability, all on one board.

Check the Microchip web page (www.microchip.com) for the complete list of demonstration, development and evaluation kits.

#### 29.12 Third-Party Development Tools

Microchip also offers a great collection of tools from third-party vendors. These tools are carefully selected to offer good value and unique functionality.

- Device Programmers and Gang Programmers from companies, such as SoftLog and CCS
- Software Tools from companies, such as Gimpel and Trace Systems
- Protocol Analyzers from companies, such as Saleae and Total Phase
- Demonstration Boards from companies, such as MikroElektronika, Digilent<sup>®</sup> and Olimex
- Embedded Ethernet Solutions from companies, such as EZ Web Lynx, WIZnet and IPLogika<sup>®</sup>

#### 30.0 ELECTRICAL CHARACTERISTICS

This section provides an overview of the PIC32MX1XX/2XX 28/36/44-pin Family electrical characteristics for devices that operate at 40 MHz. Refer to **Section 31.0** "50 MHz Electrical Characteristics" for additional specifications for operations at higher frequency. Additional information will be provided in future revisions of this document as it becomes available.

Absolute maximum ratings for the PIC32MX1XX/2XX 28/36/44-pin Family devices are listed below. Exposure to these maximum rating conditions for extended periods may affect device reliability. Functional operation of the device at these or any other conditions, above the parameters indicated in the operation listings of this specification, is not implied.

### **Absolute Maximum Ratings**

#### (See Note 1)

Ambient temperature under bias	40°C to +105°C
Storage temperature	65°C to +150°C
Voltage on VDD with respect to Vss	0.3V to +4.0V
Voltage on any pin that is not 5V tolerant, with respect to Vss (Note 3)	0.3V to (VDD + 0.3V)
Voltage on any 5V tolerant pin with respect to Vss when VDD ≥ 2.3V (Note 3)	0.3V to +5.5V
Voltage on any 5V tolerant pin with respect to Vss when VDD < 2.3V (Note 3)	0.3V to +3.6V
Voltage on D+ or D- pin with respect to VusB3v3	0.3V to (VUSB3V3 + 0.3V)
Voltage on VBUS with respect to VSS	0.3V to +5.5V
Maximum current out of Vss pin(s)	300 mA
Maximum current into VDD pin(s) (Note 2)	300 mA
Maximum output current sunk by any I/O pin	15 mA
Maximum output current sourced by any I/O pin	15 mA
Maximum current sunk by all ports	200 mA
Maximum current sourced by all ports (Note 2)	200 mA

- Note 1: Stresses above those listed under "Absolute Maximum Ratings" may cause permanent damage to the device. This is a stress rating only and functional operation of the device at those or any other conditions, above those indicated in the operation listings of this specification, is not implied. Exposure to maximum rating conditions for extended periods may affect device reliability.
  - 2: Maximum allowable current is a function of device maximum power dissipation (see Table 30-2).
  - **3:** See the "Pin Diagrams" section for the 5V tolerant pins.

#### 30.1 DC Characteristics

#### TABLE 30-1: OPERATING MIPS VS. VOLTAGE

Characteristic VDD Range Temp. Range		Max. Frequency	
Characteristic	(in Volts) <sup>(1)</sup> (in °C)	PIC32MX1XX/2XX 28/36/44-pin Family	
DC5	2.3-3.6V	-40°C to +85°C	40 MHz
DC5b	2.3-3.6V	-40°C to +105°C	40 MHz

**Note 1:** Overall functional device operation at VBORMIN < VDD < VDDMIN is tested, but not characterized. All device Analog modules, such as ADC, etc., will function, but with degraded performance below VDDMIN. Refer to parameter BO10 in Table 30-11 for BOR values.

#### TABLE 30-2: THERMAL OPERATING CONDITIONS

Rating	Symbol	Min.	Typical	Max.	Unit
Industrial Temperature Devices					
Operating Junction Temperature Range	TJ	-40	_	+125	°C
Operating Ambient Temperature Range	TA	-40		+85	°C
V-temp Temperature Devices					
Operating Junction Temperature Range	TJ	-40	_	+140	°C
Operating Ambient Temperature Range	TA	-40	_	+105	°C
Power Dissipation: Internal Chip Power Dissipation: PINT = VDD x (IDD – S IOH)	PD		PINT + PI/C	)	W
I/O Pin Power Dissipation: I/O = S (({VDD – VOH} x IOH) + S (VOL x IOL))					
Maximum Allowed Power Dissipation	PDMAX	(	ΓJ – TA)/θJ	IA	W

### **TABLE 30-3: THERMAL PACKAGING CHARACTERISTICS**

Characteristics	Symbol	Typical	Max.	Unit	Notes
Package Thermal Resistance, 28-pin SSOP	θЈА	71	_	°C/W	1
Package Thermal Resistance, 28-pin SOIC	θЈА	50	_	°C/W	1
Package Thermal Resistance, 28-pin SPDIP	θЈА	42		°C/W	1
Package Thermal Resistance, 28-pin QFN	θЈА	35	_	°C/W	1
Package Thermal Resistance, 36-pin VTLA	θЈА	31	_	°C/W	1
Package Thermal Resistance, 44-pin QFN	θЈА	32	_	°C/W	1
Package Thermal Resistance, 44-pin TQFP	θЈА	45	_	°C/W	1
Package Thermal Resistance, 44-pin VTLA	θЈА	30	_	°C/W	1

**Note 1:** Junction to ambient thermal resistance, Theta-JA (θJA) numbers are achieved by package simulations.

TABLE 30-4: DC TEMPERATURE AND VOLTAGE SPECIFICATIONS

DC CHARACTERISTICS				Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp					
Param. No.	Symbol	Characteristics	Min.	Тур.	Max.	Units	Conditions		
Operati	ng Voltag	e							
DC10	VDD	Supply Voltage (Note 2)	2.3	_	3.6	V	_		
DC12	VDR	RAM Data Retention Voltage (Note 1)	1.75	_	_	V	_		
DC16	VPOR	VDD Start Voltage to Ensure Internal Power-on Reset Signal	1.75	_	2.1	V	_		
DC17	SVDD	VDD Rise Rate to Ensure Internal Power-on Reset Signal	0.00005	_	0.115	V/μs	_		

Note 1: This is the limit to which VDD can be lowered without losing RAM data.

<sup>2:</sup> Overall functional device operation at VBORMIN < VDD < VDDMIN is tested, but not characterized. All device Analog modules, such as ADC, etc., will function, but with degraded performance below VDDMIN. Refer to parameter BO10 in Table 30-11 for BOR values.

#### TABLE 30-5: DC CHARACTERISTICS: OPERATING CURRENT (IDD)

DC CHARA	CTERISTICS	1	Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp						
Parameter No.	Typical <sup>(3)</sup>	Max.	Units	its Conditions					
Operating (	Current (IDD)	(Notes 1, 2, 5)	)						
DC20	2	3	mA	4 MH	Iz (Note 4)				
DC21	7	10.5	mA	1	0 MHz				
DC22	10	15	mA	20 Mi	Hz (Note 4)				
DC23	15	23	mA	30 MHz (Note 4)					
DC24	20	30	mA	40 MHz					
DC25	100	150	μA	+25°C, 3.3V LPRC (31 kHz) (Note 4)					

- **Note 1:** A device's IDD supply current is mainly a function of the operating voltage and frequency. Other factors, such as PBCLK (Peripheral Bus Clock) frequency, number of peripheral modules enabled, internal code execution pattern, execution from Program Flash memory vs. SRAM, I/O pin loading and switching rate, oscillator type, as well as temperature, can have an impact on the current consumption.
  - 2: The test conditions for IDD measurements are as follows:
    - Oscillator mode is EC (for 8 MHz and below) and EC+PLL (for above 8 MHz) with OSC1 driven by external square wave from rail-to-rail, (OSC1 input clock input over/undershoot < 100 mV required)
    - OSC2/CLKO is configured as an I/O input pin
    - USB PLL oscillator is disabled if the USB module is implemented, PBCLK divisor = 1:8
    - CPU, Program Flash, and SRAM data memory are operational, SRAM data memory Wait states = 1
    - No peripheral modules are operating, (ON bit = 0), but the associated PMD bit is cleared
    - WDT, Clock Switching, Fail-Safe Clock Monitor, and Secondary Oscillator are disabled
    - All I/O pins are configured as inputs and pulled to Vss
    - MCLR = VDD
    - ullet CPU executing while (1) statement from Flash
    - RTCC and JTAG are disabled
  - **3:** Data in "Typical" column is at 3.3V, 25°C at specified operating frequency unless otherwise stated. Parameters are for design guidance only and are not tested.
  - 4: This parameter is characterized, but not tested in manufacturing.
  - **5:** IPD electrical characteristics for devices with 256 KB Flash are only provided as Preliminary information.

TABLE 30-6: DC CHARACTERISTICS: IDLE CURRENT (IIDLE)

DC CHARACTI	ERISTICS		Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp				
Parameter No.	Typical <sup>(2)</sup>	Max.	Units		Conditions		
Idle Current (III	DLE): Core Of	f, Clock on E	Base Current	(Notes 1, 4)			
DC30a	1	1.5	mA		4 MHz (Note 3)		
DC31a	2	3	mA		10 MHz		
DC32a	4	6	mA		20 MHz (Note 3)		
DC33a	5.5	8	mA		30 MHz (Note 3)		
DC34a	7.5	11	mA		40 MHz		
DC37a	100	_	μA	-40°C LPRC (31 k			
DC37b	250	_	μA	+25°C 3.3V (Note 3			
DC37c	380	_	μA				

Note 1: The test conditions for IIDLE current measurements are as follows:

- Oscillator mode is EC (for 8 MHz and below) and EC+PLL (for above 8 MHz) with OSC1 driven by external square wave from rail-to-rail, (OSC1 input clock input over/undershoot < 100 mV required)</li>
- OSC2/CLKO is configured as an I/O input pin
- USB PLL oscillator is disabled if the USB module is implemented, PBCLK divisor = 1:8
- CPU is in Idle mode (CPU core Halted), and SRAM data memory Wait states = 1
- No peripheral modules are operating, (ON bit = 0), but the associated PMD bit is cleared
- · WDT, Clock Switching, Fail-Safe Clock Monitor, and Secondary Oscillator are disabled
- · All I/O pins are configured as inputs and pulled to Vss
- MCLR = VDD
- · RTCC and JTAG are disabled
- **2:** Data in the "Typical" column is at 3.3V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.
- 3: This parameter is characterized, but not tested in manufacturing.
- 4: IIDLE electrical characteristics for devices with 256 KB Flash are only provided as Preliminary information.

#### TABLE 30-7: DC CHARACTERISTICS: POWER-DOWN CURRENT (IPD)

DC CHA	RACTERIS	TICS		Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \leq \text{Ta} \leq +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \leq \text{Ta} \leq +105^{\circ}\text{C}$ for V-temp						
Param. No.	Typical <sup>(2)</sup>	Max.	Units		Conditions					
Power-E	own Curre	nt (IPD) (No	tes 1, 5)							
DC40k	44	70	μА	-40°C						
DC40I	44	70	μΑ	+25°C	Base Power-Down Current					
DC40n	168	259	μΑ	+85°C	Dase Fower-Down Current					
DC40m	335	536	μΑ	+105°C						
Module	Differential	Current								
DC41e	5	20	μΑ	3.6V Watchdog Timer Current: ΔIWDT (Note 3)						
DC42e	23	50	μА	3.6V RTCC + Timer1 w/32 kHz Crystal: △IRTCC (Note 3)						
DC43d	1000	1100	μА	3.6V ADC: ΔIADC (Notes 3,4)						

**Note 1:** The test conditions for IPD current measurements are as follows:

- Oscillator mode is EC (for 8 MHz and below) and EC+PLL (for above 8 MHz) with OSC1 driven by external square wave from rail-to-rail, (OSC1 input clock input over/undershoot < 100 mV required)
- · OSC2/CLKO is configured as an I/O input pin
- USB PLL oscillator is disabled if the USB module is implemented, PBCLK divisor = 1:8
- CPU is in Sleep mode, and SRAM data memory Wait states = 1
- No peripheral modules are operating, (ON bit = 0), but the associated PMD bit is set
- WDT, Clock Switching, Fail-Safe Clock Monitor, and Secondary Oscillator are disabled
- All I/O pins are configured as inputs and pulled to Vss
- MCLR = VDD
- RTCC and JTAG are disabled
- **2:** Data in the "Typical" column is at 3.3V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.
- 3: The  $\Delta$  current is the additional current consumed when the module is enabled. This current should be added to the base IPD current.
- 4: Test conditions for ADC module differential current are as follows: Internal ADC RC oscillator enabled.
- 5: IPD electrical characteristics for devices with 256 KB Flash are only provided as Preliminary information.

TABLE 30-8: DC CHARACTERISTICS: I/O PIN INPUT SPECIFICATIONS

DC CHA	ARACTER	RISTICS	Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp					
Param. No.	Symbol	Characteristics	Min.	Typical <sup>(1)</sup> Max.		Units	Conditions	
	VIL	Input Low Voltage						
DI10		I/O Pins with PMP	Vss	_	0.15 VDD	V		
		I/O Pins	Vss	_	0.2 VDD	V		
DI18		SDAx, SCLx	Vss	_	0.3 VDD	V	SMBus disabled (Note 4)	
DI19		SDAx, SCLx	Vss	_	0.8	V	SMBus enabled (Note 4)	
	VIH	Input High Voltage						
DI20		I/O Pins not 5V-tolerant <sup>(5)</sup>	0.65 VDD	_	VDD	V	(Note 4,6)	
		I/O Pins 5V-tolerant with PMP <sup>(5)</sup>	0.25 VDD + 0.8V	_	5.5	V	(Note 4,6)	
		I/O Pins 5V-tolerant <sup>(5)</sup>	0.65 VDD	_	5.5	V		
DI28		SDAx, SCLx	0.65 VDD	_	5.5	V	SMBus disabled (Note 4,6)	
DI29		SDAx, SCLx	2.1	_	5.5	V	SMBus enabled, 2.3V ≤ VPIN ≤ 5.5 ( <b>Note 4,6</b> )	
DI30	ICNPU	Change Notification Pull-up Current	_	_	-50	μΑ	VDD = 3.3V, VPIN = VSS (Note 3,6)	
DI31	ICNPD	Change Notification Pull-down Current <sup>(4)</sup>	_	_	-50	μA	VDD = 3.3V, VPIN = VDD	
	liL	Input Leakage Current (Note 3)						
DI50		I/O Ports	_	_	<u>+</u> 1	μΑ	Vss ≤ VPIN ≤ VDD, Pin at high-impedance	
DI51		Analog Input Pins	_	_	<u>+</u> 1	μΑ	VSS ≤ VPIN ≤ VDD, Pin at high-impedance	
DI55		MCLR <sup>(2)</sup>	_	_	<u>+</u> 1	μΑ	$Vss \leq Vpin \leq Vdd$	
DI56		OSC1	_	_	<u>+</u> 1	μА	$\label{eq:VSS} \begin{array}{l} \text{VSS} \leq \text{VPIN} \leq \text{VDD,} \\ \text{XT and HS modes} \end{array}$	

- **Note 1:** Data in "Typical" column is at 3.3V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.
  - 2: The leakage current on the MCLR pin is strongly dependent on the applied voltage level. The specified levels represent normal operating conditions. Higher leakage current may be measured at different input voltages.
  - 3: Negative current is defined as current sourced by the pin.
  - 4: This parameter is characterized, but not tested in manufacturing.
  - 5: See the "Pin Diagrams" section for the 5V-tolerant pins.
  - **6:** The VIH specifications are only in relation to externally applied inputs, and not with respect to the user-selectable internal pull-ups. External open drain input signals utilizing the internal pull-ups of the PIC32 device are guaranteed to be recognized only as a logic "high" internally to the PIC32 device, provided that the external load does not exceed the minimum value of ICNPU. For External "input" logic inputs that require a pull-up source, to guarantee the minimum VIH of those components, it is recommended to use an external pull-up resistor rather than the internal pull-ups of the PIC32 device.

#### TABLE 30-9: DC CHARACTERISTICS: I/O PIN INPUT INJECTION CURRENT SPECIFICATIONS

DC CHA	ARACTER	EISTICS	Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $ -40^{\circ}C \leq TA \leq +85^{\circ}C \text{ for Industrial} \\ -40^{\circ}C \leq TA \leq +105^{\circ}C \text{ for V-temp} $						
Param. No.	Symbol	Characteristics	Min.	Typ. <sup>(1)</sup>	Max.	Units	Conditions		
DI60a	licL	Input Low Injection Current	0	_	<sub>-5</sub> (2,5)	mA	This parameter applies to all pins, with the exception of the power pins.		
DI60b	lich	Input High Injection Current	0	_	+5(3,4,5)	mA	This parameter applies to all pins, with the exception of all 5V tolerant pins, and the SOSCI, SOSCO, OSC1, D+, and D- pins.		
DI60c	∑lict	Total Input Injection Current (sum of all I/O and Control pins)	-20 <sup>(6)</sup>		+20 <sup>(6)</sup>	mA	Absolute instantaneous sum of all $\pm$ input injection currents from all I/O pins (   IICL +   IICH   ) $\leq \Sigma$ IICT )		

- **Note 1:** Data in "Typical" column is at 3.3V, +25°C unless otherwise stated. Parameters are for design guidance only and are not tested.
  - 2: VIL source < (VSS 0.3). Characterized but not tested.
  - 3: VIH source > (VDD + 0.3) for non-5V tolerant pins only.
  - **4:** Digital 5V tolerant pins do not have an internal high side diode to VDD, and therefore, cannot tolerate any "positive" input injection current.
  - 5: Injection currents > | 0 | can affect the ADC results by approximately 4 to 6 counts (i.e., VIH Source > (VDD + 0.3) or VIL source < (Vss 0.3)).
  - 6: Any number and/or combination of I/O pins not excluded under IICL or IICH conditions are permitted provided the "absolute instantaneous" sum of the input injection currents from all pins do not exceed the specified limit. If Note 2, IICL = (((Vss 0.3) VIL source) / Rs). If Note 3, IICH = ((IICH source (VDD + 0.3)) / RS). RS = Resistance between input source voltage and device pin. If (Vss 0.3) ≤ Vsource ≤ (VDD + 0.3), injection current = 0.

TABLE 30-10: DC CHARACTERISTICS: I/O PIN OUTPUT SPECIFICATIONS

DC CHARACTERISTICS			Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated)				
Param.	Symbol	Characteristic	Min.	Тур.	Max.	Units	Conditions
DO10	Vol	Output Low Voltage I/O Pins	_	_	0.4	V	IOL ≤ 10 mA, VDD = 3.3V
		Output High Voltage	1.5 <sup>(1)</sup>	_	_		IOH $\geq$ -14 mA, VDD = 3.3V
DO20	VOH I/O Pins		2.0 <sup>(1)</sup>	_	_	V	IOH $\geq$ -12 mA, VDD = 3.3V
DO20	VOH	Jn		_	_	V	IOH $\geq$ -10 mA, VDD = 3.3V
			3.0 <sup>(1)</sup>		_		IOH $\geq$ -7 mA, VDD = 3.3V

Note 1: Parameters are characterized, but not tested.

#### TABLE 30-11: ELECTRICAL CHARACTERISTICS: BOR

INDLL	JU-11. L	LECTRICAL CHARACTER	51105.	DOIL						
DC CHARACTERISTICS			Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp							
Param. No.	Symbol	Characteristics	Min. <sup>(1)</sup> Typical Max. Units Conditions							
BO10	VBOR	BOR Event on VDD transition high-to-low <sup>(2)</sup>	2.0	_	2.3	V	_			

Note 1: Parameters are for design guidance only and are not tested in manufacturing.

<sup>2:</sup> Overall functional device operation at VBORMIN < VDD < VDDMIN is tested, but not characterized. All device Analog modules, such as ADC, etc., will function, but with degraded performance below VDDMIN.

TABLE 30-12: DC CHARACTERISTICS: PROGRAM MEMORY

DC CHARACTERISTICS			Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp							
Param. No.	Symbol	Characteristics	Min.	Typical <sup>(1)</sup>	Conditions					
		Program Flash Memory <sup>(3)</sup>								
D130	EP	Cell Endurance	20,000	_	_	E/W	_			
D131	VPR	VDD for Read	2.3	_	3.6	V	_			
D132	VPEW	VDD for Erase or Write	2.3	_	3.6	V	_			
D134	TRETD	Characteristic Retention	20	_	_	Year	Provided no other specifications are violated			
D135	IDDP	Supply Current during Programming	_	10	_	mA	_			
	Tww	Word Write Cycle Time		411	_	es	See Note 4			
D136	Trw	Row Write Cycle Time	—   411   —   <u>%</u>   See <b>Note 4</b>   See <b>Note 2,4</b>							
D137	TPE	Page Erase Cycle Time		20011	_	FRC (	See Note 4			
	TCE	Chip Erase Cycle Time	_	80180		H.	See Note 4			

- Note 1: Data in "Typical" column is at 3.3V, 25°C unless otherwise stated.
  - 2: The minimum SYSCLK for row programming is 4 MHz. Care should be taken to minimize bus activities during row programming, such as suspending any memory-to-memory DMA operations. If heavy bus loads are expected, selecting Bus Matrix Arbitration mode 2 (rotating priority) may be necessary. The default Arbitration mode is mode 1 (CPU has lowest priority).
  - **3:** Refer to the "PIC32 Flash Programming Specification" (DS60001145) for operating conditions during programming and erase cycles.
  - 4: Translating this value to seconds depends on the FRC accuracy (See Table 30-19) and FRC tuning values (See Register 8-2).

### **TABLE 30-13: COMPARATOR SPECIFICATIONS**

DC CHA	DC CHARACTERISTICS			Standard Operating Conditions (see Note 4): 2.3V to 3.6 (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp						
Param. No.	Symbol	Min.	Typical	Max.	Units	Comments				
D300	VIOFF	Input Offset Voltage	_	±7.5	±25	mV	AVDD = VDD, AVSS = VSS			
D301	VICM	Input Common Mode Voltage	0	_	VDD	V	AVDD = VDD, AVSS = VSS (Note 2)			
D302	CMRR	Common Mode Rejection Ratio	55	_	_	dB	Max Vicm = (VDD - 1)V (Note 2)			
D303A	TRESP	Large Signal Response Time	_	150	400	ns	AVDD = VDD, AVSS = VSS (Note 1,2)			
D303B	TSRESP	Small Signal Response Time	_	1	_	μS	This is defined as an input step of 50 mV with 15 mV of overdrive (Note 2)			
D304	D304 ON2ov Comparator Enabled to Output Valid		_		10	μs	Comparator module is configured before setting the comparator ON bit (Note 2)			
D305	IVREF	Internal Voltage Reference	1.14	1.2	1.26	V	_			
D312	TSET	Internal Comparator Voltage DRC Reference Setting time	_	_	10	μs	(Note 3)			

- **Note 1:** Response time measured with one comparator input at (VDD 1.5)/2, while the other input transitions from Vss to VDD.
  - 2: These parameters are characterized but not tested.
  - 3: Settling time measured while CVRR = 1 and CVR<3:0> transitions from '0000' to '1111'. This parameter is characterized, but not tested in manufacturing.
  - **4:** The Comparator module is functional at VBORMIN < VDD < VDDMIN, but with degraded performance. Unless otherwise stated, module functionality is tested, but not characterized.

#### **TABLE 30-14: COMPARATOR VOLTAGE REFERENCE SPECIFICATIONS**

DC CHARACTERISTICS			Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp							
Param. No.	Symbol	Characteristics	Min.	Тур.	Max.	Units	Comments			
D312	TSET	Internal 4-bit DAC Comparator Reference Settling time	_	_	10	μs	See Note 1			
D313	DACREFH		AVss	_	AVDD	V	CVRSRC with CVRSS = 0			
		Reference Range	VREF-	_	VREF+	V	CVRSRC with CVRSS = 1			
D314	DVREF	CVREF Programmable Output Range	0	_	0.625 x DACREFH	V	0 to 0.625 DACREFH with DACREFH/24 step size			
			0.25 x DACREFH	_	0.719 x DACREFH	V	0.25 x DACREFH to 0.719 DACREFH with DACREFH/32 step size			
D315	DACRES	Resolution	_	_	DACREFH/24	_	CVRCON <cvrr> = 1</cvrr>			
			_	_	DACREFH/32	_	CVRCON <cvrr> = 0</cvrr>			
D316	DACACC	Absolute Accuracy <sup>(2)</sup>	_	_	1/4	LSB	DACREFH/24, CVRCON <cvrr> = 1</cvrr>			
			_	_	1/2	LSB	DACREFH/32, CVRCON <cvrr> = 0</cvrr>			

**Note 1:** Settling time was measured while CVRR = 1 and CVR<3:0> transitions from '0000' to '1111'. This parameter is characterized, but is not tested in manufacturing.

#### **TABLE 30-15: INTERNAL VOLTAGE REGULATOR SPECIFICATIONS**

DC CHARACTERISTICS			Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp					
Param. No. Characteristics				Typical	Max.	Units	Comments	
D321	CEFC External Filter Capacitor Value		8	10	ı	μF	Capacitor must be low series resistance (1 ohm). Typical voltage on the VCAP pin is 1.8V.	

<sup>2:</sup> These parameters are characterized but not tested.

# 30.2 AC Characteristics and Timing Parameters

The information contained in this section defines PIC32MX1XX/2XX 28/36/44-pin Family AC characteristics and timing parameters.

FIGURE 30-1: LOAD CONDITIONS FOR DEVICE TIMING SPECIFICATIONS





TABLE 30-16: CAPACITIVE LOADING REQUIREMENTS ON OUTPUT PINS

	7.22.00 10. 07.17.01.112.20.12.110 1.2.20.12.11.0 01.00.1 01.1 11.0									
AC CHARACTERISTICS			Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{Ta} \le +105^{\circ}\text{C}$ for V-temp							
Param. No.	Symbol	Characteristics	Min. Typical <sup>(1)</sup> Max. Units Conditions							
DO50	Cosco	OSC2 Pin	_	_	15	pF	In XT ans HS modes, when external crystal is used to drive OSC1			
DO56	Сю	All I/O pins and OSC2	50 pF EC mode							
DO58	Св	SCLx, SDAx	— — 400 pF In I <sup>2</sup> C mode							

**Note 1:** Data in "Typical" column is at 3.3V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.

#### FIGURE 30-2: EXTERNAL CLOCK TIMING



#### **TABLE 30-17: EXTERNAL CLOCK TIMING REQUIREMENTS**

AC CHA	AC CHARACTERISTICS			Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp							
Param. No.	Symbol	Characteristics	Min.	Typical <sup>(1)</sup>	-40°C ≤ IA ≤ Max.	+105°C Units	Conditions				
OS10	Fosc	External CLKI Frequency (External clocks allowed only in EC and ECPLL modes)	DC 4		40 40	MHz MHz	EC (Note 4) ECPLL (Note 3)				
OS11		Oscillator Crystal Frequency	3	_	10	MHz	XT (Note 4)				
OS12			4	_	10	MHz	XTPLL (Notes 3,4)				
OS13			10	_	25	MHz	HS (Note 5)				
OS14			10	_	25	MHz	HSPLL (Notes 3,4)				
OS15			32	32.768	100	kHz	Sosc (Note 4)				
OS20	Tosc	Tosc = 1/Fosc = Tcy (Note 2)	_	_	_	_	See parameter OS10 for Fosc value				
OS30	TosL, TosH	External Clock In (OSC1) High or Low Time	0.45 x Tosc	_	_	ns	EC (Note 4)				
OS31	TosR, TosF	External Clock In (OSC1) Rise or Fall Time	_	_	0.05 x Tosc	ns	EC (Note 4)				
OS40	Тоѕт	Oscillator Start-up Timer Period (Only applies to HS, HSPLL, XT, XTPLL and Sosc Clock Oscillator modes)	_	1024	_	Tosc	(Note 4)				
OS41	TFSCM	Primary Clock Fail Safe Time-out Period	_	2	_	ms	(Note 4)				
OS42	Gм	External Oscillator Transconductance (Primary Oscillator only)	_	12	_	mA/V	VDD = 3.3V, TA = +25°C (Note 4)				

- **Note 1:** Data in "Typical" column is at 3.3V, 25°C unless otherwise stated. Parameters are characterized but are not tested.
  - 2: Instruction cycle period (TCY) equals the input oscillator time base period. All specified values are based on characterization data for that particular oscillator type under standard operating conditions with the device executing code. Exceeding these specified limits may result in an unstable oscillator operation and/or higher than expected current consumption. All devices are tested to operate at "min." values with an external clock applied to the OSC1/CLKI pin.
  - **3:** PLL input requirements: 4 MHz ≤ FPLLIN ≤ 5 MHz (use PLL prescaler to reduce Fosc). This parameter is characterized, but tested at 10 MHz only at manufacturing.
  - 4: This parameter is characterized, but not tested in manufacturing.

2

+0.25

ms

%

period

Measured over 100 ms

#### **TABLE 30-18: PLL CLOCK TIMING SPECIFICATIONS**

AC CHARACTERISTICS			(unless of	Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp						
Param. No. Symbol Characterist			cs <sup>(1)</sup>	Min. Typical Max. Units Conditions						
OS50	OS50 FPLLI PLL Voltage Controlled Oscillator (VCO) Input Frequency Range		3.92	_	5	MHz	ECPLL, HSPLL, XTPLL, FRCPLL modes			
OS51 Fsys On-Chip VCO System Frequency		m	60	_	120	MHz	_			

-0.25

Note 1: These parameters are characterized, but not tested in manufacturing.

PLL Start-up Time (Lock Time)

(Period Jitter or Cumulative)

CLKO Stability<sup>(2)</sup>

2: This jitter specification is based on clock-cycle by clock-cycle measurements. To get the effective jitter for individual time-bases on communication clocks, use the following formula:

$$Effective Jitter = \frac{D_{CLK}}{\sqrt{\frac{SYSCLK}{CommunicationClock}}}$$

For example, if SYSCLK = 40 MHz and SPI bit rate = 20 MHz, the effective jitter is as follows:

$$Effective Jitter = \frac{D_{CLK}}{\sqrt{\frac{40}{20}}} = \frac{D_{CLK}}{1.41}$$

#### **TABLE 30-19: INTERNAL FRC ACCURACY**

OS52

OS53

**TLOCK** 

DCLK

AC CHA	RACTERISTICS	Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp								
Param. No.	Characteristics		Typical	Max.	Units	Conditions				
Internal	Internal FRC Accuracy @ 8.00 MHz <sup>(1)</sup>									
F20b	FRC	-0.9	_	+0.9	9 % —					


Note 1: Frequency calibrated at 25°C and 3.3V. The TUN bits can be used to compensate for temperature drift.

#### **TABLE 30-20: INTERNAL LPRC ACCURACY**

AC CHA	RACTERISTICS	Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \leq \text{TA} \leq +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \leq \text{TA} \leq +105^{\circ}\text{C}$ for V-temp							
Param. No.	Characteristics	Min.	Typical	Max.	Units	Conditions			
LPRC @	) 31.25 kHz <sup>(1)</sup>								
F21	LPRC	-15	_	+15	%	_			

Note 1: Change of LPRC frequency as VDD changes.

#### FIGURE 30-3: I/O TIMING CHARACTERISTICS



#### **TABLE 30-21: I/O TIMING REQUIREMENTS**


AC CHARACTERISTICS			(unless other	Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{Ta} \le +105^{\circ}\text{C}$ for V-temp						
Param. No. Symbol Characteri			stics <sup>(2)</sup>	Min. Typical <sup>(1)</sup> Max. Units Con						
DO31	TioR	Port Output Rise Tin	ne	_	5	15	ns	VDD < 2.5V		
				_	5	10	ns	VDD > 2.5V		
DO32	TioF	Port Output Fall Tim	е	_	5	15	ns	VDD < 2.5V		
				_	5	10	ns	VDD > 2.5V		
DI35 TINP INTx Pin High or Low Time		w Time	10	_		ns	_			
DI40 TRBP CNx High or Low Time (ir			me (input)	2	_	_	Tsysclk	_		

Note 1: Data in "Typical" column is at 3.3V, 25°C unless otherwise stated.


2: This parameter is characterized, but not tested in manufacturing.

#### FIGURE 30-4: POWER-ON RESET TIMING CHARACTERISTICS

Internal Voltage Regulator Enabled
Clock Sources = (FRC, FRCDIV, FRCDIV16, FRCPLL, EC, ECPLL and LPRC)




Internal Voltage Regulator Enabled Clock Sources = (HS, HSPLL, XT, XTPLL and Sosc)



Note 1: The power-up period will be extended if the power-up sequence completes before the device exits from BOR (VDD < VDDMIN).

2: Includes interval voltage regulator stabilization delay.

FIGURE 30-5: EXTERNAL RESET TIMING CHARACTERISTICS




**TABLE 30-22: RESETS TIMING** 

AC CHARACTERISTICS				Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp						
Param. No.	Symbol	Characteristics <sup>(1)</sup>	Min.	Typical <sup>(2)</sup>	Max.	Units	Conditions			
SY00	Tpu	Power-up Period Internal Voltage Regulator Enabled	_	400	600	μS	_			
SY02	TSYSDLY	System Delay Period: Time Required to Reload Device Configuration Fuses plus SYSCLK Delay before First instruction is Fetched.	_	1 μs + 8 SYSCLK cycles	_	_	_			
SY20	TMCLR	MCLR Pulse Width (low)	2	-	_	μS	_			
SY30	TBOR	BOR Pulse Width (low)	_	1	_	μS	_			

Note 1: These parameters are characterized, but not tested in manufacturing.

2: Data in "Typ" column is at 3.3V, 25°C unless otherwise stated. Characterized by design but not tested.

FIGURE 30-6: TIMER1, 2, 3, 4, 5 EXTERNAL CLOCK TIMING CHARACTERISTICS



#### TABLE 30-23: TIMER1 EXTERNAL CLOCK TIMING REQUIREMENTS

AC CHA	ARACTERIS'	ГІСЅ <sup>(1)</sup>		(un	J 1		+85°C	for Ind	
Param. No.	Symbol	Charac	teristics <sup>(2)</sup>	Min. Typical Max. Units Condi					Conditions
TA10	TTXH	TxCK	Synchrono	us,	[(12.5 ns or 1 TPB)/N	1 —	_	ns	Must also meet

No.	Symbol	Charac	teristics <sup>(2)</sup>	Min.	Typical	Max.	Units	Conditions
TA10	ТтхН	TxCK High Time	Synchronous, with prescaler	[(12.5 ns or 1 TPB)/N] + 25 ns	_	_	ns	Must also meet parameter TA15
			Asynchronous, with prescaler	10	_	_	ns	_
TA11	TTXL	TxCK Low Time	Synchronous, with prescaler	[(12.5 ns or 1 TPB)/N] + 25 ns	_	_	ns	Must also meet parameter TA15
			Asynchronous, with prescaler	10	_	_	ns	_
TA15	ТтхР	TxCK Input Period	Synchronous, with prescaler	[(Greater of 25 ns or 2 TPB)/N] + 30 ns	_	_	ns	VDD > 2.7V
				[(Greater of 25 ns or 2 TPB)/N] + 50 ns	_	_	ns	VDD < 2.7V
			Asynchronous, with prescaler	20	_	_	ns	V <sub>DD</sub> > 2.7V (Note 3)
				50	_	_	ns	V <sub>DD</sub> < 2.7V (Note 3)
OS60	Fт1			32	_	100	kHz	_
TA20	TCKEXTMRL	Delay from E Clock Edge t Increment	xternal TxCK o Timer	_	_	1	Трв	_

Note 1: Timer1 is a Type A timer.

2: This parameter is characterized, but not tested in manufacturing.

**3:** N = Prescale Value (1, 8, 64, 256).

TABLE 30-24: TIMER2, 3, 4, 5 EXTERNAL CLOCK TIMING REQUIREMENTS

AC CH	ARACTERIS	Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp							
Param. No.	Symbol	Cha	racteristic	ics <sup>(1)</sup> Min. Max. Units Conditions					ions
TB10	ТтхН	TxCK High Time	Synchron- prescaler	,	[(12.5 ns or 1 TPB)/N] + 25 ns	_	ns	Must also meet parameter TB15	N = prescale value (1, 2, 4, 8,
TB11	TTXL	TxCK Low Time	Synchron prescaler	ous, with	[(12.5 ns or 1 TPB)/N] + 25 ns	_	ns	Must also meet parameter TB15	16, 32, 64, 256)
TB15	TTXP	TxCK	Synchron	ous, with	[(Greater of [(25 ns or	_	ns	VDD > 2.7V	

2 TPB/N] + 30 ns

[(Greater of [(25 ns or

2 TPB)/N] + 50 ns

Note 1: These parameters are characterized, but not tested in manufacturing.

Clock Edge to Timer Increment

prescaler


Input

TB20

Period

TCKEXTMRL Delay from External TxCK

### FIGURE 30-7: INPUT CAPTURE (CAPx) TIMING CHARACTERISTICS



#### TABLE 30-25: INPUT CAPTURE MODULE TIMING REQUIREMENTS


AC CHARACTERISTICS Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp								
Param. No.	Symbol	Charac	cteristics <sup>(1)</sup>	Min.	Max.	Units	Cor	nditions
IC10	TccL	ICx Input	t Low Time	[(12.5 ns or 1 TPB)/N] + 25 ns	_	ns	Must also meet parameter IC15.	N = prescale value (1, 4, 16)
IC11	TccH	ICx Input	t High Time	[(12.5 ns or 1 TPB)/N] + 25 ns	_	ns	Must also meet parameter IC15.	
IC15	TccP	ICx Input	t Period	[(25 ns or 2 TPB)/N] + 50 ns	_	ns	_	

Note 1: These parameters are characterized, but not tested in manufacturing.

VDD < 2.7V

Трв

#### FIGURE 30-8: OUTPUT COMPARE MODULE (OCx) TIMING CHARACTERISTICS



#### TABLE 30-26: OUTPUT COMPARE MODULE TIMING REQUIREMENTS

AC CHA	AC CHARACTERISTICS			Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated)   Operating temperature $-40^{\circ}\text{C} \leq \text{TA} \leq +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \leq \text{TA} \leq +105^{\circ}\text{C}$ for V-temp					
Param. No.	Symbol	Characteristics <sup>(1)</sup>	Min.	Typical <sup>(2)</sup>	Max.	Units	Conditions		
OC10	TccF	OCx Output Fall Time	_	_	_	ns	See parameter DO32		
OC11	TccR	OCx Output Rise Time	ns See paramete						

Note 1: These parameters are characterized, but not tested in manufacturing.

2: Data in "Typical" column is at 3.3V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.

#### FIGURE 30-9: OCx/PWM MODULE TIMING CHARACTERISTICS




TABLE 30-27: SIMPLE OCx/PWM MODE TIMING REQUIREMENTS

AC CHARACTERISTICS			Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp					
Param No.	Symbol	Characteristics <sup>(1)</sup>	Min Typical <sup>(2)</sup> Max Units				Conditions	
OC15	TFD	Fault Input to PWM I/O Change	_	_	50	ns	_	
OC20	TFLT	Fault Input Pulse Width	50	_	_	ns	_	

Note 1: These parameters are characterized, but not tested in manufacturing.

2: Data in "Typical" column is at 3.3V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.

FIGURE 30-10: SPIX MODULE MASTER MODE (CKE = 0) TIMING CHARACTERISTICS




TABLE 30-28: SPIx MASTER MODE (CKE = 0) TIMING REQUIREMENTS

AC CHA	ARACTERIST	TICS	Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{Ta} \le +105^{\circ}\text{C}$ for V-temp						
Param. No.	Symbol	Characteristics <sup>(1)</sup>	Min.	Typical <sup>(2)</sup>	Max.	Units	Conditions		
SP10	TscL	SCKx Output Low Time (Note 3)	Tsck/2	_	_	ns	_		
SP11	TscH	SCKx Output High Time (Note 3)	Tsck/2	_		ns	_		
SP20	TscF	SCKx Output Fall Time (Note 4)	_			ns	See parameter DO32		
SP21	TscR	SCKx Output Rise Time (Note 4)	_	_	_	ns	See parameter DO31		
SP30	TDOF	SDOx Data Output Fall Time (Note 4)	_	_		ns	See parameter DO32		
SP31	TDOR	SDOx Data Output Rise Time (Note 4)	_	_		ns	See parameter DO31		
SP35	TscH2DoV,	SDOx Data Output Valid after	_	_	15	ns	VDD > 2.7V		
	TscL2doV	SCKx Edge	_		20	ns	VDD < 2.7V		
SP40	TDIV2scH, TDIV2scL	Setup Time of SDIx Data Input to SCKx Edge	10	_		ns	_		
SP41	TSCH2DIL, TSCL2DIL	Hold Time of SDIx Data Input to SCKx Edge	10	_	_	ns	_		

- Note 1: These parameters are characterized, but not tested in manufacturing.
  - **2:** Data in "Typical" column is at 3.3V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.
  - **3:** The minimum clock period for SCKx is 50 ns. Therefore, the clock generated in Master mode must not violate this specification.
  - 4: Assumes 50 pF load on all SPIx pins.

FIGURE 30-11: SPIX MODULE MASTER MODE (CKE = 1) TIMING CHARACTERISTICS




TABLE 30-29: SPIX MODULE MASTER MODE (CKE = 1) TIMING REQUIREMENTS

AC CHA	ARACTERIST	rics	Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated)   Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp					
Param. No.	Symbol	Characteristics <sup>(1)</sup>	Min.	Typ. <sup>(2)</sup>	Max.	Units	Conditions	
SP10	TscL	SCKx Output Low Time (Note 3)	Tsck/2	_		ns	_	
SP11	TscH	SCKx Output High Time (Note 3)	Tsck/2	_	_	ns	_	
SP20	TscF	SCKx Output Fall Time (Note 4)	_	_	_	ns	See parameter DO32	
SP21	TscR	SCKx Output Rise Time (Note 4)	_	_	_	ns	See parameter DO31	
SP30	TDOF	SDOx Data Output Fall Time (Note 4)	_	_	_	ns	See parameter DO32	
SP31	TDOR	SDOx Data Output Rise Time (Note 4)	_	_	_	ns	See parameter DO31	
SP35	TscH2DoV,	SDOx Data Output Valid after	_	_	15	ns	VDD > 2.7V	
	TscL2DoV	SCKx Edge	_	_	20	ns	VDD < 2.7V	
SP36	TDOV2SC, TDOV2SCL	SDOx Data Output Setup to First SCKx Edge	15	_	_	ns	_	
SP40	TDIV2scH,	Setup Time of SDIx Data Input to	15	_	_	ns	VDD > 2.7V	
	TDIV2scL	SCKx Edge	20	_	_	ns	VDD < 2.7V	
SP41	,	Hold Time of SDIx Data Input	15	_	_	ns	VDD > 2.7V	
	TscL2dlL	to SCKx Edge	20	_	_	ns	VDD < 2.7V	

- Note 1: These parameters are characterized, but not tested in manufacturing.
  - **2:** Data in "Typical" column is at 3.3V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.
  - **3:** The minimum clock period for SCKx is 50 ns. Therefore, the clock generated in Master mode must not violate this specification.
  - 4: Assumes 50 pF load on all SPIx pins.

FIGURE 30-12: SPIX MODULE SLAVE MODE (CKE = 0) TIMING CHARACTERISTICS




TABLE 30-30: SPIX MODULE SLAVE MODE (CKE = 0) TIMING REQUIREMENTS

AC CHA	ARACTERIS	TICS	(unless o	therwis	e stated ture -40	i) °C≤TA	: 2.3V to 3.6V ≤ +85°C for Industrial ≤ +105°C for V-temp
Param. No.	Symbol						
SP70	TscL	SCKx Input Low Time (Note 3)	Tsck/2	_	_	ns	_
SP71	TscH	SCKx Input High Time (Note 3)	Tsck/2	_	_	ns	_
SP72	TscF	SCKx Input Fall Time	_	_	_	ns	See parameter DO32
SP73	TscR	SCKx Input Rise Time	_	_	_	ns	See parameter DO31
SP30	TDOF	SDOx Data Output Fall Time (Note 4)	_	_		ns	See parameter DO32
SP31	TDOR	SDOx Data Output Rise Time (Note 4)	_			ns	See parameter DO31
SP35		SDOx Data Output Valid after	_		15	ns	VDD > 2.7V
	TscL2DoV	SCKx Edge	_	_	20	ns	VDD < 2.7V
SP40	TDIV2scH, TDIV2scL	Setup Time of SDIx Data Input to SCKx Edge	10		1	ns	_
SP41	TscH2DIL, TscL2DIL	Hold Time of SDIx Data Input to SCKx Edge	10	1	_	ns	_
SP50	TssL2scH, TssL2scL	SSx ↓ to SCKx ↑ or SCKx Input	175		_	ns	_
SP51	TssH2DoZ	SSx ↑ to SDOx Output High-Impedance (Note 3)	5	_	25	ns	_
SP52	TscH2ssH TscL2ssH	SSx after SCKx Edge	Tsck + 20	_	_	ns	_

- Note 1: These parameters are characterized, but not tested in manufacturing.
  - **2:** Data in "Typical" column is at 3.3V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.
  - 3: The minimum clock period for SCKx is 50 ns.
  - 4: Assumes 50 pF load on all SPIx pins.

SP60 SSx SP52 SCKx (CKP = 0)SP71 SP70 SP73 SP72 SCKx (CKP = 1)SP72 MSb Bit 14 LSb **SDOx** SP30,SP31 SP51 **SDIx** MSb In LSb In SP41 Note: Refer to Figure 30-1 for load conditions.

FIGURE 30-13: SPIx MODULE SLAVE MODE (CKE = 1) TIMING CHARACTERISTICS

TABLE 30-31: SPIX MODULE SLAVE MODE (CKE = 1) TIMING REQUIREMENTS

AC CHA	ARACTERIS	rics	Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{Ta} \le +105^{\circ}\text{C}$ for V-temp					
Param. No.	Symbol   Characteristics\''   Min   Typical\2/   Max   Units							
SP70	TscL	SCKx Input Low Time (Note 3)	Tsck/2	_		ns	_	
SP71	TscH	SCKx Input High Time (Note 3)	Tsck/2	_	_	ns	_	
SP72	TscF	SCKx Input Fall Time	_	5	10	ns	_	
SP73	TscR	SCKx Input Rise Time	_	5	10	ns	_	
SP30	TDOF	SDOx Data Output Fall Time (Note 4)	_	_	_	ns	See parameter DO32	
SP31	TDOR	SDOx Data Output Rise Time (Note 4)	_	_	_	ns	See parameter DO31	
SP35	TscH2DoV,	SDOx Data Output Valid after	_	_	20	ns	VDD > 2.7V	
	TscL2DoV	SCKx Edge	_	_	30	ns	VDD < 2.7V	
SP40	TDIV2scH, TDIV2scL	Setup Time of SDIx Data Input to SCKx Edge	10	_	_	ns	_	
SP41	TSCH2DIL, TSCL2DIL	Hold Time of SDIx Data Input to SCKx Edge	10	_	_	ns	_	
SP50	TssL2scL	SSx ↓ to SCKx ↓ or SCKx ↑ Input		_	_	ns	_	


- Note 1: These parameters are characterized, but not tested in manufacturing.
  - Data in "Typical" column is at 3.3V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.
  - 3: The minimum clock period for SCKx is 50 ns.
  - Assumes 50 pF load on all SPIx pins.

### TABLE 30-31: SPIx MODULE SLAVE MODE (CKE = 1) TIMING REQUIREMENTS (CONTINUED)

AC CHA	ARACTERIS	TICS	Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{Ta} \le +105^{\circ}\text{C}$ for V-temp				
Param. No.	Symbol	Characteristics <sup>(1)</sup>	) Min. Typical <sup>(2)</sup> Max. Units Conditions				
SP51	TssH2DoZ	SSx ↑ to SDOx Output High-Impedance (Note 4)	5	_	25	ns	_
SP52	TscH2ssH TscL2ssH	SSx ↑ after SCKx Edge	TSCK + 20	_	_	ns	_
SP60	TssL2doV	SDOx Data Output Valid after SSx Edge	_	_	25	ns	_

- Note 1: These parameters are characterized, but not tested in manufacturing.
  - **2:** Data in "Typical" column is at 3.3V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.
  - **3:** The minimum clock period for SCKx is 50 ns.
  - 4: Assumes 50 pF load on all SPIx pins.

#### FIGURE 30-14: I2Cx BUS START/STOP BITS TIMING CHARACTERISTICS (MASTER MODE)



### FIGURE 30-15: I2Cx BUS DATA TIMING CHARACTERISTICS (MASTER MODE)




TABLE 30-32: I2Cx BUS DATA TIMING REQUIREMENTS (MASTER MODE)

AC CHA	RACTER	ISTICS		Standard Operation (unless otherwise Operating temperations)	e <b>stated)</b> iture -40	)°C ≤ TA ≤	SV to 3.6V +85°C for Industrial +105°C for V-temp
Param. No.	Symbol	Charact	eristics	Min. <sup>(1)</sup>	Max.	Units	Conditions
IM10	TLO:SCL	Clock Low Time	100 kHz mode	TPB * (BRG + 2)	_	μS	_
			400 kHz mode	Трв * (BRG + 2)	_	μS	_
			1 MHz mode (Note 2)	Трв * (BRG + 2)	_	μs	_
IM11	THI:SCL	Clock High Time	100 kHz mode	Трв * (BRG + 2)	_	μS	_
			400 kHz mode	Трв * (BRG + 2)	_	μS	_
			1 MHz mode (Note 2)	Трв * (BRG + 2)	_	μS	_
IM20	TF:SCL	SDAx and SCLx	100 kHz mode	_	300	ns	CB is specified to be
		Fall Time	400 kHz mode	20 + 0.1 Св	300	ns	from 10 to 400 pF
			1 MHz mode (Note 2)	_	100	ns	
IM21	TR:SCL	SDAx and SCLx	100 kHz mode	_	1000	ns	CB is specified to be
		Rise Time	400 kHz mode	20 + 0.1 Св	300	ns	from 10 to 400 pF
			1 MHz mode (Note 2)	_	300	ns	
IM25	TSU:DAT	Data Input	100 kHz mode	250	_	ns	_
		Setup Time	400 kHz mode	100	_	ns	
			1 MHz mode (Note 2)	100	_	ns	
IM26	THD:DAT	Data Input	100 kHz mode	0	_	μs	_
		Hold Time	400 kHz mode	0	0.9	μS	
			1 MHz mode (Note 2)	0	0.3	μS	
IM30	Tsu:sta	Start Condition	100 kHz mode	Трв * (BRG + 2)	_	μS	Only relevant for
		Setup Time	400 kHz mode	Трв * (BRG + 2)	_	μS	Repeated Start
			1 MHz mode (Note 2)	Трв * (BRG + 2)	_	μS	condition
IM31	THD:STA	Start Condition	100 kHz mode	Трв * (BRG + 2)	_	μS	After this period, the
		Hold Time	400 kHz mode	TPB * (BRG + 2)	_	μS	first clock pulse is generated
			1 MHz mode (Note 2)	Трв * (BRG + 2)	_	μS	generated
IM33	Tsu:sto	Stop Condition	100 kHz mode	Трв * (BRG + 2)	_	μS	
		Setup Time	400 kHz mode	Трв * (BRG + 2)	_	μs	
			1 MHz mode (Note 2)	Трв * (BRG + 2)	_	μS	
IM34	THD:STO	Stop Condition	100 kHz mode	Трв * (BRG + 2)	_	ns	
		Hold Time	400 kHz mode	Трв * (BRG + 2)	_	ns	
			1 MHz mode (Note 2)	Трв * (BRG + 2)	_	ns	

**Note 1:** BRG is the value of the I<sup>2</sup>C Baud Rate Generator.

<sup>2:</sup> Maximum pin capacitance = 10 pF for all I2Cx pins (for 1 MHz mode only).

**<sup>3:</sup>** The typical value for this parameter is 104 ns.

TABLE 30-32: I2Cx BUS DATA TIMING REQUIREMENTS (MASTER MODE) (CONTINUED)


AC CHARACTERISTICS				Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp			
Param. No.	Symbol	Characteristics		Min. <sup>(1)</sup>	Max.	Units	Conditions
IM40	TAA:SCL	Output Valid from Clock	100 kHz mode	_	3500	ns	_
			400 kHz mode	_	1000	ns	_
			1 MHz mode (Note 2)	_	350	ns	_
IM45	TBF:SDA	Bus Free Time	100 kHz mode	4.7	_	μS	The amount of time the bus must be free before a new transmission can start
			400 kHz mode	1.3	_	μs	
			1 MHz mode (Note 2)	0.5	_	μS	
IM50	Св	Bus Capacitive Loading		_	400	pF	_
IM51	TPGD	Pulse Gobbler Delay		52	312	ns	See Note 3

**Note 1:** BRG is the value of the I<sup>2</sup>C Baud Rate Generator.

<sup>2:</sup> Maximum pin capacitance = 10 pF for all I2Cx pins (for 1 MHz mode only).

**<sup>3:</sup>** The typical value for this parameter is 104 ns.

## FIGURE 30-16: I2Cx BUS START/STOP BITS TIMING CHARACTERISTICS (SLAVE MODE)



#### FIGURE 30-17: I2Cx BUS DATA TIMING CHARACTERISTICS (SLAVE MODE)




TABLE 30-33: I2Cx BUS DATA TIMING REQUIREMENTS (SLAVE MODE)

AC CHA	RACTERIS	STICS		Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp				
Param. No.	Symbol	Charact	eristics	Min.	Max.	Units	Conditions	
IS10	TLO:SCL	Clock Low Time	100 kHz mode	4.7	_	μS	PBCLK must operate at a minimum of 800 kHz	
			400 kHz mode	1.3	_	μS	PBCLK must operate at a minimum of 3.2 MHz	
			1 MHz mode (Note 1)	0.5	_	μS	_	
IS11	THI:SCL	Clock High Time	100 kHz mode	4.0	_	μS	PBCLK must operate at a minimum of 800 kHz	
			400 kHz mode	0.6	_	μS	PBCLK must operate at a minimum of 3.2 MHz	
			1 MHz mode (Note 1)	0.5	_	μS	_	
IS20	TF:SCL	SDAx and SCLx	100 kHz mode	_	300	ns	CB is specified to be from	
		Fall Time	400 kHz mode	20 + 0.1 CB	300	ns	10 to 400 pF	
			1 MHz mode (Note 1)		100	ns		
IS21	TR:SCL	SDAx and SCLx	100 kHz mode	_	1000	ns	CB is specified to be from	
		Rise Time	400 kHz mode	20 + 0.1 CB	300	ns	10 to 400 pF	
			1 MHz mode (Note 1)	_	300	ns		
IS25	TSU:DAT	Data Input	100 kHz mode	250	_	ns	_	
		Setup Time	400 kHz mode	100		ns		
			1 MHz mode (Note 1)	100	_	ns		
IS26	THD:DAT	Data Input	100 kHz mode	0	_	ns	_	
		Hold Time	400 kHz mode	0	0.9	μS		
			1 MHz mode (Note 1)	0	0.3	μS		
IS30	Tsu:sta	Start Condition	100 kHz mode	4700	_	ns	Only relevant for Repeated	
		Setup Time	400 kHz mode	600	_	ns	Start condition	
			1 MHz mode (Note 1)	250	_	ns		
IS31	THD:STA	Start Condition	100 kHz mode	4000	_	ns	After this period, the first	
		Hold Time	400 kHz mode	600		ns	clock pulse is generated	
			1 MHz mode (Note 1)	250	_	ns		
IS33	Tsu:sto	Stop Condition	100 kHz mode	4000	_	ns	_	
		Setup Time	400 kHz mode	600	_	ns		
			1 MHz mode (Note 1)	600	_	ns		

**Note 1:** Maximum pin capacitance = 10 pF for all I2Cx pins (for 1 MHz mode only).

## TABLE 30-33: I2Cx BUS DATA TIMING REQUIREMENTS (SLAVE MODE) (CONTINUED)

AC CHA	RACTERIS	STICS		Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{Ta} \le +105^{\circ}\text{C}$ for V-temp			
Param. No.	Symbol	Charact	eristics	Min.	Max.	Units	Conditions
IS34	THD:STO	Stop Condition	100 kHz mode	4000	_	ns	_
		Hold Time	400 kHz mode	600	_	ns	
			1 MHz mode (Note 1)	250		ns	
IS40	TAA:SCL	Output Valid from	100 kHz mode	0	3500	ns	_
		Clock	400 kHz mode	0	1000	ns	
			1 MHz mode (Note 1)	0	350	ns	
IS45	TBF:SDA	Bus Free Time	100 kHz mode	4.7	_	μS	The amount of time the bus
			400 kHz mode	1.3	_	μS	must be free before a new
			1 MHz mode (Note 1)	0.5	_	μS	transmission can start
IS50	Св	Bus Capacitive Lo	ading	_	400	pF	_

**Note 1:** Maximum pin capacitance = 10 pF for all I2Cx pins (for 1 MHz mode only).

**TABLE 30-34: ADC MODULE SPECIFICATIONS** 

	AC CHAF	RACTERISTICS	Standard O (unless oth Operating to	erwise sta	ted) -40°C ≤ TA	≤ +85°	e 5): 2.5V to 3.6V C for Industrial c°C for V-temp
Param. No.	Symbol	Characteristics	Min.	Typical	Max.	Units	Conditions
Device	Supply						
AD01	AVDD	Module VDD Supply	Greater of VDD – 0.3 or 2.5		Lesser of VDD + 0.3 or 3.6	V	_
AD02	AVss	Module Vss Supply	Vss	_	AVDD	V	(Note 1)
Referen	ce Inputs						
AD05 AD05a	VREFH	Reference Voltage High	AVss + 2.0 2.5	1 1	AVDD 3.6	V V	(Note 1) VREFH = AVDD (Note 3)
AD06	VREFL	Reference Voltage Low	AVss	l	VREFH - 2.0	V	(Note 1)
AD07	VREF	Absolute Reference Voltage (VREFH – VREFL)	2.0	l	AVDD	V	(Note 3)
AD08 AD08a	IREF	Current Drain	_	250 —	400 3	μA μA	ADC operating ADC off
Analog	Input						
AD12	VINH-VINL	Full-Scale Input Span	VREFL		VREFH	V	_
AD13	VINL	Absolute VINL Input Voltage	AVss - 0.3		AVDD/2	V	_
AD14	VIN	Absolute Input Voltage	AVss - 0.3	_	AVDD + 0.3	V	_
AD15	_	Leakage Current		±0.001	±0.610	μA	VINL = AVSS = VREFL = 0V, AVDD = VREFH = $3.3V$ Source Impedance = $10 \text{ k}\Omega$
AD17	RIN	Recommended Impedance of Analog Voltage Source		l	5k	Ω	(Note 1)
ADC Ac	curacy – N	leasurements with Exte	rnal VREF+/V	REF-			
AD20c	Nr	Resolution		10 data bit	s	bits	_
AD21c	INL	Integral Non-linearity	> -1	_	< 1	LSb	VINL = AVSS = VREFL = 0V, AVDD = VREFH = 3.3V
AD22c	DNL	Differential Non-linearity	> -1	_	< 1	LSb	VINL = AVSS = VREFL = 0V, AVDD = VREFH = 3.3V (Note 2)
AD23c	GERR	Gain Error	> -1	_	< 1	LSb	VINL = AVSS = VREFL = 0V, AVDD = VREFH = 3.3V
AD24c	EOFF	Offset Error	> -1	_	< 1	Lsb	VINL = AVSS = 0V, AVDD = 3.3V
AD25c	_	Monotonicity			_	_	Guaranteed

- Note 1: These parameters are not characterized or tested in manufacturing.
  - 2: With no missing codes.
  - 3: These parameters are characterized, but not tested in manufacturing.
  - 4: Characterized with a 1 kHz sine wave.
  - **5:** The ADC module is functional at VBORMIN < VDD < 2.5V, but with degraded performance. Unless otherwise stated, module functionality is tested, but not characterized.

**TABLE 30-34: ADC MODULE SPECIFICATIONS** 

	AC CHAR	RACTERISTICS	Standard Operating Conditions (see Note 5): 2.5V to 3.6V (unless otherwise stated)   Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp					
Param. No.	Symbol	Characteristics	Min.	Typical	Max.	Units	Conditions	
ADC Ac	curacy - N	leasurements with Inter	nal VREF+/V	REF-				
AD20d	Nr	Resolution		10 data bits	3	bits	(Note 3)	
AD21d	INL	Integral Non-linearity	> -1	_	< 1	LSb	VINL = AVSS = 0V, AVDD = 2.5V to 3.6V (Note 3)	
AD22d	DNL	Differential Non-linearity	> -1	_	< 1	LSb	VINL = AVSS = 0V, AVDD = 2.5V to 3.6V (Notes 2,3)	
AD23d	GERR	Gain Error	> -4	_	< 4	LSb	VINL = AVSS = 0V, AVDD = 2.5V to 3.6V (Note 3)	
AD24d	EOFF	Offset Error	> -2	_	< 2	Lsb	VINL = AVss = 0V, AVDD = 2.5V to 3.6V (Note 3)	
AD25d	_	Monotonicity	_	_	_	_	Guaranteed	
Dynami	c Performa	ance	•		•	•		
AD32b	SINAD	Signal to Noise and Distortion	55	58.5	_	dB	(Notes 3,4)	
AD34b	ENOB	Effective Number of bits	9.0	9.5	_	bits	(Notes 3,4)	

Note 1: These parameters are not characterized or tested in manufacturing.

<sup>2:</sup> With no missing codes.

**<sup>3:</sup>** These parameters are characterized, but not tested in manufacturing.

**<sup>4:</sup>** Characterized with a 1 kHz sine wave.

**<sup>5:</sup>** The ADC module is functional at VBORMIN < VDD < 2.5V, but with degraded performance. Unless otherwise stated, module functionality is tested, but not characterized.

TABLE 30-35: 10-BIT CONVERSION RATE PARAMETERS

AC CHARA	CTERISTIC	S <sup>(2)</sup>	Standard Operating Conditions (see Note 3): 2.5V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp					
ADC Speed	TAD Min.	Sampling Time Min.	Rs Max.	VDD	ADC Channels Configuration			
1 Msps to 400 ksps <sup>(1)</sup>	65 ns	132 ns	500Ω	3.0V to 3.6V	ANX CHX ADC			
Up to 400 ksps	200 ns	200 ns	5.0 kΩ	2.5V to 3.6V	ANX SHA ADC  ANX or VREF-			

- Note 1: External VREF- and VREF+ pins must be used for correct operation.
  - 2: These parameters are characterized, but not tested in manufacturing.
  - **3:** The ADC module is functional at VBORMIN < VDD < 2.5V, but with degraded performance. Unless otherwise stated, module functionality is tested, but not characterized.

#### TABLE 30-36: ANALOG-TO-DIGITAL CONVERSION TIMING REQUIREMENTS

AC CHA	AC CHARACTERISTICS			Standard Operating Conditions (see Note 4): 2.5V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{Ta} \le +105^{\circ}\text{C}$ for V-temp					
Param. No.	Symbol	Characteristics	Min.	Typical <sup>(1)</sup>	Max.	Units	Conditions		
Clock P	arameters	S							
AD50	TAD	ADC Clock Period <sup>(2)</sup>	65	_	_	ns	See Table 30-35		
Convers	sion Rate								
AD55	TCONV	Conversion Time	_	12 TAD	_	_	_		
AD56	FCNV	Throughput Rate	_		1000	ksps	AVDD = 3.0V to 3.6V		
		(Sampling Speed)	_	-	400	ksps	AVDD = 2.5V to 3.6V		
AD57	TSAMP	Sample Time	1 TAD		_	_	TSAMP must be ≥ 132 ns		
Timing	Paramete	rs							
AD60	TPCS	Conversion Start from Sample Trigger <sup>(3)</sup>	_	1.0 TAD	_	_	Auto-Convert Trigger (SSRC<2:0> = 111) not selected		
AD61	TPSS	Sample Start from Setting Sample (SAMP) bit	0.5 TAD		1.5 TAD	_	_		
AD62	TCSS	Conversion Completion to Sample Start (ASAM = $1$ ) <sup>(3)</sup>	_	0.5 TAD	_	_	_		
AD63	TDPU	Time to Stabilize Analog Stage from ADC Off to ADC On <sup>(3)</sup>	_	_	2	μS	_		


Note 1: These parameters are characterized, but not tested in manufacturing.

**<sup>2:</sup>** Because the sample caps will eventually lose charge, clock rates below 10 kHz can affect linearity performance, especially at elevated temperatures.

<sup>3:</sup> Characterized by design but not tested.


**<sup>4:</sup>** The ADC module is functional at VBORMIN < VDD < 2.5V, but with degraded performance. Unless otherwise stated, module functionality is tested, but not characterized.

FIGURE 30-18: ANALOG-TO-DIGITAL CONVERSION (10-BIT MODE) TIMING CHARACTERISTICS (ASAM = 0, SSRC<2:0> = 000)




- 1 Software sets ADxCON. SAMP to start sampling.
- ② Sampling starts after discharge period. TSAMP is described in Section 17. "10-bit Analog-to-Digital Converter (ADC)" (DS60001104) in the "PIC32 Family Reference Manual".
- 3 Software clears ADxCON. SAMP to start conversion.
- (4) Sampling ends, conversion sequence starts.
- 6 Convert bit 9.
- (6) Convert bit 8.
- 7 Convert bit 0.
- 8 One TAD for end of conversion.

FIGURE 30-19: ANALOG-TO-DIGITAL CONVERSION (10-BIT MODE) TIMING CHARACTERISTICS (ASAM = 1, SSRC<2:0> = 111, SAMC<4:0> = 00001)



(4) - Convert bit 8.





**TABLE 30-37: PARALLEL SLAVE PORT REQUIREMENTS** 

AC CH	IARACTE	RISTICS	Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp					
Para m.No.	Symbol	Characteristics <sup>(1)</sup>	Min.	Тур.	Max.	Units	Conditions	
PS1	TdtV2wr H	Data In Valid before WR or CS Inactive (setup time)	20	_	_	ns	_	
PS2	TwrH2dt I	WR or CS Inactive to Data-In Invalid (hold time)	40			ns	_	
PS3	TrdL2dt V	RD and CS Active to Data-Out Valid	_		60	ns	_	
PS4	TrdH2dtl	RD Active or CS Inactive to Data-Out Invalid	0		10	ns	_	
PS5	Tcs	CS Active Time	TpB + 40	_	_	ns	_	
PS6	Twr	WR Active Time	TpB + 25		_	ns	_	
PS7	TRD	RD Active Time	TpB + 25		_	ns	_	

Note 1: These parameters are characterized, but not tested in manufacturing.

FIGURE 30-21: PARALLEL MASTER PORT READ TIMING DIAGRAM





TABLE 30-38: PARALLEL MASTER PORT READ TIMING REQUIREMENTS

AC CHA	ARACTER	ISTICS	Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp					
Param. No.	Symbol	Characteristics <sup>(1)</sup>	Min.	Тур.	Max.	Units	Conditions	
PM1	TLAT	PMALL/PMALH Pulse Width	_	1 Трв	_	_	_	
PM2	TADSU	Address Out Valid to PMALL/PMALH Invalid (address setup time)	_	2 Трв		_	_	
РМ3	TADHOLD	PMALL/PMALH Invalid to Address Out Invalid (address hold time)	_	1 Трв	_	_	_	
PM4	TAHOLD	PMRD Inactive to Address Out Invalid (address hold time)	5	_	_	ns	_	
PM5	TRD	PMRD Pulse Width	_	1 Tpb			_	
РМ6	TDSU	PMRD or PMENB Active to Data In Valid (data setup time)	15	_	_	ns	_	
PM7	TDHOLD	PMRD or PMENB Inactive to Data In Invalid (data hold time)	5	_	_	ns	_	

Note 1: These parameters are characterized, but not tested in manufacturing.

FIGURE 30-22: PARALLEL MASTER PORT WRITE TIMING DIAGRAM



#### TABLE 30-39: PARALLEL MASTER PORT WRITE TIMING REQUIREMENTS

AC CHARACTERISTICS			Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) $ \begin{array}{ll} \text{Operating temperature} & -40^{\circ}\text{C} \leq \text{TA} \leq +85^{\circ}\text{C for Industrial} \\ -40^{\circ}\text{C} \leq \text{TA} \leq +105^{\circ}\text{C for V-temp} \end{array} $					
Param. No.	Symbol	Characteristics <sup>(1)</sup>	Min.	Тур.	Max.	Units	Conditions	
PM11	Twr	PMWR Pulse Width	_	1 Трв	_	_	_	
PM12	TDVSU	Data Out Valid before PMWR or PMENB goes Inactive (data setup time)	_	2 ТРВ	_	_	_	
PM13	TDVHOLD	PMWR or PMEMB Invalid to Data Out Invalid (data hold time)	_	1 Трв	_	_	_	

Note 1: These parameters are characterized, but not tested in manufacturing.

## TABLE 30-40: OTG ELECTRICAL SPECIFICATIONS

AC CHARACTERISTICS			Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated)   Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp				
Param. No.	Symbol	Characteristics <sup>(1)</sup>	Min.	Тур.	Max.	Units	Conditions
USB313	VUSB3V3	USB Voltage	3.0	_	3.6	V	Voltage on VUSB3V3 must be in this range for proper USB operation
USB315	VILUSB	Input Low Voltage for USB Buffer		_	0.8	V	_
USB316	VIHUSB	Input High Voltage for USB Buffer	2.0	_	_	V	_
USB318	VDIFS	Differential Input Sensitivity	_		0.2	V	The difference between D+ and D- must exceed this value while VCM is met
USB319	VCM	Differential Common Mode Range	0.8	_	2.5	V	_
USB320	Zout	Driver Output Impedance	28.0	_	44.0	Ω	_
USB321	Vol	Voltage Output Low	0.0	_	0.3	V	1.425 kΩ load connected to Vusb3v3
USB322	Vон	Voltage Output High	2.8	_	3.6	V	1.425 kΩ load connected to ground


Note 1: These parameters are characterized, but not tested in manufacturing.

**TABLE 30-41: CTMU CURRENT SOURCE SPECIFICATIONS** 

	DC CHA	RACTERISTICS	Standard Operating Conditions (see Note 3):2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +105^{\circ}\text{C}$ for V-temp					
Param No.	Symbol	Characteristic	Min.	Тур.	Max.	Units	Conditions	
CTMU CUR	RENT SOUR	CE						
CTMUI1	IOUT1	Base Range <sup>(1)</sup>	_	0.55	_	μA	CTMUCON<9:8> = 01	
CTMUI2	Іоит2	10x Range <sup>(1)</sup>	_	5.5	_	μA	CTMUCON<9:8> = 10	
CTMUI3	Іоит3	100x Range <sup>(1)</sup>	_	55	_	μA	CTMUCON<9:8> = 11	
CTMUI4	Iout4	1000x Range <sup>(1)</sup>	_	550	_	μA	CTMUCON<9:8> = 00	
CTMUFV1	VF	Temperature Diode Forward Voltage <sup>(1,2)</sup>	_	0.598	_	V	TA = +25°C, CTMUCON<9:8> = 01	
			_	0.658	_	V	TA = +25°C, CTMUCON<9:8> = 10	
			_	0.721	_	V	TA = +25°C, CTMUCON<9:8> = 11	
CTMUFV2	VFVR	Temperature Diode Rate of		-1.92		mV/ºC	CTMUCON<9:8> = 01	
		Change <sup>(1,2)</sup>		-1.74		mV/ºC	CTMUCON<9:8> = 10	
			_	-1.56	_	mV/°C	CTMUCON<9:8> = 11	

- **Note 1:** Nominal value at center point of current trim range (CTMUCON<15:10> = 000000).
  - **2:** Parameters are characterized but not tested in manufacturing. Measurements taken with the following conditions:
    - VREF+ = AVDD = 3.3V
    - ADC module configured for conversion speed of 500 ksps
    - All PMD bits are cleared (PMDx = 0)
    - Executing a while(1) statement
    - Device operating from the FRC with no PLL
  - **3:** The CTMU module is functional at VBORMIN < VDD < VDDMIN, but with degraded performance. Unless otherwise stated, module functionality is tested, but not characterized.

FIGURE 30-23: EJTAG TIMING CHARACTERISTICS



**TABLE 30-42: EJTAG TIMING REQUIREMENTS** 

AC CHARACTERISTICS			Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for Ir $-40^{\circ}\text{C} \le \text{Ta} \le +105^{\circ}\text{C}$ for				
Param. No.	Symbol	Description <sup>(1)</sup>	Min.	Max.	Units	Conditions	
EJ1	Ттсксус	TCK Cycle Time	25	_	ns	_	
EJ2	Ттскнідн	TCK High Time	10	_	ns	_	
EJ3	TTCKLOW	TCK Low Time	10	_	ns	_	
EJ4	TTSETUP	TAP Signals Setup Time Before Rising TCK	5	_	ns	_	
EJ5	TTHOLD	TAP Signals Hold Time After Rising TCK	3	_	ns	_	
EJ6	Ттроопт	TDO Output Delay Time from Falling TCK	_	5	ns	_	
EJ7	TTDOZSTATE	TDO 3-State Delay Time from Falling TCK	_	5	ns	_	
EJ8	Trrstlow	TRST Low Time	25		ns	_	
EJ9	TRF	TAP Signals Rise/Fall Time, All Input and Output		_	ns	_	

Note 1: These parameters are characterized, but not tested in manufacturing.

#### 31.0 50 MHz ELECTRICAL CHARACTERISTICS

This section provides an overview of the PIC32MX1XX/2XX 28/36/44-pin Family electrical characteristics for devices operating at 50 MHz.

The specifications for 50 MHz are identical to those shown in **Section 30.0 "Electrical Characteristics"**, with the exception of the parameters listed in this chapter.

Parameters in this chapter begin with the letter "M", which denotes 50 MHz operation. For example, parameter DC29a in **Section 30.0** "**Electrical Characteristics**", is the up to 40 MHz operation equivalent for MDC29a.

Absolute maximum ratings for the PIC32MX1XX/2XX 28/36/44-pin Family 50 MHz devices are listed below. Exposure to these maximum rating conditions for extended periods may affect device reliability. Functional operation of the device at these or any other conditions, above the parameters indicated in the operation listings of this specification, is not implied.

## **Absolute Maximum Ratings**

#### (See Note 1)

Ambien	t temperature under bias	40°C to +85°C
Storage	temperature	65°C to +150°C
Voltage	on VDD with respect to Vss	0.3V to +4.0V
Voltage	on any pin that is not 5V tolerant, with respect to Vss (Note 3)	0.3V to (VDD + 0.3V)
Voltage	on any 5V tolerant pin with respect to Vss when Vdd $\geq$ 2.3V (Note 3)	0.3V to +5.5V
Voltage	on any 5V tolerant pin with respect to Vss when VDD < 2.3V (Note 3)	0.3V to +3.6V
Voltage	on D+ or D- pin with respect to Vusb3v3	0.3V to (VUSB3V3 + 0.3V)
Voltage	on VBUS with respect to VSS	0.3V to +5.5V
Maximu	m current out of Vss pin(s)	300 mA
Maximu	m current into VDD pin(s) (Note 2)	300 mA
Maximu	m output current sunk by any I/O pin	15 mA
Maximu	m output current sourced by any I/O pin	15 mA
Maximu	m current sunk by all ports	200 mA
Maximu	m current sourced by all ports (Note 2)	200 mA

- Note 1: Stresses above those listed under "Absolute Maximum Ratings" may cause permanent damage to the device. This is a stress rating only and functional operation of the device at those or any other conditions, above those indicated in the operation listings of this specification, is not implied. Exposure to maximum rating conditions for extended periods may affect device reliability.
  - 2: Maximum allowable current is a function of device maximum power dissipation (see Table 30-2).
  - 3: See the "Pin Diagrams" section for the 5V tolerant pins.

#### 31.1 DC Characteristics

#### TABLE 31-1: OPERATING MIPS VS. VOLTAGE

Characteristic	V <sub>DD</sub> Range	Temp. Range	Max. Frequency		
Characteristic	(in Volts) <sup>(1)</sup>	(in °C)	PIC32MX1XX/2XX 28/36/44-pin Family		
MDC5	2.3-3.6V	-40°C to +85°C	50 MHz		

Note 1: Overall functional device operation at VBORMIN < VDD < VDDMIN is tested, but not characterized. All device Analog modules, such as ADC, etc., will function, but with degraded performance below VDDMIN. Refer to parameter BO10 in Table 30-11 for BOR values.

#### TABLE 31-2: DC CHARACTERISTICS: OPERATING CURRENT (IDD)

DC CHARA	CTERISTICS	<b>i</b>	Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial						
Parameter No.	Typical <sup>(3)</sup>	Max.	Units Conditions						
Operating (	Operating Current (IDD) (Note 1, 2)								
MDC24	25	37	mA	mA 50 MHz					

- **Note 1:** A device's IDD supply current is mainly a function of the operating voltage and frequency. Other factors, such as PBCLK (Peripheral Bus Clock) frequency, number of peripheral modules enabled, internal code execution pattern, execution from Program Flash memory vs. SRAM, I/O pin loading and switching rate, oscillator type, as well as temperature, can have an impact on the current consumption.
  - 2: The test conditions for IDD measurements are as follows:
    - Oscillator mode is EC (for 8 MHz and below) and EC+PLL (for above 8 MHz) with OSC1 driven by external square wave from rail-to-rail, (OSC1 input clock input over/undershoot < 100 mV required)
    - OSC2/CLKO is configured as an I/O input pin
    - USB PLL oscillator is disabled if the USB module is implemented, PBCLK divisor = 1:8
    - CPU, Program Flash, and SRAM data memory are operational, SRAM data memory Wait states = 1
    - No peripheral modules are operating, (ON bit = 0), but the associated PMD bit is cleared
    - · WDT, Clock Switching, Fail-Safe Clock Monitor, and Secondary Oscillator are disabled
    - · All I/O pins are configured as inputs and pulled to Vss
    - MCLR = VDD
    - CPU executing while (1) statement from Flash
  - 3: RTCC and JTAG are disabled
  - **4:** Data in "Typical" column is at 3.3V, 25°C at specified operating frequency unless otherwise stated. Parameters are for design guidance only and are not tested.

#### TABLE 31-3: DC CHARACTERISTICS: IDLE CURRENT (IDLE)

DC CHARACTERISTICS			Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated)  Operating temperature -40°C ≤ TA ≤ +85°C for Industrial					
Parameter No.	Typical <sup>(2)</sup>	Max.	Units Conditions					
Idle Current (III	DLE): Core Of	f, Clock on E	Base Current	(Note 1)				
MDC34a	8	13	mA 50 MHz					

- Note 1: The test conditions for IDLE current measurements are as follows:
  - Oscillator mode is EC (for 8 MHz and below) and EC+PLL (for above 8 MHz) with OSC1 driven by external square wave from rail-to-rail, (OSC1 input clock input over/undershoot < 100 mV required)</li>
  - · OSC2/CLKO is configured as an I/O input pin
  - USB PLL oscillator is disabled if the USB module is implemented, PBCLK divisor = 1:8
  - CPU is in Idle mode (CPU core Halted), and SRAM data memory Wait states = 1
  - No peripheral modules are operating, (ON bit = 0), but the associated PMD bit is cleared
  - WDT, Clock Switching, Fail-Safe Clock Monitor, and Secondary Oscillator are disabled
  - · All I/O pins are configured as inputs and pulled to Vss
  - MCLR = VDD
  - · RTCC and JTAG are disabled
  - 2: Data in the "Typical" column is at 3.3V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.

#### TABLE 31-4: DC CHARACTERISTICS: POWER-DOWN CURRENT (IPD)

DC CHAR	RACTERIST	ics	Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial						
Param. No.	Typical <sup>(2)</sup>	Max.	Units	Conditions					
Power-Do	own Curren	t (IPD) (Not	e 1)						
MDC40k	10	25	μА	-40°C					
MDC40n	250	500	μА	+85°C	Base Power-Down Current				
Module D	ifferential (	Current							
MDC41e	10	55	μА	3.6V	Watchdog Timer Current: ∆IWDT (Note 3)				
MDC42e	23	55	μА	3.6V RTCC + Timer1 w/32 kHz Crystal: ΔIRTCC (Note 3)					
MDC43d	1100	1300	μА	3.6V ADC: ΔΙΑΦΟ (Notes 3,4)					

- Note 1: The test conditions for IPD current measurements are as follows:
  - Oscillator mode is EC (for 8 MHz and below) and EC+PLL (for above 8 MHz) with OSC1 driven by external square wave from rail-to-rail, (OSC1 input clock input over/undershoot < 100 mV required)</li>
  - OSC2/CLKO is configured as an I/O input pin
  - USB PLL oscillator is disabled if the USB module is implemented, PBCLK divisor = 1:8
  - ullet CPU is in Sleep mode, and SRAM data memory Wait states = 1
  - No peripheral modules are operating, (ON bit = 0), but the associated PMD bit is set
  - · WDT, Clock Switching, Fail-Safe Clock Monitor, and Secondary Oscillator are disabled
  - All I/O pins are configured as inputs and pulled to Vss
  - MCLR = VDD
  - · RTCC and JTAG are disabled
  - **2:** Data in the "Typical" column is at 3.3V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.
  - **3:** The Δ current is the additional current consumed when the module is enabled. This current should be added to the base IPD current.
  - 4: Test conditions for ADC module differential current are as follows: Internal ADC RC oscillator enabled.

#### TABLE 31-5: EXTERNAL CLOCK TIMING REQUIREMENTS

AC CHARACTERISTICS			Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial					
Param. No.	Symbol	Characteristics	Min. Typical Max. Units Conditions					
MOS10	Fosc	External CLKI Frequency (External clocks allowed only in EC and ECPLL modes)	DC 4	_	50 50		EC (Note 2) ECPLL (Note 1)	

**Note 1:** PLL input requirements: 4 MHz ≤ FPLLIN ≤ 5 MHz (use PLL prescaler to reduce Fosc). This parameter is characterized, but tested at 10 MHz only at manufacturing.

#### TABLE 31-6: SPIX MASTER MODE (CKE = 0) TIMING REQUIREMENTS

AC CHARACTERISTICS			Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial				
Param. No. Characteristics			Min.	Typical	Max.	Units	Conditions
MSP10	TscL	SCKx Output Low Time (Note 1,2)	Тѕск/2	1	_	ns	
MSP11	TscH	SCKx Output High Time (Note 1,2)	Tsck/2	_	_	ns	_

Note 1: These parameters are characterized, but not tested in manufacturing.

#### TABLE 31-7: SPIX MODULE MASTER MODE (CKE = 1) TIMING REQUIREMENTS

TO THE STATE OF THE MICE STATE OF THE STATE							. •
AC CHARACTERISTICS			Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for Industrial				
Param. No.	Symbol	Characteristics <sup>(1)</sup>	Min. Typ. Max. Units Conditions				
MSP10	TscL	SCKx Output Low Time (Note 1,2)	Tsck/2	_	_	ns	_
MSP11	TscH	SCKx Output High Time (Note 1,2)	Tsck/2		_	ns	_

Note 1: These parameters are characterized, but not tested in manufacturing.

<sup>2:</sup> This parameter is characterized, but not tested in manufacturing.

**<sup>2:</sup>** The minimum clock period for SCKx is 40 ns. Therefore, the clock generated in Master mode must not violate this specification.

<sup>2:</sup> The minimum clock period for SCKx is 40 ns. Therefore, the clock generated in Master mode must not violate this specification.

TABLE 31-8: SPIX MODULE SLAVE MODE (CKE = 0) TIMING REQUIREMENTS

IABLE	31-0. SI	IX MODULE SLAVE MODE (CKE -	- U) THINIT	IG KEQ	OIKEW		
AC CHARACTERISTICS			(unless o	therwis	e stated ture -40	I) °C ≤ Ta :	: <b>2.3V to 3.6V</b> ≤ +85°C for Industrial ≤ +105°C for V-temp
Param. No.	Symbol	Characteristics	Min. Typ. Max. Units Conditions				
MSP70	TscL	SCKx Input Low Time (Note 1,2)	Tsck/2	_	_	ns	_
MSP71	TscH	SCKx Input High Time (Note 1,2)	Tsck/2	_	_	ns	
MSP51	TssH2DoZ	SSx ↑ to SDOx Output High-Impedance (Note 2)	5	_	25	ns	_

Note 1: These parameters are characterized, but not tested in manufacturing.

## TABLE 31-9: SPIX MODULE SLAVE MODE (CKE = 1) TIMING REQUIREMENTS

			Standard Operating Conditions: 2.3V to 3.6V (unless otherwise stated) Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for Industrial				
Param. No.	Symbol   Characteristics   Min			Typical	Max.	Units	Conditions
SP70	TscL	SCKx Input Low Time (Note 1,2)	Tsck/2	_		ns	_
SP71	TscH	SCKx Input High Time (Note 1,2)	Tsck/2	_	_	ns	_

Note 1: These parameters are characterized, but not tested in manufacturing.


<sup>2:</sup> The minimum clock period for SCKx is 40 ns.


**<sup>2:</sup>** The minimum clock period for SCKx is 40 ns.


NOTES:			


# 32.0 DC AND AC DEVICE CHARACTERISTICS GRAPHS


The graphs provided following this note are a statistical summary based on a limited number of samples and are provided for design guidance purposes only. The performance characteristics listed herein are not tested or guaranteed. In some graphs, the data presented may be outside the specified operating range (e.g., outside specified power supply range) and therefore, outside the warranted range. Note:




















NOTES:		

#### 33.0 PACKAGING INFORMATION

## 33.1 Package Marking Information


28-Lead SOIC




#### Example

PIC32MX220F 032B-I/SO (€3) **1**130235

#### 28-Lead SPDIP



#### Example




#### 28-Lead SSOP



#### Example



#### 28-Lead QFN



#### Example



Legend: XX...X Customer-specific information
Y Year code (last digit of calendar year)
YY Year code (last 2 digits of calendar year)
WW Week code (week of January 1 is week '01')
NNN Alphanumeric traceability code
By-free JEDEC designator for Matte Tin (Sn)
This package is Pb-free. The Pb-free JEDEC designator (©3))
can be found on the outer packaging for this package.

**Note:** If the full Microchip part number cannot be marked on one line, it is carried over to the next line, thus limiting the number of available characters for customer-specific information.

#### **Package Marking Information (Continued)** 33.1

36-Lead VTLA




44-Lead VTLA



44-Lead QFN



44-Lead TQFP



Example



032CE/TL@3 1130235

Example



MX120F0 32DI/TL (e3) 1130235

Example



Example




Legend: XX...XCustomer-specific information Year code (last digit of calendar year) ΥY Year code (last 2 digits of calendar year) WW Week code (week of January 1 is week '01') NNN Alphanumeric traceability code Pb-free JEDEC designator for Matte Tin (Sn) (e3) This package is Pb-free. The Pb-free JEDEC designator (@3) can be found on the outer packaging for this package.

## 33.2 Package Details

This section provides the technical details of the packages.

## 28-Lead Plastic Shrink Small Outline (SS) - 5.30 mm Body [SSOP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Units		MILLIMETERS			
Dimension Limits		MIN	NOM	MAX	
Number of Pins	N	28			
Pitch	е	0.65 BSC			
Overall Height	Α	2.00			
Molded Package Thickness	A2	1.65	1.75	1.85	
Standoff	A1	0.05	_	_	
Overall Width	Е	7.40	7.80	8.20	
Molded Package Width	E1	5.00	5.30	5.60	
Overall Length	D	9.90	10.20	10.50	
Foot Length	L	0.55	0.75	0.95	
Footprint	L1	1.25 REF			
Lead Thickness	С	0.09	_	0.25	
Foot Angle	ф	0°	4°	8°	
Lead Width	b	0.22	_	0.38	


#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed 0.20 mm per side.
- 3. Dimensioning and tolerancing per ASME Y14.5M.
  - BSC: Basic Dimension. Theoretically exact value shown without tolerances.
  - REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-073B

28-Lead Plastic Shrink Small Outline (SS) - 5.30 mm Body [SSOP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	MILLIMETERS			
Dimension Limits		MIN	NOM	MAX
Contact Pitch	E	0.65 BSC		
Contact Pad Spacing	С		7.20	
Contact Pad Width (X28)	X1			0.45
Contact Pad Length (X28)	Y1			1.75
Distance Between Pads	G	0.20		

#### Notes:


1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2073A

## 28-Lead Skinny Plastic Dual In-Line (SP) - 300 mil Body [SPDIP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units		INCHES			
Dimension Limits		MIN	NOM	MAX		
Number of Pins	N	28				
Pitch	е		.100 BSC			
Top to Seating Plane	A	-	-	.200		
Molded Package Thickness	A2	.120	.135	.150		
Base to Seating Plane	A1	.015	-	-		
Shoulder to Shoulder Width	E	.290	.310	.335		
Molded Package Width	E1	.240	.285	.295		
Overall Length	D	1.345	1.365	1.400		
Tip to Seating Plane	L	.110	.130	.150		
Lead Thickness	С	.008	.010	.015		
Upper Lead Width	b1	.040	.050	.070		
Lower Lead Width	b	.014	.018	.022		
Overall Row Spacing §	eB	_	_	.430		

#### Notes:


- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. § Significant Characteristic.
- 3. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M.


BSC: Basic Dimension. Theoretically exact value shown without tolerances.


Microchip Technology Drawing C04-070B

#### 28-Lead Plastic Small Outline (SO) - Wide, 7.50 mm Body [SOIC]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging









Microchip Technology Drawing C04-052C Sheet 1 of 2

#### 28-Lead Plastic Small Outline (SO) - Wide, 7.50 mm Body [SOIC]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging





Units		MILLIMETERS			
Dimension Limits		MIN	NOM	MAX	
Number of Pins	N	28			
Pitch	е	1.27 BSC			
Overall Height	Α	-	-	2.65	
Molded Package Thickness	A2	2.05	-	-	
Standoff §	A1	0.10	-	0.30	
Overall Width	E	10.30 BSC			
Molded Package Width	E1	7.50 BSC			
Overall Length	D	17.90 BSC			
Chamfer (Optional)	h	0.25 - 0.75			
Foot Length	Г	0.40	-	1.27	
Footprint	L1	1.40 REF			
Lead Angle	Θ	0°	-	-	
Foot Angle	φ	0°	-	8°	
Lead Thickness	С	0.18	-	0.33	
Lead Width	b	0.31	-	0.51	
Mold Draft Angle Top	α	5°	-	15°	
Mold Draft Angle Bottom	β	5° - 15°			


#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. § Significant Characteristic
- Dimension D does not include mold flash, protrusions or gate burrs, which shall not exceed 0.15 mm per end. Dimension E1 does not include interlead flash or protrusion, which shall not exceed 0.25 mm per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M
  - BSC: Basic Dimension. Theoretically exact value shown without tolerances.
  - REF: Reference Dimension, usually without tolerance, for information purposes only.
- 5. Datums A & B to be determined at Datum H.

Microchip Technology Drawing C04-052C Sheet 2 of 2

28-Lead Plastic Small Outline (SO) - Wide, 7.50 mm Body [SOIC]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



## **RECOMMENDED LAND PATTERN**

Units		MILLIMETERS			
Dimension Limits		MIN	NOM	MAX	
Contact Pitch	E	1.27 BSC			
Contact Pad Spacing	С		9.40		
Contact Pad Width (X28)	Х			0.60	
Contact Pad Length (X28)	Υ			2.00	
Distance Between Pads	Gx	0.67			
Distance Between Pads	G	7.40			

#### Notes:


1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2052A

# 28-Lead Plastic Quad Flat, No Lead Package (ML) – 6x6 mm Body [QFN] with 0.55 mm Contact Length

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units		MILLIMETERS		
Dimensio	Dimension Limits		NOM	MAX	
Number of Pins	N	28			
Pitch	е	0.65 BSC			
Overall Height	Α	0.80 0.90 1.00			
Standoff	A1	0.00	0.02	0.05	
Contact Thickness	А3	0.20 REF			
Overall Width	Е	6.00 BSC			
Exposed Pad Width	E2	3.65	3.70	4.20	
Overall Length	D	6.00 BSC			
Exposed Pad Length	D2	3.65	3.70	4.20	
Contact Width	b	0.23	0.30	0.35	
Contact Length	L	0.50	0.55	0.70	
Contact-to-Exposed Pad	K	0.20	_	_	

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Package is saw singulated.
- 3. Dimensioning and tolerancing per ASME Y14.5M.


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-105B

# 28-Lead Plastic Quad Flat, No Lead Package (ML) – 6x6 mm Body [QFN] with 0.55 mm Contact Length

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



RECOMMENDED LAND PATTERN

Units		MILLIMETERS			
Dimension Limits		MIN	NOM	MAX	
Contact Pitch	Е	0.65 BSC			
Optional Center Pad Width	W2			4.25	
Optional Center Pad Length	T2			4.25	
Contact Pad Spacing	C1		5.70		
Contact Pad Spacing	C2		5.70		
Contact Pad Width (X28)	X1			0.37	
Contact Pad Length (X28)	Y1			1.00	
Distance Between Pads	G	0.20			

#### Notes:


1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2105A

# 36-Terminal Very Thin Thermal Leadless Array Package (TL) – 5x5x0.9 mm Body with Exposed Pad [VTLA]


**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging




Microchip Technology Drawing C04-187C Sheet 1 of 2

# 36-Terminal Very Thin Thermal Leadless Array Package (TL) – 5x5x0.9 mm Body with Exposed Pad [VTLA]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging





**DETAIL A** 

	Units	N	ILLIMETER	S
Dimension	Limits	MIN	NOM	MAX
Number of Pins	N		36	
Number of Pins per Side	ND		10	
Number of Pins per Side	NE		8	
Pitch	е		0.50 BSC	
Overall Height	Α	0.80	0.90	1.00
Standoff	A1	0.025	-	0.075
Overall Width	Е		5.00 BSC	
Exposed Pad Width	E2	3.60	3.75	3.90
Overall Length	D	5.00 BSC		
Exposed Pad Length	D2	3.60	3.75	3.90
Contact Width	b	0.20	0.25	0.30
Contact Length	L	0.20	0.25	0.30
Contact-to-Exposed Pad	K	0.20	-	-

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Package is saw singulated.
- 3. Dimensioning and tolerancing per ASME Y14.5M.


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-187C Sheet 2 of 2

# 44-Terminal Very Thin Leadless Array Package (TL) – 6x6x0.9 mm Body With Exposed Pad [VTLA]


**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging




Microchip Technology Drawing C04-157C Sheet 1 of 2

# 44-Terminal Very Thin Leadless Array Package (TL) – 6x6x0.9 mm Body With Exposed Pad [VTLA]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging







Units		MILLIMETERS		S
Dimension	Limits	MIN	NOM	MAX
Number of Pins	N		44	
Number of Pins per Side	ND		12	
Number of Pins per Side	NE		10	
Pitch	е		0.50 BSC	
Overall Height	Α	0.80	0.90	1.00
Standoff	A1	0.025	ı	0.075
Overall Width	Е		6.00 BSC	
Exposed Pad Width	E2	4.40	4.55	4.70
Overall Length	D		6.00 BSC	
Exposed Pad Length	D2	4.40	4.55	4.70
Contact Width	b	0.20	0.25	0.30
Contact Length	L	0.20	0.25	0.30
Contact-to-Exposed Pad	K	0.20	-	-

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Package is saw singulated.
- 3. Dimensioning and tolerancing per ASME Y14.5M.


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.


Microchip Technology Drawing C04-157C Sheet 2 of 2


## 44-Lead Plastic Quad Flat, No Lead Package (ML) - 8x8 mm Body [QFN]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging









	Units		MILLIMETERS		
Dimensio	n Limits	MIN	NOM	MAX	
Number of Pins	N		44		
Pitch	е		0.65 BSC		
Overall Height	Α	0.80	0.90	1.00	
Standoff	A1	0.00	0.02	0.05	
Contact Thickness	A3		0.20 REF		
Overall Width	Е		8.00 BSC		
Exposed Pad Width	E2	6.30	6.45	6.80	
Overall Length	D		8.00 BSC		
Exposed Pad Length	D2	6.30	6.45	6.80	
Contact Width	b	0.25	0.30	0.38	
Contact Length	L	0.30	0.40	0.50	
Contact-to-Exposed Pad	K	0.20	-	_	

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Package is saw singulated.
- 3. Dimensioning and tolerancing per ASME Y14.5M.


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-103B

## 44-Lead Plastic Quad Flat, No Lead Package (ML) - 8x8 mm Body [QFN]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



MILLIMETERS Units MIN NOM MAX **Dimension Limits** Contact Pitch 0.65 BSC Ε Optional Center Pad Width W2 6.80 Optional Center Pad Length T2 6.80 Contact Pad Spacing C1 8.00 Contact Pad Spacing C2 8.00 Contact Pad Width (X44) <u>X1</u> 0.35 Contact Pad Length (X44) <u>Y1</u> 0.80 Distance Between Pads G 0.25

#### Notes:


1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2103A

## 44-Lead Plastic Thin Quad Flatpack (PT) – 10x10x1 mm Body, 2.00 mm [TQFP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units		MILLIMETERS	3
	Dimension Limits	MIN	NOM	MAX
Number of Leads	N		44	
Lead Pitch	е		0.80 BSC	
Overall Height	A	-	_	1.20
Molded Package Thickness	A2	0.95	1.00	1.05
Standoff	A1	0.05	_	0.15
Foot Length	L	0.45	0.60	0.75
Footprint	L1		1.00 REF	
Foot Angle	ф	0°	3.5°	7°
Overall Width	E	12.00 BSC		
Overall Length	D	12.00 BSC		
Molded Package Width	E1	10.00 BSC		
Molded Package Length	D1	10.00 BSC		
Lead Thickness	С	0.09	_	0.20
Lead Width	b	0.30	0.37	0.45
Mold Draft Angle Top	α	11°	12°	13°
Mold Draft Angle Bottom	β	11°	12°	13°


#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Chamfers at corners are optional; size may vary.
- 3. Dimensions D1 and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed 0.25 mm per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M.
  - BSC: Basic Dimension. Theoretically exact value shown without tolerances.
  - REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-076B

44-Lead Plastic Thin Quad Flatpack (PT) 10X10X1 mm Body, 2.00 mm Footprint [TQFP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



RECOMMENDED LAND PATTERN

Units		MILLIMETERS		
Dimension Limits		MIN	NOM	MAX
Contact Pitch	Е		0.80 BSC	
Contact Pad Spacing	C1		11.40	
Contact Pad Spacing	C2		11.40	
Contact Pad Width (X44)	X1			0.55
Contact Pad Length (X44)	Y1			1.50
Distance Between Pads	G	0.25		

#### Notes:

1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2076B

## APPENDIX A: REVISION HISTORY

## Revision A (May 2011)

This is the initial released version of this document.

## **Revision B (October 2011)**

The following two global changes are included in this revision:

- All packaging references to VLAP have been changed to VTLA throughout the document
- · All references to VCORE have been removed
- All occurrences of the ASCL1, ASCL2, ASDA1, and ASDA2 pins have been removed
- V-temp temperature range (-40°C to +105°C) was added to all electrical specification tables

This revision includes the addition of the following devices:

- PIC32MX130F064B
- PIC32MX230F064B
- PIC32MX130F064C
- PIC32MX230F064C
- PIC32MX130F064D
- PIC32MX230F064D
- PIC32MX150F128B
- PIC32MX250F128B
- PIC32MX150F128C
- PIC32MX250F128C
- PIC32MX150F128D
- PIC32MX250F128D

Text and formatting changes were incorporated throughout the document.

All other major changes are referenced by their respective section in Table A-1.

#### TABLE A-1: MAJOR SECTION UPDATES

Section	Update Description
"32-bit Microcontrollers (up to 128 KB Flash and 32 KB SRAM) with Audio	Split the existing Features table into two: PIC32MX1XX General Purpose Family Features (Table 1) and PIC32MX2XX USB Family Features (Table 2).
and Graphics Interfaces, USB, and Advanced Analog"	Added the SPDIP package reference (see Table 1, Table 2, and "Pin Diagrams").
	Added the new devices to the applicable pin diagrams.
	Changed PGED2 to PGED1 on pin 35 of the 36-pin VTLA diagram for PIC32MX220F032C, PIC32MX220F016C, PIC32MX230F064C, and PIC32MX250F128C devices.
1.0 "Device Overview"	Added the SPDIP package reference and updated the pin number for AN12 for 44-pin QFN devices in the Pinout I/O Descriptions (see Table 1-1).
	Added the PGEC4/PGED4 pin pair and updated the C1INA-C1IND and C2INA-C2IND pin numbers for 28-pin SSOP/SPDIP/SOIC devices in the Pinout I/O Descriptions (see Table 1-1).
2.0 "Guidelines for Getting Started with 32-bit Microcontrollers"	Updated the Recommended Minimum Connection diagram (see Figure 2-1).

TABLE A-1: MAJOR SECTION UPDATES (CONTINUED)

Section	Update Description
4.0 "Memory Organization"	Added Memory Maps for the new devices (see Figure 4-3 and Figure 4-4).
	Removed the BMXCHEDMA bit from the Bus Matrix Register map (see Table 4-1).
	Added the REFOTRIM register, added the DIVSWEN bit to the REFOCON registers, added Note 4 to the ULOCK and SOSCEN bits and added the PBDIVRDY bit in the OSCCON register in the in the System Control Register map (see Table 4-16).
	Removed the ALTI2C1 and ALTI2C2 bits from the DEVCFG3 register and added Note 1 to the UPLLEN and UPLLIDIV<2:0> bits of the DEVCFG2 register in the Device Configuration Word Summary (see Table 4-17).
	Updated Note 1 in the Device and Revision ID Summary (see Table 4-18).
	Added Note 2 to the PORTA Register map (see Table 4-19).
	Added the ANSB6 and ANSB12 bits to the ANSELB register in the PORTB Register map (see Table 4-20).
	Added Notes 2 and 3 to the PORTC Register map (see Table 4-21).
	Updated all register names in the Peripheral Pin Select Register map (see Table 4-23).
	Added values in support of new devices (16 KB RAM and 32 KB RAM) in the Data RAM Size register (see Register 4-5).
	Added values in support of new devices (64 KB Flash and 128 KB Flash) in the Data RAM Size register (see Register 4-5).
8.0 "Oscillator Configuration"	Added Note 5 to the PIC32MX1XX/2XX Family Clock Diagram (see Figure 8-1).
	Added the PBDIVRDY bit and Note 2 to the Oscillator Control register (see Register 8-1).
	Added the DIVSWEN bit and Note 3 to the Reference Oscillator Control register (see Register 8-3).
	Added the REFOTRIM register (see Register 8-4).
21.0 "10-bit Analog-to-Digital	Updated the ADC1 Module Block Diagram (see Figure 21-1).
Converter (ADC)"	Updated the Notes in the ADC Input Select register (see Register 21-4).
24.0 "Charge Time Measurement	Updated the CTMU Block Diagram (see Figure 24-1).
Unit (CTMU)"	Added Note 3 to the CTMU Control register (see Register 24-1)
26.0 "Special Features"	Added Note 1 and the PGEC4/PGED4 pin pair to the ICESEL<1:0> bits in DEVCFG0: Device Configuration Word 0 (see Register 26-1).
	Removed the ALTI2C1 and ALTI2C2 bits from the Device Configuration Word 3 register (see Register 26-4).
	Removed 26.3.3 "Power-up Requirements".
	Added Note 3 to the Connections for the On-Chip Regulator diagram (see Figure 26-2).
	Updated the Block Diagram of Programming, Debugging and Trace Ports diagram (see Figure 26-3).

TABLE A-1: MAJOR SECTION UPDATES (CONTINUED)

Section	Update Description
29.0 "Electrical Characteristics"	Updated the Absolute Maximum Ratings (removed Voltage on VCORE with respect to Vss).
	Added the SPDIP specification to the Thermal Packaging Characteristics (see Table 29-2).
	Updated the Typical values for parameters DC20-DC24 in the Operating Current (IDD) specification (see Table 29-5).
	Updated the Typical values for parameters DC30a-DC34a in the Idle Current (IIDLE) specification (see Table 29-6).
	Updated the Typical values for parameters DC40i and DC40n and removed parameter DC40m in the Power-down Current (IPD) specification (see Table 29-7).
	Removed parameter D320 (VCORE) from the Internal Voltage Regulator Specifications and updated the Comments (see Table 29-13).
	Updated the Minimum, Typical, and Maximum values for parameter F20b in the Internal FRC Accuracy specification (see Table 29-17).
	Removed parameter SY01 (TPWRT) and removed all Conditions from Resets Timing (see Table 29-20).
	Updated all parameters in the CTMU Specifications (see Table 29-39).
31.0 "Packaging Information"	Added the 28-lead SPDIP package diagram information (see <b>31.1 "Package Marking Information"</b> and <b>31.2 "Package Details"</b> ).
"Product Identification System"	Added the SPDIP (SP) package definition.

## **Revision C (November 2011)**

All major changes are referenced by their respective section in Table A-2.

TABLE A-2: MAJOR SECTION UPDATES

Section	Update Description
"32-bit Microcontrollers (up to 128 KB Flash and 32 KB SRAM) with Audio and Graphics Interfaces, USB, and Advanced Analog"	Revised the source/sink on I/O pins (see "Input/Output" on page 1).  Added the SPDIP package to the PIC32MX220F032B device in the PIC32MX2XX USB Family Features (see Table 2).
4.0 "Memory Organization"	Removed ANSB6 from the ANSELB register and added the ODCB6, ODCB10, and ODCB11 bits in the PORTB Register Map (see Table 4-20).
29.0 "Electrical Characteristics"	Updated the minimum value for parameter OS50 in the PLL Clock Timing Specifications (see Table 29-16).

## **Revision D (February 2012)**

All occurrences of VUSB were changed to: VUSB3V3. In addition, text and formatting changes were incorporated throughout the document.

All other major changes are referenced by their respective section in Table A-3.

TABLE A-3: MAJOR SECTION UPDATES

Section	Update Description
"32-bit Microcontrollers (up to 128	Corrected a part number error in all pin diagrams.
KB Flash and 32 KB SRAM) with Audio and Graphics Interfaces, USB, and Advanced Analog"	Updated the DMA Channels (Programmable/Dedicated) column in the PIC32MX1XX General Purpose Family Features (see Table 1).
1.0 "Device Overview"	Added the TQFP and VTLA packages to the 44-pin column heading and updated the pin numbers for the SCL1, SCL2, SDA1, and SDA2 pins in the Pinout I/O Descriptions (see Table 1-1).
7.0 "Interrupt Controller"	Updated the Note that follows the features.
	Updated the Interrupt Controller Block Diagram (see Figure 7-1).
29.0 "Electrical Characteristics"	Updated the Maximum values for parameters DC20-DC24, and the Minimum value for parameter DC21 in the Operating Current (IDD) DC Characteristics (see Table 29-5).
	Updated all Minimum and Maximum values for the Idle Current (IIDLE) DC Characteristics (see Table 29-6).
	Updated the Maximum values for parameters DC40k, DC40l, DC40n, and DC40m in the Power-down Current (IPD) DC Characteristics (see Table 29-7).
	Changed the minimum clock period for SCKx from 40 ns to 50 ns in Note 3 of the SPIx Master and Slave Mode Timing Requirements (see Table 29-26 through Table 29-29).
30.0 "DC and AC Device Characteristics Graphs"	Updated the Typical IIDLE Current @ VDD = 3.3V graph (see Figure 30-5).

## **Revision E (October 2012)**

All singular pin diagram occurrences of CVREF were changed to: CVREFOUT. In addition, minor text and formatting changes were incorporated throughout the document.

All major changes are referenced by their respective section in Table A-4.

TABLE A-4: MAJOR SECTION UPDATES

Section	Update Description
"32-bit Microcontrollers (up to 128 KB Flash and 32 KB SRAM) with Audio and Graphics Interfaces, USB, and Advanced Analog"	Updated the following feature sections:  • "Operating Conditions"  • "Communication Interfaces"
2.0 "Guidelines for Getting Started with 32-bit MCUs"	Removed Section 2.8 "Configuration of Analog and Digital Pins During ICSP Operations".
3.0 "CPU"	Removed references to GPR shadow registers in <b>3.1 "Features"</b> and <b>3.2.1 "Execution Unit"</b> .
4.0 "Memory Organization"	Updated the BRG bit range in the SPI1 and SPI2 Register Map (see Table 4-8). Added the PWP<6> bit to the Device Configuration Word Summary (see Table 4-17).
5.0 "Flash Program Memory"	Added a note with Flash page size and row size information.
7.0 "Interrupt Controller"	Updated the TPC<2:0> bit definitions (see Register 7-1).  Updated the IPTMR<31:0> bit definition (see Register 7-3).
8.0 "Oscillator Configuration"	Updated the PIC32MX1XX/2XX Family Clock Diagram (see Figure 8-1). Updated the RODIV<14:0> bit definitions (see Register 8-3).
10.0 "USB On-The-Go (OTG)"	Updated the Notes in the USB Interface Diagram (see Figure 10-1).
18.0 "Universal Asynchronous Receiver Transmitter (UART)"	Updated the baud rate range in the list of primary features.
26.0 "Special Features"	Added the PWP<6> bit to the Device Configuration Word 0 (see Register 26-1).
29.0 "Electrical Characteristics"	Added Note 1 to Operating MIPS vs. Voltage (see Table 29-1).  Added Note 2 to DC Temperature and Voltage Specifications (see Table 29-4).  Updated the Conditions for parameter DC25 in DC Characteristics: Operating Current (IDD) (see Table 29-5).  Added Note 2 to Electrical Characteristics: BOR (see Table 29-10).  Added Note 4 to Comparator Specifications (see Table 29-12).  Added Note 5 to ADC Module Specifications (see Table 29-32).  Updated the 10-bit Conversion Rate Parameters and added Note 3 (see Table 29-33).  Added Note 4 to the Analog-to-Digital Conversion Timing Requirements (see Table 29-34).
	Added Note 3 to CTMU Current Source Specifications (see Table 29-39).
30.0 "50 MHz Electrical Characteristics"	New chapter with electrical characteristics for 50 MHz devices.
31.0 "Packaging Information"	The 36-pin and 44-pin VTLA packages have been updated.

## **Revision F (February 2014)**

This revision includes the addition of the following devices:

• PIC32MX170F256B

• PIC32MX270F256B

• PIC32MX170F256D

• PIC32MX270F256D

In addition, this revision includes the following major changes as described in Table A-5, as well as minor updates to text and formatting, which were incorporated throughout the document.

#### TABLE A-5: MAJOR SECTION UPDATES

Section	Update Description
32-bit Microcontrollers (up to 256 KB Flash and 64 KB SRAM) with Audio and Graphics Interfaces, USB, and Advanced Analog	Added new devices to the family features (see Table 1 and Table 2). Updated pin diagrams to include new devices (see "Pin Diagrams").
1.0 "Device Overview"	Added Note 3 reference to the following pin names: VBUS, VUSB3V3, VBUSON, D+, D-, and USBID.
2.0 "Guidelines for Getting Started with 32-bit MCUs"	Replaced Figure 2-1: Recommended Minimum Connection.  Updated Figure 2-2: MCLR Pin Connections.  Added 2.9 "Sosc Design Recommendation".
4.0 "Memory Organization"	Added memory tables for devices with 64 KB RAM (see Table 4-4 through Table 4-5).
	Changed the Virtual Addresses for all registers and updated the PWP bits in the DEVCFG: Device Configuration Word Summary (see Table 4-17).
	Updated the ODCA, ODCB, and ODCC port registers (see Table 4-19, Table 4-20, and Table 4-21).
	The RTCTIME, RTCDATE, ALRMTIME, and ALRMDATE registers were updated (see Table 4-25).
	Added Data Ram Size value for 64 KB RAM devices (see Register 4-5).
12.0 "Timer1"	Added Program Flash Size value for 256 KB Flash devices (see Register 4-5).
	The Timer1 block diagram was updated to include the 16-bit data bus (see Figure 12-1).
13.0 "Timer2/3, Timer4/5"	The Timer2-Timer5 block diagram (16-bit) was updated to include the 16-bit data bus (see Figure 13-1).
	The Timer2/3, Timer4/5 block diagram (32-bit) was updated to include the 32-bit data bus (see Figure 13-1).
19.0 "Parallel Master Port (PMP)"	The CSF<1:0> bit value definitions for '00' and '01' were updated (see Register 19-1).
	Bit 14 in the Parallel Port Address register (PMADDR) was updated (see Register 19-3).
20.0 "Real-Time Clock and Calendar (RTCC)"	The following registers were updated:  RTCTIME (see Register 20-3)
	RTCDATE (see Register 20-4)
	ALRMTIME (see Register 20-5)
	ALRMDATE (see Register 20-6)
26.0 "Special Features"	Updated the PWP bits (see Register 26-1).
29.0 "Electrical Characteristics"	Added parameters DO50 and DO50a to the Capacitive Loading Requirements on Output Pins (see Table 29-14).
	Added Note 5 to the IDD DC Characteristics (see Table 29-5).
	Added Note 4 to the IIDLE DC Characteristics (see Table 29-6).
	Added Note 5 to the IPD DC Characteristics (see Table 29-7).
	Updated the conditions for parameters USB321 (VOL) and USB322 (VOH) in the OTG Electrical Specifications (see Table 29-38).
Product Identification System	Added 40 MHz speed information.

## **Revision G (April 2015)**

This revision includes the addition of the following devices:

- PIC32MX130F256B
- PIC32MX230F256B
- PIC32MX130F256D
- PIC32MX230F256D

The title of the document was updated to avoid confusion with the PIC32MX1XX/2XX/5XX 64/100-pin Family data sheet.

All peripheral SFR maps have been relocated from the Memory chapter to their respective peripheral chapters.

In addition, this revision includes the following major changes as described in Table A-6, as well as minor updates to text and formatting, which were incorporated throughout the document.

TABLE A-6: MAJOR SECTION UPDATES

Section	Update Description			
32-bit Microcontrollers (up to 256 KB Flash and 64 KB SRAM) with Audio and Graphics Interfaces, USB, and Advanced Analog	Added new devices to the family features (see Table 1 and Table 2).  Updated pin diagrams to include new devices (see Pin Diagrams).			
2.0 "Guidelines for Getting Started with 32-bit MCUs"	Updated these sections: 2.2 "Decoupling Capacitors", 2.3 "Capacitor on Internal Voltage Regulator (VCAP)", 2.4 "Master Clear (MCLR) Pin", 2.8.1 "Crystal Oscillator Design Consideration"			
4.0 "Memory Organization"	Added Memory Map for new devices (see Figure 4-6).			
14.0 "Watchdog Timer (WDT)"	New chapter created from content previously located in the Special Features chapter.			
30.0 "Electrical Characteristics"	Removed parameter D312 (TSET) from the Comparator Specifications (see Table 30-12).			
	Added the Comparator Voltage Reference Specifications (see Table 30-13).			
	Updated Table 30-12.			

## Revision H (July 2015)

This revision includes the following major changes as described in Table A-7, as well as minor updates to text and formatting, which were incorporated throughout the document.

TABLE A-7: MAJOR SECTION UPDATES

Section	Update Description		
2.0 "Guidelines for Getting Started with 32-bit MCUs"	Section 2.9 "Sosc Design Recommendation" was removed.		
8.0 "Oscillator Configuration"	The Primary Oscillator (Posc) logic in the Oscillator diagram was updated (see Figure 8-1).		
30.0 "Electrical Characteristics"	The Power-Down Current (IPD) DC Characteristics parameter DC40k was updated (see Table 30-7).		
	Table 30-9: "DC Characteristics: I/O Pin Input Injection current Specifications" was added.		

## Revision J (April 2016)

This revision includes the following major changes as described in Table A-8, as well as minor updates to text and formatting, which were incorporated throughout the document.

TABLE A-8: MAJOR SECTION UPDATES

Section	Update Description
"32-bit Microcontrollers (up to 256 KB Flash and 64 KB SRAM) with Audio and Graphics Interfaces, USB, and Advanced Analog"	The PIC32MX270FDB device and Note 4 were added to TABLE 2: "PIC32MX2XX 28/36/44-pin USB Family Features".
2.0 "Guidelines for Getting Started with 32-bit MCUs"	EXAMPLE 2-1: "Crystal Load Capacitor Calculation" was updated.
30.0 "Electrical Characteristics"	Parameter DO50a (Csosc) was removed from the Capacitive Loading Requirements on Output Pins AC Characteristics (see Table 30-16).
"Product Identification System"	The device mapping was updated to include type B for Software Targeting.

## Revision K (May 2018)

This revision includes the following major changes as described in Table A-9, as well as minor updates to text and formatting, which were incorporated throughout the document.

TABLE A-9: MAJOR SECTION UPDATES

Section	Update Description
"32-bit Microcontrollers (up to 256 KB Flash and 64 KB SRAM) with Audio and Graphics Interfaces, USB, and Advanced Analog"	The PIC32MX270F256DB device and Note 4 were removed from the PIC32MX2XX 28/36/44-Pin USB Family Features (see Table 2).
"Product Identification System"	Type B for Software Targeting was removed.
Section 2.10 "Considerations When Interfacing To Remotely Powered Circuits"	A new section has been added.

## Revision L (September 2019)

This revision includes the following major changes as described in Table A-10, as well as minor updates to text and formatting, which were incorporated throughout the document.

## **TABLE A-10: MAJOR SECTION UPDATES**

Section	Update Description
2.0 "Guidelines for Getting Started with 32-bit MCUs"	Added new section 2.11 "EMI/EMC/EFT (IEC 61000-4-4 and IEC 61000-4-2) Suppression Considerations"
17.0 "Serial Peripheral Interface (SPI)"	Updated information for the FRMPOL bit for Register 17-1: "SPIx CON: SPI Control Register"
20.0 "Parallel Master Port (PMP)"	Updated Register 20-2: "PMMODE: Parallel Port Mode Register" with a new Note 3
,	Updated Register Register 20-5: "PMSTAT: Parallel Port Status Register (Slave modes only)" with a new Note 1
22.0 "10-bit Analog-to-Digital Converter (ADC)"	<ul> <li>Updated Note 2 of FIGURE 22-1: "ADC1 Module Block Diagram"</li> <li>Updated Note 4 of Register 22-4: "AD1CHS: ADC Input Select Register"</li> </ul>

NOTES:			

## **INDEX**

Numerics		Core
50 MHz Electrical Characteristics	305	EJTA
A		Powe CPU Mod
	072	Customer
AC Characteristics		Customer
ADC Specifications		Customer
Analog-to-Digital Conversion Requirements		Ъ
EJTAG Timing Requirements		D
Internal FRC Accuracy		DC and A
Internal RC Accuracy		Grap
OTG Electrical Specifications	302	DC Chara
Parallel Master Port Read Requirements		I/O F
Parallel Master Port Write		I/O P Idle (
Parallel Master Port Write Requirements		Powe
Parallel Slave Port Requirements		Prog
PLL Clock Timing		Tem
Analog-to-Digital Converter (ADC)	213	DC Chara
Assembler	050	Idle (
MPASM Assembler	258	Powe
В		Developm
Block Diagrams		Direct Me
ADC Module	213	E
Comparator I/O Operating Modes		E
Comparator Voltage Reference		Electrical
Connections for On-Chip Voltage Regulator		AC
Core and Peripheral Modules		Errata
CPU	37	External C
CTMU Configurations		Time
Time Measurement	231	Time Timir
DMA	87	External C
I2C Circuit		External C
Input Capture		1111111
Interrupt Controller		F
JTAG Programming, Debugging and Trace Ports.		Flash Pro
Output Compare Module		RTS
PMP Pinout and Connections to External Devices		
Reset System		ı
RTCCSPI Module		I/O Ports
Timer1		Para
Timer2/3/4/5 (16-Bit)		Write
Typical Multiplexed Port Structure		Input Cha
UART		Instruction
WDT and Power-up Timer		Inter-Integ
Brown-out Reset (BOR)	101	Internal V
and On-Chip Voltage Regulator	254	Internet A
		Interrupt (
C		IRG,
C Compilers		M
MPLAB C18	258	Memory N
Charge Time Measurement Unit. See CTMU.		PIC3
Clock Diagram	78	1.00
Comparator		PIC3
Specifications27	,	
Comparator Module		PIC3
Comparator Voltage Reference (CVref		
Configuration Bit		PIC3
Configuring Analog Port Pins	132	
CPU Architecture Overview	20	PIC3
Architecture Overview		
Coprocessor 0 Registers	39	PIC3

Core Exception Types 40	
EJTAG Debug Support40	
Power Management	
CPU Module	7
Customer Change Notification Service	
Customer Notification Service	7
Customer Support	7
<b>B</b>	
D	
DC and AC Characteristics	
Graphs and Tables311	1
DC Characteristics	
I/O Pin Input Specifications	3
I/O Pin Output Specifications	9
Idle Current (IIDLE)265	
Power-Down Current (IPD)266	3
Program Memory270	
Temperature and Voltage Specifications 263	3
DC Characteristics (50 MHz)	3
Idle Current (IIDLE)307	
Power-Down Current (IPD)307	
Development Support257	
Direct Memory Access (DMA) Controller87	
E	
Electrical Characteristics	1
AC273	3
Errata	7
External Clock	
Timer1 Timing Requirements 279	
Timer2, 3, 4, 5 Timing Requirements 280	)
Timing Requirements	4
External Clock (50 MHz)	
External Clock (50 MHz) Timing Requirements	3
Timing Requirements	3
Timing Requirements	
Timing Requirements	7
Timing Requirements	7
Timing Requirements 308  F  Flash Program Memory 57  RTSP Operation 57	7
Timing Requirements	7
Timing Requirements	7 7 1
Timing Requirements	7 7 1 2
Timing Requirements	7 7 1 2 2
Timing Requirements       308         F       57         Flash Program Memory       57         RTSP Operation       57         I       I/O Ports       131         Parallel I/O (PIO)       132         Write/Read Timing       132         Input Change Notification       132	7 7 1 2 2 2
Timing Requirements       308         F         Flash Program Memory       57         RTSP Operation       57         I         I/O Ports       131         Parallel I/O (PIO)       132         Write/Read Timing       132         Input Change Notification       132         Instruction Set       255	7 7 1 2 2 5
Timing Requirements       308         F       57         Flash Program Memory       57         RTSP Operation       57         I       I/O Ports       131         Parallel I/O (PIO)       132         Write/Read Timing       132         Input Change Notification       132         Instruction Set       255         Inter-Integrated Circuit (I2C       177	7 7 1 2 2 5 7
Timing Requirements       308         F       57         Flash Program Memory       57         RTSP Operation       57         I       I/O Ports       131         Parallel I/O (PIO)       132         Write/Read Timing       132         Input Change Notification       132         Instruction Set       255         Inter-Integrated Circuit (I2C       177         Internal Voltage Reference Specifications       272	7 1 2 2 5 7 2
Timing Requirements       308         F       57         Flash Program Memory       57         RTSP Operation       57         I       I/O Ports       131         Parallel I/O (PIO)       132         Write/Read Timing       132         Input Change Notification       132         Instruction Set       255         Inter-Integrated Circuit (I2C       177         Internal Voltage Reference Specifications       272         Internet Address       347	77 1225727
Timing Requirements       308         F       57         Flash Program Memory       57         RTSP Operation       57         I       I/O Ports       131         Parallel I/O (PIO)       132         Write/Read Timing       132         Input Change Notification       132         Instruction Set       255         Inter-Integrated Circuit (I2C       177         Internal Voltage Reference Specifications       272         Internet Address       347         Interrupt Controller       67	77 12257277
Timing Requirements       308         F       57         Flash Program Memory       57         RTSP Operation       57         I       I/O Ports       131         Parallel I/O (PIO)       132         Write/Read Timing       132         Input Change Notification       132         Instruction Set       255         Inter-Integrated Circuit (I2C       177         Internal Voltage Reference Specifications       272         Internet Address       347	77 12257277
Timing Requirements       308         F       57         Flash Program Memory       57         RTSP Operation       57         I       I/O Ports       131         Parallel I/O (PIO)       132         Write/Read Timing       132         Input Change Notification       132         Instruction Set       255         Inter-Integrated Circuit (I2C       177         Internal Voltage Reference Specifications       272         Internet Address       347         Interrupt Controller       67	77 12257277
Timing Requirements       308         F         Flash Program Memory       57         RTSP Operation       57         I         I/O Ports       131         Parallel I/O (PIO)       132         Write/Read Timing       132         Input Change Notification       132         Instruction Set       255         Inter-Integrated Circuit (I2C       177         Internal Voltage Reference Specifications       272         Internet Address       347         Interrupt Controller       67         IRG, Vector and Bit Location       68         M	77 12257277
Timing Requirements       308         F         Flash Program Memory       57         RTSP Operation       57         I         I/O Ports       131         Parallel I/O (PIO)       132         Write/Read Timing       132         Input Change Notification       132         Instruction Set       255         Inter-Integrated Circuit (I2C       177         Internal Voltage Reference Specifications       272         Internet Address       347         Interrupt Controller       67         IRG, Vector and Bit Location       68         M         Memory Maps	77 12257277
Timing Requirements       308         F         Flash Program Memory       57         RTSP Operation       57         I         I/O Ports       131         Parallel I/O (PIO)       132         Write/Read Timing       132         Input Change Notification       132         Instruction Set       255         Inter-Integrated Circuit (I2C       177         Internal Voltage Reference Specifications       277         Internet Address       347         Interrupt Controller       67         IRG, Vector and Bit Location       68         M         Memory Maps       PIC32MX110/210 Devices	7 7 1 1 2 2 2 7 7 7 7 8
Timing Requirements       308         F         Flash Program Memory       57         RTSP Operation       57         I         I/O Ports       131         Parallel I/O (PIO)       132         Write/Read Timing       132         Input Change Notification       132         Instruction Set       255         Inter-Integrated Circuit (I2C       177         Internal Voltage Reference Specifications       272         Internet Address       347         Interrupt Controller       67         IRG, Vector and Bit Location       68         M         Memory Maps       PIC32MX110/210 Devices         (4 KB RAM, 16 KB Flash)       42	7 7 1 1 2 2 2 7 7 7 7 8
Timing Requirements       308         F         Flash Program Memory       57         RTSP Operation       57         I         I/O Ports       131         Parallel I/O (PIO)       132         Write/Read Timing       132         Input Change Notification       132         Instruction Set       255         Inter-Integrated Circuit (I2C       177         Internal Voltage Reference Specifications       272         Internet Address       347         Interrupt Controller       67         IRG, Vector and Bit Location       68         M         Memory Maps       PIC32MX110/210 Devices         (4 KB RAM, 16 KB Flash)       42         PIC32MX120/220 Devices	7 7 1 2 2 5 7 7 7 7 8
Timing Requirements       308         F         Flash Program Memory       57         RTSP Operation       57         I         I/O Ports       131         Parallel I/O (PIO)       132         Write/Read Timing       132         Input Change Notification       132         Instruction Set       255         Inter-Integrated Circuit (I2C       177         Internal Voltage Reference Specifications       272         Internet Address       347         Interrupt Controller       67         IRG, Vector and Bit Location       68         M         Memory Maps       PIC32MX110/210 Devices         (4 KB RAM, 16 KB Flash)       42         PIC32MX120/220 Devices       (8 KB RAM, 32 KB Flash)       43	7 7 1 2 2 5 7 7 7 7 8
Timing Requirements       308         F         Flash Program Memory       57         RTSP Operation       57         I       I/O Ports       131         Parallel I/O (PIO)       132         Write/Read Timing       132         Input Change Notification       132         Instruction Set       255         Inter-Integrated Circuit (I2C       177         Internal Voltage Reference Specifications       272         Internet Address       347         Interrupt Controller       67         IRG, Vector and Bit Location       68         M         Memory Maps       PIC32MX110/210 Devices         (4 KB RAM, 16 KB Flash)       42         PIC32MX120/220 Devices       (8 KB RAM, 32 KB Flash)       43         PIC32MX130/230	7 7 7 1 2 2 5 7 7 7 8
Timing Requirements       308         F         Flash Program Memory       57         RTSP Operation       57         I       I/O Ports       131         Parallel I/O (PIO)       132         Write/Read Timing       132         Input Change Notification       132         Instruction Set       255         Inter-Integrated Circuit (I2C       177         Internal Voltage Reference Specifications       272         Internet Address       347         Interrupt Controller       67         IRG, Vector and Bit Location       68         M         M       M         Memory Maps       PIC32MX110/210 Devices         (4 KB RAM, 16 KB Flash)       42         PIC32MX120/220 Devices       (8 KB RAM, 32 KB Flash)       43         PIC32MX130/230       (16 KB RAM, 256 KB Flash)       47	7 7 7 1 2 2 5 7 7 7 8
Timing Requirements       308         F         Flash Program Memory       57         RTSP Operation       57         I         I/O Ports       131         Parallel I/O (PIO)       132         Write/Read Timing       132         Input Change Notification       132         Instruction Set       255         Inter-Integrated Circuit (I2C       177         Internal Voltage Reference Specifications       272         Internet Address       347         Interrupt Controller       67         IRG, Vector and Bit Location       68         M         Memory Maps       PIC32MX110/210 Devices         (4 KB RAM, 16 KB Flash)       42         PIC32MX120/220 Devices       (8 KB RAM, 32 KB Flash)       43         PIC32MX130/230       (16 KB RAM, 256 KB Flash)       47         PIC32MX130/230 Devices       47	7 7 7 1 2 2 5 7 7 7 3
Timing Requirements       308         F         Flash Program Memory       57         RTSP Operation       57         I         I/O Ports       131         Parallel I/O (PIO)       132         Write/Read Timing       132         Input Change Notification       132         Instruction Set       255         Inter-Integrated Circuit (I2C       177         Internal Voltage Reference Specifications       272         Internet Address       347         Interrupt Controller       67         IRG, Vector and Bit Location       68         M         M         Memory Maps       PIC32MX110/210 Devices         (4 KB RAM, 16 KB Flash)       42         PIC32MX120/220 Devices       (8 KB RAM, 32 KB Flash)       43         PIC32MX130/230       (16 KB RAM, 256 KB Flash)       47         PIC32MX130/230 Devices       (16 KB RAM, 64 KB Flash)       47          PIC32MX130/230 Devices       (16 KB RAM, 64 KB Flash)       48	7 7 7 1 2 2 5 7 7 7 3
Timing Requirements       308         F         Flash Program Memory       57         RTSP Operation       57         I         I/O Ports       131         Parallel I/O (PIO)       132         Write/Read Timing       132         Input Change Notification       132         Instruction Set       255         Inter-Integrated Circuit (I2C       177         Internal Voltage Reference Specifications       272         Internet Address       347         Interrupt Controller       67         IRG, Vector and Bit Location       68         M         M         Memory Maps       PIC32MX110/210 Devices         (4 KB RAM, 16 KB Flash)       42         PIC32MX120/220 Devices       (8 KB RAM, 32 KB Flash)       43         PIC32MX130/230       (16 KB RAM, 256 KB Flash)       47         PIC32MX130/230 Devices       (16 KB RAM, 64 KB Flash)       44         PIC32MX150/250 Devices	7 7 7 1 2 2 5 7 7 7 3 7 4
Timing Requirements       308         F         Flash Program Memory       57         RTSP Operation       57         I         I/O Ports       131         Parallel I/O (PIO)       132         Write/Read Timing       132         Input Change Notification       132         Instruction Set       255         Inter-Integrated Circuit (I2C       177         Internal Voltage Reference Specifications       272         Internet Address       347         Interrupt Controller       67         IRG, Vector and Bit Location       68         M         M         Memory Maps       PIC32MX110/210 Devices         (4 KB RAM, 16 KB Flash)       42         PIC32MX120/220 Devices       (8 KB RAM, 32 KB Flash)       43         PIC32MX130/230       (16 KB RAM, 256 KB Flash)       47         PIC32MX130/230 Devices       (16 KB RAM, 64 KB Flash)       47          PIC32MX130/230 Devices       (16 KB RAM, 64 KB Flash)       48	7 7 7 1 2 2 5 7 7 7 3 7 4

(64 KB RAM, 256 KB Flash)	46	DCHxSPTR (DMA Channel 'x' Source Pointer)	10
Memory Organization		DCHxSSA (DMA Channel 'x' Source Start Address	
Microchip Internet Web Site		DCHxSSIZ (DMA Channel 'x' Source Size)	,
MPLAB ASM30 Assembler, Linker, Librarian		DCRCCON (DMA CRC Control)	
MPLAB Integrated Development Environment Softw		DCRCDATA (DMA CRC Data)	
MPLAB PM3 Device Programmer		DCRCXOR (DMA CRCXOR Enable)	
MPLAB REAL ICE In-Circuit Emulator System		DEVCFG0 (Device Configuration Word 0)	
MPLINK Object Linker/MPLIB Object Librarian		DEVCFG1 (Device Configuration Word 1)	
	200	DEVCFG2 (Device Configuration Word 2)	
0		DEVCFG3 (Device Configuration Word 3)	
Oscillator Configuration	77	DEVID (Device and Revision ID)	
Output Compare		DMAADDR (DMA Address)	
·		DMACON (DMA Controller Control)	
P		DMASTAT (DMA Status)	
Packaging	315	I2CxCON (I2C Control)	
Details		I2CxSTAT (I2C Status)	
Marking	315	ICxCON (Input Capture 'x' Control)	
Parallel Master Port (PMP)		IECx (Interrupt Enable Control)	
PIC32 Family USB Interface Diagram		IFSx (Interrupt Flag Status)	
Pinout I/O Descriptions (table)		INTCON (Interrupt Control)	
Power-on Reset (POR)		INTSTAT (Interrupt Status)	
and On-Chip Voltage Regulator	254	IPCx (Interrupt Priority Control)	
Power-Saving Features			
CPU Halted Methods		IPTMR (Interrupt Proximity Timer) NVMADDR (Flash Address)	
Operation		NVMCON (Programming Control)	
with CPU Running		`	
with or o realining	207	NVMDATA (Flash Program Data)	
R		NVMKEY (Programming Unlock)	
Real-Time Clock and Calendar (RTCC)	203	NVMSRCADDR (Source Data Address)	
Register Maps		OCXCON (Output Compare 'x' Control)	
Registers		OSCCON (Oscillator Control)	
[pin name]R (Peripheral Pin Select Input)	145	OSCTUN (FRC Tuning)	
AD1CHS (ADC Input Select)		PMADDR (Parallel Port Address)	
AD1CON1 (ADC Control 1)		PMAEN (Parallel Port Pin Enable)	
AD1CON2 (ADC Control 2)		PMCON (Parallel Port Control)	
AD1CON3 (ADC Control 3)		PMMODE (Parallel Port Mode)	
AD1CSSL (ADC Input Scan Select)		PMSTAT (Parallel Port Status (Slave Modes Only)	,
ALRMDATE (Alarm Date Value)		REFOCON (Reference Oscillator Control)	
ALRMTIME (Alarm Time Value)		REFOTRIM (Reference Oscillator Trim)	
BMXBOOTSZ (Boot Flash (IFM) Size		RPnR (Peripheral Pin Select Output)	
BMXCON (Bus Matrix Configuration)		RSWRST (Software Reset)	
BMXDKPBA (Data RAM Kernel Program		RTCALRM (RTC Alarm Control)	
Base Address)	51	RTCCON (RTC Control)	
BMXDRMSZ (Data RAM Size Register)		RTCDATE (RTC Date Value)	
BMXDUDBA (Data RAM User Data Base Addr		RTCTIME (RTC Time Value)	
BMXDUPBA (Data RAM User Program	ess) J2	SPIxCON (SPI Control)	
Base Address)	53	SPIxCON2 (SPI Control 2)	
BMXPFMSZ (Program Flash (PFM) Size)		SPIxSTAT (SPI Status)	
, , , ,		T1CON (Type A Timer Control)	
BMXPUPBA (Program Flash (PFM) User Progr		TxCON (Type B Timer Control)	
Base Address) CFGCON (Configuration Control)		U1ADDR (USB Address)	
`		U1BDTP1 (USB BDT Page 1)	
CM1CON (Comparator 1 Control)		U1BDTP2 (USB BDT Page 2)	
CMSTAT (Comparator Status Register)		U1BDTP3 (USB BDT Page 3)	
CNCONx (Change Notice Control for PORTx).		U1CNFG1 (USB Configuration 1)	12
CTMUCON (CTMU Control)		U1CON (USB Control)	12
CVRCON (Comparator Voltage Reference Cor		U1EIE (USB Error Interrupt Enable)	
DCHxCON (DMA Channel 'x' Control)		U1EIR (USB Error Interrupt Status)	
DCHxCPTR (DMA Channel 'x' Cell Pointer)		U1EP0-U1EP15 (USB Endpoint Control)	
DCHxCSIZ (DMA Channel 'x' Cell-Size)		U1FRMH (USB Frame Number High)	
DCHxDAT (DMA Channel 'x' Pattern Data)		U1FRML (USB Frame Number Low)	
DCHxDPTR (Channel 'x' Destination Pointer)	103	U1IE (USB Interrupt Enable)	
DCHxDSA (DMA Channel 'x' Destination		U1IR (USB Interrupt)	
Start Address)		U1OTGCON (USB OTG Control)	
DCHxDSIZ (DMA Channel 'x' Destination Size)	,	U1OTGIE (USB OTG Interrupt Enable)	
DCHxECON (DMA Channel 'x' Event Control).		U10TGIR (USB OTG Interrupt Status)	
DCHxINT (DMA Channel 'x' Interrupt Control)	99	- · · · · · · · · · · · · · · · · · · ·	

U1OTGSTAT (USB OTG Status)	. 114
U1PWRC (USB Power Control)	. 116
U1SOF (USB SOF Threshold)	. 127
U1STAT (USB Status)	. 122
U1TOK (USB Token)	. 126
UxMODE (UARTx Mode)	
UxSTA (UARTx Status and Control)	. 189
WDTCON (Watchdog Timer Control)	. 159
Resets	63
Revision History	
RTCALRM (RTC ALARM Control)	. 207
S	
Serial Peripheral Interface (SPI)	. 169
Software Simulator (MPLAB SIM)	
Special Features	
т	
Timer1 Module	147
Timer2/3, Timer4/5 Modules	
Timing Diagrams	
10-Bit Analog-to-Digital Conversion	
(ASAM = 0, SSRC<2:0> = 000)	. 297
10-Bit Analog-to-Digital Conversion (ASAM = 1,	
SSRC<2:0> = 111, SAMC<4:0> = 00001)	. 298
EJTAG	
External Clock	. 273
I/O Characteristics	. 276
I2Cx Bus Data (Master Mode)	. 287
I2Cx Bus Data (Slave Mode)	
I2Cx Bus Start/Stop Bits (Master Mode)	. 287
I2Cx Bus Start/Stop Bits (Slave Mode)	. 290
Input Capture (CAPx)	. 280
OCx/PWM	. 281
Output Compare (OCx)	
Parallel Master Port Read	. 300
Parallel Master Port Write	. 301

Parallel Slave Port	299
SPIx Master Mode (CKE = 0)	282
SPIx Master Mode (CKE = 1)	283
SPIx Slave Mode (CKE = 0)	284
SPIx Slave Mode (CKE = 1)	285
Timer1, 2, 3, 4, 5 External Clock	
UART Reception	191
UART Transmission (8-bit or 9-bit Data)	191
Timing Requirements	
CLKO and I/O	276
Timing Specifications	
I2Cx Bus Data Requirements (Master Mode)	
I2Cx Bus Data Requirements (Slave Mode)	291
Input Capture Requirements	
Output Compare Requirements	281
Simple OCx/PWM Mode Requirements	281
SPIx Master Mode (CKE = 0) Requirements	282
SPIx Master Mode (CKE = 1) Requirements	283
SPIx Slave Mode (CKE = 1) Requirements	285
SPIx Slave Mode Requirements (CKE = 0)	284
Timing Specifications (50 MHz)	
SPIx Master Mode (CKE = 0) Requirements	
SPIx Master Mode (CKE = 1) Requirements	
SPIx Slave Mode (CKE = 1) Requirements	
SPIx Slave Mode Requirements (CKE = 0)	309
U	
UART	105
USB On-The-Go (OTG)	
03B 011-11le-G0 (01G)	107
V	
VCAP pin	254
Voltage Regulator (On-Chip)	254
W	
WWW Address	347
MMMM On Line Cunnert	

NOTES:	 	

#### THE MICROCHIP WEB SITE

Microchip provides online support via our WWW site at www.microchip.com. This web site is used as a means to make files and information easily available to customers. Accessible by using your favorite Internet browser, the web site contains the following information:

- Product Support Data sheets and errata, application notes and sample programs, design resources, user's guides and hardware support documents, latest software releases and archived software
- General Technical Support Frequently Asked Questions (FAQ), technical support requests, online discussion groups, Microchip consultant program member listing
- Business of Microchip Product selector and ordering guides, latest Microchip press releases, listing of seminars and events, listings of Microchip sales offices, distributors and factory representatives

# CUSTOMER CHANGE NOTIFICATION SERVICE

Microchip's customer notification service helps keep customers current on Microchip products. Subscribers will receive e-mail notification whenever there are changes, updates, revisions or errata related to a specified product family or development tool of interest.

To register, access the Microchip web site at www.microchip.com. Under "Support", click on "Customer Change Notification" and follow the registration instructions.

#### **CUSTOMER SUPPORT**

Users of Microchip products can receive assistance through several channels:

- · Distributor or Representative
- · Local Sales Office
- Field Application Engineer (FAE)
- · Technical Support

Customers should contact their distributor, representative or Field Application Engineer (FAE) for support. Local sales offices are also available to help customers. A listing of sales offices and locations is included in the back of this document.

Technical support is available through the web site at: http://microchip.com/support

## PRODUCT IDENTIFICATION SYSTEM

To order or obtain information, e.g., on pricing or delivery, refer to the factory or the listed sales office.

Microchip Brand Architecture Product Groups Flash Memory Family Program Memory Size (KB) Pin Count Tape and Reel Flag (if applicable) Speed (if applicable) Temperature Range Package Pattern  Example: PIC32 MX 1XX F 032 D T - 50 I / PT - XXX  Example: PIC32MX110F032DT-I/PT: General purpose PIC32, 32-bit RISC MCU with M4K® core, 32 KB program memory, 44-pin, Industrial temperature, TQFP package.	
Flash Memory Family	
Architecture	MX = M4K <sup>®</sup> MCU core
Product Groups	1XX = General purpose microcontroller family 2XX = General purpose microcontroller family
Flash Memory Family	F = Flash program memory
Program Memory Size	016 = 16K 032 = 32K 064 = 64K 128 = 128K 256 = 256K
Pin Count	B = 28-pin C = 36-pin D = 44-pin
Speed	( ) = 40 MHz – ( ) indicates a blank field; package markings for 40 MHz devices do not include the Speed 50 = 50 MHz
Temperature Range	I = -40°C to +85°C (Industrial) V = -40°C to +105°C (V-temp)
Package	ML = 28-Lead (6x6 mm) QFN (Plastic Quad Flatpack) ML = 44-Lead (8x8 mm) QFN (Plastic Quad Flatpack) PT = 44-Lead (10x10x1 mm) TQFP (Plastic Thin Quad Flatpack) SO = 28-Lead (7.50 mm) SOIC (Plastic Small Outline) SP = 28-Lead (300 mil) SPDIP (Skinny Plastic Dual In-line) SS = 28-Lead (5x30 mm) SSOP (Plastic Shrink Small Outline) TL = 36-Lead (5x5 mm) VTLA (Very Thin Leadless Array) TL = 44-Lead (6x6 mm) VTLA (Very Thin Leadless Array)
Pattern	Three-digit QTP, SQTP, Code or Special Requirements (blank otherwise) ES = Engineering Sample

#### Note the following details of the code protection feature on Microchip devices:

- · Microchip products meet the specification contained in their particular Microchip Data Sheet.
- Microchip believes that its family of products is one of the most secure families of its kind on the market today, when used in the intended manner and under normal conditions.
- There are dishonest and possibly illegal methods used to breach the code protection feature. All of these methods, to our
  knowledge, require using the Microchip products in a manner outside the operating specifications contained in Microchip's Data
  Sheets. Most likely, the person doing so is engaged in theft of intellectual property.
- · Microchip is willing to work with the customer who is concerned about the integrity of their code.
- Neither Microchip nor any other semiconductor manufacturer can guarantee the security of their code. Code protection does not mean that we are guaranteeing the product as "unbreakable."

Code protection is constantly evolving. We at Microchip are committed to continuously improving the code protection features of our products. Attempts to break Microchip's code protection feature may be a violation of the Digital Millennium Copyright Act. If such acts allow unauthorized access to your software or other copyrighted work, you may have a right to sue for relief under that Act.

Information contained in this publication regarding device applications and the like is provided only for your convenience and may be superseded by updates. It is your responsibility to ensure that your application meets with your specifications. MICROCHIP MAKES NO REPRESENTATIONS OR WARRANTIES OF ANY KIND WHETHER EXPRESS OR IMPLIED, WRITTEN OR ORAL, STATUTORY OR OTHERWISE, RELATED TO THE INFORMATION, INCLUDING BUT NOT LIMITED TO ITS CONDITION, QUALITY, PERFORMANCE, MERCHANTABILITY OR FITNESS FOR PURPOSE. Microchip disclaims all liability arising from this information and its use. Use of Microchip devices in life support and/or safety applications is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless Microchip from any and all damages, claims, suits, or expenses resulting from such use. No licenses are conveyed, implicitly or otherwise, under any Microchip intellectual property rights unless otherwise stated.

Microchip received ISO/TS-16949:2009 certification for its worldwide headquarters, design and wafer fabrication facilities in Chandler and Tempe, Arizona; Gresham, Oregon and design centers in California and India. The Company's quality system processes and procedures are for its PIC® MCUs and dsPIC® DSCs, KEELOQ® code hopping devices, Serial EEPROMs, microperipherals, nonvolatile memory and analog products. In addition, Microchip's quality system for the design and manufacture of development systems is ISO 9001:2000 certified.

# QUALITY MANAGEMENT SYSTEM CERTIFIED BY DNV = ISO/TS 16949=

#### Trademarks

The Microchip name and logo, the Microchip logo, AnyRate, AVR, AVR logo, AVR Freaks, BitCloud, chipKIT, chipKIT logo, CryptoMemory, CryptoRF, dsPIC, FlashFlex, flexPWR, Heldo, JukeBlox, KeeLoq, Kleer, LANCheck, LINK MD, maXStylus, maXTouch, MediaLB, megaAVR, MOST, MOST logo, MPLAB, OptoLyzer, PIC, picoPower, PICSTART, PIC32 logo, Prochip Designer, QTouch, SAM-BA, SpyNIC, SST, SST Logo, SuperFlash, tinyAVR, UNI/O, and XMEGA are registered trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

ClockWorks, The Embedded Control Solutions Company, EtherSynch, Hyper Speed Control, HyperLight Load, IntelliMOS, mTouch, Precision Edge, and Quiet-Wire are registered trademarks of Microchip Technology Incorporated in the U.S.A. Adjacent Key Suppression, AKS, Analog-for-the-Digital Age, Any Capacitor, AnyIn, AnyOut, BodyCom, CodeGuard, CryptoAuthentication, CryptoAutomotive, CryptoCompanion, CryptoController, dsPICDEM, dsPICDEM.net, Dynamic Average Matching, DAM, ECAN, EtherGREEN, In-Circuit Serial Programming, ICSP, INICnet, Inter-Chip Connectivity, JitterBlocker, KleerNet, KleerNet logo, memBrain, Mindi, MiWi, motorBench, MPASM, MPF, MPLAB Certified logo, MPLIB, MPLINK, MultiTRAK, NetDetach, Omniscient Code Generation, PICDEM, PICDEM.net, PICkit, PICtail, PowerSmart, PureSilicon, QMatrix, REAL ICE, Ripple Blocker, SAM-ICE, Serial Quad I/O, SMART-I.S., SQI, SuperSwitcher, SuperSwitcher II, Total Endurance, TSHARC, USBCheck, VariSense, ViewSpan, WiperLock, Wireless DNA, and ZENA are trademarks of Microchip Technology Incorporated in the U.S.A. and other

SQTP is a service mark of Microchip Technology Incorporated in the U.S.A.

Silicon Storage Technology is a registered trademark of Microchip Technology Inc. in other countries.

GestIC is a registered trademark of Microchip Technology Germany II GmbH & Co. KG, a subsidiary of Microchip Technology Inc., in other countries.

All other trademarks mentioned herein are property of their respective companies.

© 2018, Microchip Technology Incorporated, All Rights Reserved. ISBN: 978-1-5224-4825-9



## Worldwide Sales and Service

#### **AMERICAS**

**Corporate Office** 

2355 West Chandler Blvd. Chandler, AZ 85224-6199 Tel: 480-792-7200

Fax: 480-792-7277 Technical Support:

http://www.microchip.com/ support

Web Address:

www.microchip.com

Atlanta

Duluth, GA Tel: 678-957-9614 Fax: 678-957-1455

**Austin, TX** Tel: 512-257-3370

**Boston** 

Westborough, MA Tel: 774-760-0087 Fax: 774-760-0088

Chicago Itasca. IL

Tel: 630-285-0071 Fax: 630-285-0075

**Dallas** Addison, TX

Tel: 972-818-7423 Fax: 972-818-2924

Detroit

Novi, MI

Tel: 248-848-4000

Houston, TX Tel: 281-894-5983

Indianapolis

Noblesville, IN Tel: 317-773-8323 Fax: 317-773-5453 Tel: 317-536-2380

Los Angeles

Mission Viejo, CA Tel: 949-462-9523 Fax: 949-462-9608 Tel: 951-273-7800

**Raleigh, NC** Tel: 919-844-7510

New York, NY Tel: 631-435-6000

**San Jose, CA** Tel: 408-735-9110 Tel: 408-436-4270

**Canada - Toronto** Tel: 905-695-1980 Fax: 905-695-2078

#### ASIA/PACIFIC

Australia - Sydney Tel: 61-2-9868-6733

**China - Beijing** Tel: 86-10-8569-7000

**China - Chengdu** Tel: 86-28-8665-5511

China - Chongqing Tel: 86-23-8980-9588

**China - Dongguan** Tel: 86-769-8702-9880

China - Guangzhou Tel: 86-20-8755-8029

**China - Hangzhou** Tel: 86-571-8792-8115

China - Hong Kong SAR Tel: 852-2943-5100

China - Nanjing

Tel: 86-25-8473-2460 **China - Qingdao** Tel: 86-532-8502-7355

China - Shanghai Tel: 86-21-3326-8000

**China - Shenyang** Tel: 86-24-2334-2829

**China - Shenzhen** Tel: 86-755-8864-2200

**China - Suzhou** Tel: 86-186-6233-1526

China - Wuhan

Tel: 86-27-5980-5300 China - Xian

Tel: 86-29-8833-7252

**China - Xiamen** Tel: 86-592-2388138

**China - Zhuhai** Tel: 86-756-3210040

#### ASIA/PACIFIC

India - Bangalore Tel: 91-80-3090-4444

India - New Delhi Tel: 91-11-4160-8631

India - Pune

Tel: 91-20-4121-0141

**Japan - Osaka** Tel: 81-6-6152-7160

**Japan - Tokyo** Tel: 81-3-6880- 3770

**Korea - Daegu** Tel: 82-53-744-4301

Korea - Seoul Tel: 82-2-554-7200

Malaysia - Kuala Lumpur Tel: 60-3-7651-7906

Malaysia - Penang Tel: 60-4-227-8870

Philippines - Manila Tel: 63-2-634-9065

Singapore

Tel: 65-6334-8870

**Taiwan - Hsin Chu** Tel: 886-3-577-8366

Taiwan - Kaohsiung Tel: 886-7-213-7830

**Taiwan - Taipei** Tel: 886-2-2508-8600

Thailand - Bangkok Tel: 66-2-694-1351

Vietnam - Ho Chi Minh Tel: 84-28-5448-2100

#### **EUROPE**

Austria - Wels

Tel: 43-7242-2244-39 Fax: 43-7242-2244-393

**Denmark - Copenhagen** Tel: 45-4450-2828 Fax: 45-4485-2829

Finland - Espoo

Tel: 358-9-4520-820

France - Paris
Tel: 33-1-69-53-63-20
Fax: 33-1-69-30-90-79

**Germany - Garching** Tel: 49-8931-9700

**Germany - Haan** Tel: 49-2129-3766400

**Germany - Heilbronn** Tel: 49-7131-72400

Germany - Karlsruhe Tel: 49-721-625370

**Germany - Munich** Tel: 49-89-627-144-0 Fax: 49-89-627-144-44

**Germany - Rosenheim** Tel: 49-8031-354-560

Israel - Ra'anana Tel: 972-9-744-7705

Italy - Milan Tel: 39-0331-742611

Fax: 39-0331-466781 Italy - Padova

Tel: 39-049-7625286 **Netherlands - Drunen** Tel: 31-416-690399

Fax: 31-416-690340 **Norway - Trondheim** Tel: 47-7288-4388

**Poland - Warsaw** Tel: 48-22-3325737

Romania - Bucharest Tel: 40-21-407-87-50

**Spain - Madrid** Tel: 34-91-708-08-90 Fax: 34-91-708-08-91

**Sweden - Gothenberg** Tel: 46-31-704-60-40 **Sweden - Stockholm** Tel: 46-8-5090-4654

**UK - Wokingham** Tel: 44-118-921-5800 Fax: 44-118-921-5820