


Soldering Parameters


Reflow Condition		Pb – Free assembly
Pre Heat	-Temperature Min (T _{s(min)})	150°C
	-Temperature Max (T _{s(max)})	200°C
	-Time (Min to Max) (t _s)	60 - 180 seconds
Average Ramp-up Rate (Liquidus Temp (T_L) to peak)		5°C/second max.
$T_{S(max)}$ to T_L - Ramp-up Rate		5°C/second max.
Reflow	-Temperature (T _L) (Liquidus)	217°C
	-Temperature (t _L)	60 - 150 seconds
Peak Temperature (T _P)		260 ^{+0/-5} °C
Time within 5°C of actual peak Temperature (t _p)		20 - 40 seconds
Ramp-down Rate		5°C/second max.
Time 25°C to peak Temperature (T _p)		8 minutes max.
Do not exceed		260°C




Product Characteristics

Operating Temperature -55°C to 125°C

Dimensions



Part Numbering System



Example: 1.5 amp Fast-acting product is 0154<u>**01.5</u>DR**.</u>

1.5 amp Time-lag product is 0154**01.5**DRT.

(1 amp product shown above).

Packaging Quantity & Quantity **Packaging Specification** Option Packaging Code EIA RS-481-2 (IEC 60286-3, Reel Pack 1500 DR

part 3)

Additional Information







Disclaimer Notice - Information furnished is believed to be accurate and reliable. However, users should independently evaluate the suitability of and test each product selected for their own applications. Littelfuse products are not designed for, and may not be used in, all applications. Read complete Disclaimer Notice at: www.littelfuse.com/disclaimer-electronics